Building Schedule of Rates

For

CONSTRUCTION WORKS

OF

Government Buildings

B.S.R -2024

Department of Buildings

B.S.R. Workgroup Committee,
Dept. of Buildings,
" Sethsiripaya",
Battaramulla.

Contents

Page Nos.

A.	*INTRODUCTORY NOTES & ADDITIONS TO SPECIFICATIONS*		
	A.1	*INTRODUCTORY NOTES*	*A1-A3*
	A.2	*ADDITIONS TO SPECIFICATIONS*	*A4-A7*
B.	*PRICING PREAMBLES*		*B1-B16*
C.	*DEMOLITIONS*		*C1*
D.	*EXCAVATION & EARTHWORK*		*D1-D2*
F.	*CONCRETE WORK*		*F1-F4*
G.	*MASONRY WORK*		*G1-G2*
H.	*WATER PROOFING*		*H1*
J.	*STRUCTURAL METAL WORK*		*J1*
K.	*METAL WORK*		*K1-K6*
L.	*WOOD WORK*		*L1-L11*
	L1	*CARPENTRY-STRUCTURAL TIMBER WORK-(ROOF)*	*L1*
	L2	*JOINERY (WALLS)*	*L2-L6*
	L3	*IRON MONGERY*	*L7-L11*
M.	*CLADDING*		*M1*
N.	*PARTITION LINING / SUSPENDED CEILING*		*N1-N6*
P.	*ROOF COVERING*		*P1-P3*
Q.	*PLUMBING / SANITORY INSTALLATION*		*Q1-Q21*
R.	*MECHANICAL INSTALLATIONS TRANSPORT SYSTEMS*		*R1-R7*
S.	*ELECTRICAL INSTALLATION*		*S1-S11*
T.	*FINISHING & FLOORING*		*T1-T 7*
	T1	*PLASTERER*	*T1-T2*
	T2	*PAVIOR*	*T3-T7*
U.	*GLAZING*		*U1*
V.	*PAINTING & DECORATING*		*V1-V4*
W.	*DRAINAGE SYSTEMS*		*W1-W3*
X.	*EXTERNAL WORK*		*X1-X2*

DUB Build Future .... Restore Past

A. INTRODUCTORY NOTES & ADDITIONS TO SPECIFICATIONS

A.1 INTRODUCTORY NOTES

A.1.1 Trade Names ;

Where trade names , brands and / or catalogue numbers are referred to sole preference to any material or equipment is not intended . Any other material or equipment may be used, provided that the characteristics of type, quality,appearance, finish, method of construction and / or performance is not less than what is specified and provided, and prior approval is obtained.

A.1.2 Based Standard

This BSR has been prepared generally in accordance with the principles of "Method of Measurement of Building Works(First Revision) , Sri Lanka Standard 573:1999"

A.1.3 Analysis for Basic Rates

The Material and Labour component required for the various items of work including the minimal plant required for same is detailed in the analysis of the Basic Rates which consist of the following

(a) Materials

The quantities of material required for the items are computed from known data and experience. Their total value is calculated on the basis of current prices at source of supply. Unless otherwise stated wastage is allowed in the norms.

(b) Transport

This component provides for the cost of transport of material from sources of supply to the sites of work. This component is usually added to the material cost.

(C) Labour

The labour wages are as approved by the Government from time to time and on the basis of an 8 hour working day.

Rates used in this B.S.R. are as follows.

Category	Rate/ Per day
Unskilled Labour	2250
Semi Skilled Labour	2500
Skilled Labour	2750
Special Skilled Labour	3000

(d) Plant

This component provides for the minimum plant required for the item of work. The cost of tools is provided for in the Overheads component.

(e) Basic Cost

The basic cost is the sum of the costs of items **(a),(b),(c)**and **(d)** above.

A.1.4 Preliminaries

Preliminaries for building works should be claimed under guide lines of ICTAD Publication No. ICTAD/ID/04 Second Edition - June 2009

A.1.5 Overheads and Profit factors

These rates dose not include any overhead and profit factors and VAT etc. Hence it should be included whenever necessry according to the nature of the contract considering the usage of priliminaries as mentioned in the clause A1.4 above. However, Social Security Contribution Levy (SSCL) tax included to rates.

A.1.6 Allowances for lifting work

Allowances to be made in the rates for lifting respect of work on upper floors.

In the analysis of the various items of work (other than specified) in the following pages, the rates refer to work on the ground floor.

(a). Ground and 3 upper floors

To these rates the percentage (of the ground floor rates) indicated in table below should be added to obtain the rates applicable to the 1st, 2nd and 3rd floors. This B.S.R is limited to work on the ground and 3 upper floors only.

Serial No.	Item	Ground to 1st floor %	Ground to 2nd floor %	Ground to 3rd floor %
1	Concrete	3	5	7
2	9" Brickwork (Area wise)	5	7	9
3	9" Brickwork (Volume wise)	5	7	10
4	4 1/2" Brickwork	5	7	10
5	Steel reinforcement	2.5	4.5	5
6	Plastering	5	10	15
7	Floor Tiling	2	4	6
8	Wall Tilling	2	4	6
9	Roof Calicut tile	3	6	9
10	Roof asbestos	3	5	7
11	Ceiling work	3	5	7
12	Painting	3	6	9

(b).Fourth floor and above

If a building has more than four floors or when the contract period is compressed to a few months, then it will be necessary to allow for the use of heavy machinery such as tower crane, mobile cranes, dumpers loaders, batching plant for mixing of concrete ,bins for the storage of concrete material etc.and also for the employment of contract managers and additional staff.

The cost of such items of work will not be accommodated within the general ' Mark-Up' and will have to be provided for in separate items such as preliminaries to the contract.

This BSR is for Construction works only

A.1.7 Earth work and landscaping

Soils met within excavation have been classified as follows.

1. Soft /Loose soil
2. Ordinary soil
3. Hard /Dense soil
4. Mud/ wet clay
5. Soft disintegrated rock(i.e. rock not requiring blasting)
6. Hard rock - a) Where blasting is approved
   b) Where blasting is prohibited

The classification of soil in note 1 above and the analysis provide for the different type of soil will help the estimator in arriving at the actual of excavation, for which he will have to allow in his estimate.

Under note 1(6) b Hard rock ,an analysis is provided for removing Hard Rock met with in foundation excavations where blasting is prohibited or cannot be done, like in built up areas where blasting can cause damage to adjoining buildings

For excavation beyond the depth of 5' 0" an additional unskilled laborer should be added for every additional depth of 5' 0" or part thereof for each cube of excavation beyond the original 5' 0" depth

DOB Build Future ..... Restore Past

This BSR is for Construction works only

A.2 ADDITIONS TO SPECIFICATIONS

A.2.1 Timber :

Unless otherwise specified in the respective Trades / Sections , the timber for all trades shall be as specified in Carpentry and Joinery.

All timbers under exceptional Circumstances, any equivalent timber to the given Species may be used with the approval of the Engineer.

(Group-1): Door, Window and Fanlight Frames

Category A	Path kela	Kon	Milla	Ketakala	Tulang
	Halmilla	Mee	Hulanhik	Wewarana	Valdel.
	Kohomba	Jak	Kohomba		
Category B	Microcoris	Grandis			

(Group-2): Door , Window and Fanlight Sashes , Cupboards, Counters and Shelving

Category A	Hulanhik	Tulan	Halmilla	Sooriya mara
	Kohomba	Wewarana		
Category B	Ginisapu			

(Group-3): Roof Framework

Category A	Madan	Milla	Velang	Wewarana	Tulang
	Mee	Jak	Micro	Kolon	Etathimbiri
	Dun				
Category B	Domba	Grandis	Saligna	Ginisapu	Sooriya mara

(Group-4): Ceiling Framework and Partitions

Category A	Velang	Dun	Milla	Ketakala	Tulang
	Halmilla	Mee	Hulanhik	Wewarana	Valdel.
	Kohomba	Etathimbiri	Teak	Jak	
Category B	Domba	Grandis	Cyprus	Saligna	Boron treated pinus

(Group-5): Valance Board and Valley Boarding

Category A	Kolon	Tulang	Val Del	Kohomba	Sooriya mara
	Panakka	Jak	Hulanhik	Wewarana	
Category B	Ginisapu	Toona	Dewata		

(Group-6): Beadings :

Alstonia	Mahogany	Lunumidella

(Group-7): Special Timber

Jak	Teak	Ebony	Nadun	Satin

Source: Selection of timber species- State Timber Coorporation.

This BSR is for Construction works only

A.2.2 Aluminium Panels

All Aluminium sections shall be fully treated extruded Aluminium alloy sections in accordance with BS 1470,1471, 1473, 1474 or latest relevant EN standed

All Aluminium sections to be locally extruded

All Aluminium sections shall present clear, straight and sharply defined lines. They shall be free from defects, impairing strength, appearance and durability.

Finish

All members shall be finished either by

(i) Anodizing or

(ii) Powder coating (What ever specified in Aluminium Items)

Anodizing -Exposed surface of all members shall be anodized using two steps. Anodizing process to an anodic thickness of not less than 10-15 microns and shall be free of any defects.

Powder coating

Powder coating shall be carried out using polyester coating with proper and appropriate pre- treatment to a thickness of not less than 60-80 microns, measured on all significant surfaces.

Screws and Hardware Items

Concealed screws, nuts, bolts, rivets and other fastening devices shall be of Aluminium, non-magnetic stainless steel or other approved corrosive resistant materials. If visible, they shall blend with the finish of the framing Aluminium sections.

Glass

Glazing shall be minimum of 5mm thick clear float glass. Glass shall be secured at all edges with compression gaskets and glazing beads. When fixing glass, all glazing sealant shall be carefully applied and cleaned off properly.

Workmanship

The fabrication and installation of all Aluminium work must be carried out by specialist tradesmen.

All dimensions shown on the drawings and the shop drawings must be verified by actual site measurement before fabrication and installation. Any cutting to enlarge the size of openings and approved practical method to fill the excess void behind frames required after installation shall be executed by the Contractor at his own expense.

All Aluminium members shall be factory fabricated to the best standard of workmanship under experienced factory supervision and control.

Materials, method of fabrication, assembly, installation, fastenings, supports, braces, operating parts and the like shall be in accordance with the approved shop drawings.

This BSR is for Construction works only

All joints in frames at corners, junctions and intersections shall be mechanically jointed and be such that when assembled they are as strong and rigid as adjoining sections. Due care must be taken to ensure that all joints are water tight and leak-proof. Joint lines should not be visible.

Provisions must be made for expansion and contraction in horizontal and vertical members which are exposed to the weather or environments. Any distortion of members or any glass cracked or broken as a result of inadequate provisions must be rectified by the Contractor at his own expenses.

All works shall be securely installed and anchored in position, set plumb, square and level in accurate alignment with other work, all in accordance with the approved shop drawings to the Engineer's satisfaction.(The allowable tolerance in terms of specified dimensions shall be plus/minus 1.5mm.)

Submissions

The Contractor shall submit shop drawings showing the following information where appropriate to the item ;

layout (Sectional plan and elevation) of complete assembly

- full size sections of members
- methods of assembly
- methods of glazing
- methods of installation, including fixings caulking, flashing
- provisions for vertical and horizontal expansion
- junctions and trim to adjoining surfaces
- fittings and accessories

The Contractor shall submit certificates from the Aluminium manufacture and/or an approved testing laboratory which attest that the coating thickness offered is as specified.

Doors & Windows

Frame and /or sash sections shall be of extruded EN-AW 6063-T5 Aluminium Alloy

Aluminium Louvers

Fixed louvers shall be of the weather proof type, suitable for overcoming water carried-over by wind and the fixed louvers shall have free areas of not less than 50%

The Contractor shall provide a guarantee in respect of the weatherproof properties of the fixed louvers.

All powder coatings shall match the windows. Panels shall be so constructed as to be completely weather proof at junctions with adjoin structures .

This BSR is for Construction works only

Partitions

The frames shall be properly machined to permit easy assembly and to form weather-tight joints when caulked.

Partition members shall be 76mm in depth and the thickness of 1.2mm.

Following dimensions are applied for the frame members of each assembly units

Assembly Unit	Minimum Member Depth (mm)	Minimum Member Thickness (mm)
Casement Window,Fanlight	70	1.5
Sliding door/Window	80	1.5
Door	100	1.5
Fixed glass Window	100	1.5

Rates shall include for all necessary hinges, screws, rubber beadings, Skelton bolts, Aluminium louvers, pinhead stickers, etc.(Door Locks ,Door Handles,Door closers paid separately)

Locks- (Union or equivalent)

Hinges-(Union or equivalent)

Handle-Grade 304 stainless steel

***Reffer notes 7.(d), Under pricing preambles*

Build Future ..... Restore Past

B. PRICING PREAMBLES

1. GENERAL

a. The Bidder shall read and be conversant with the full description of workmanship and materials as described in this document under section (A) ,Pricing preambles, notes on trades in BSR and ICTAD Specification for the respective items of work/ trades prior to the preparation of the Bid.

b. The Bidder shall refer to the relevant Clauses of Pricing Preamble when pricing composite item of works.

c. The rate for each item must be comprehensive and must include for complying in all respects with the requirements of the aforesaid specifications, these Pricing Preambles, cover all the obligations under the Contract, and all matters and things necessary for the proper construction, completion and maintenance of the Works. No claim for additional payment shall be allowed for any error or misunderstanding by the Contractor of the work involved.

d. The rate for each item shall also include for all the following -

i. Labour and all connected costs ;

ii. Materials and goods including all connected costs;

iii. Preparatory works and setting out of particular item ;

iv. Complying with regulations of the Municipal Council and/or any other relevant authority under which particular item of work is to be executed unless otherwise included in the Preliminaries ;

v. Fitting and fixing materials and goods in position, including hoisting to any height or lowering to any depth and all temporary works, equipment and small tools ;

vi. Plant and equipment unless otherwise included in Preliminaries ;

vii. Handling of materials and working in situation where there is very restricted working space or no working space ;

viii. Square cutting and Waste of materials ;

ix. Forming of ends, angles, miters and junctions between straight and raking or curved work ;

x. Protecting and cleaning ;

xi. All other incidental works and necessary works which are not described in the B.O.Q. but described in the aforesaid specifications and or shown in the drawings for the proper completion of the relevant item of work ;

xii. Establishment charges and overheads(not included in preliminaries or anywhere in the Bill Of Quantities), and profits.

e. In addition to above, the rates for items of work in Substructure shall include for the works at depths extending below ground water table where applicable including excavation under water,removal and disposal of mud and sand and preparation of place to a condition suitable for proper execution of the works.

2. EXCAVATION AND EARTHWORK

a. All works under this section are measured net and no working space is allowed.

b. The Contractor shall be responsible for the design and execution of the excavation method which is subject to scrutiny by the Engineer. However, scrutiny by the Engineer shall not in any way relieve the contractor of his responsibilities and duty of care.

c. Existing ground levels shown in the Drawings have been taken at the surface of the ground, with no particular differentiation to indicate buried foundations, pavings etc.

d. The Contractor shall note that the rate for compacted earth fill and granular fill, stone, gravel and sand beds shall include for imported materials or materials from borrow areas.

e. Rates for Excavation & Earthwork shall include for -

i. Accepting site as found and preparing to condition suitable for proper execution of the Works

ii. Excavating by whatever means are necessary including excavation done manually or by machine in any type of ground including ground with boulders (except rock) and excavation around existing RCC. bored piles and jet grout piles ;

iii. Trimming sides, keeping clean and consolidating bottom of basement, sumps, pits and trenches ;

iv. Backfilling and disposal of surplus excavated materials as specified and directed ;

v. Any necessary additional works required due to

a. Working space required by the Contractor ;
b. Earthworks supports ;
c. Formwork ;

vi. Any additional trimming or appropriate back- filling to provide specified or approved formations and profiles necessitated by the uneven excavation of the earth, unless otherwise measured separately ;

f. Rates for compacted earth fill, granular fill and gravel and sand beds shall include for finishing sub-grade to slopes and falls, depositing in layers, leveling, blinding, and machine or hand-packing to form vertical or battered or level faces, and for forming sinking where required under floor slabs or sub-floor layers.

This BSR is for Construction works only

g. Rates for approved damp-proof membrane shall include for laps, and straight, raking and circular cutting, and for notching around all obstructions.

3. CONCRETE WORK

a. Rates for concrete work shall include for -

i. Mixing as per specification, depositing, handling, hoisting and placing at any height or depth ;

ii. In case of readymix concrete, transporting, admixtures, handling, pumping/hoisting and placing at any height or depth ;

iii. Packing and tamping around reinforcement, including vibrating ;

iv. Contractor's designed kickers, construction joints and sealents ;

v. Finishing to slopes and falls, and preparing surface ready for screeds or paving, where necessary, including cutting to sizes and temporary supports to form necessary grooves ;

vi. Curing ;

vii. Preparation of ground surface, grading to slope and falls, if any, and machine or hand packing to form vertical or battered or level surface and all necessary formwork to edges of blinding concrete in case of pile caps ground slab/ramps/beams.

FORMWORK:

a. Formwork for similar concrete members are measured together irrespective of the height or depth and the shape or form.

b. Extra-over rate for a particular type of high quality formwork should be applied only for the areas of formwork which requires such high quality type formwork as specified.

c. Formwork shall be properly designed and strictly as described in the specifications for the particular type of concrete surface finish and it should be sufficiently strong and grout tight.

d. Faces of Jet grouting piles, masonry and concrete work which will be formed or used as formwork shall not be measured as formwork and no payment shall be made for same.

e. <u>Rate for formwork shall include for -</u>

i. Fabricating setting up and erection at any height or depth ;

ii. Strutting, supporting through lower floors and supporting at any level, including additional propping, strutting and supporting decks ;

This BSR is for Construction works only

iii. Coating with shuttering oil and or lining ;

iv. Easing, striking and removing ;

v. Cleaning, preparing for reuse ;

vi. Removal when no longer required ;

vii. Props, stays, struts, wedges, bolts, incidental items and materials such as nails, screws anchors hooks etc ;

viii. All overlaps and passing at angles ;

ix. Labour at intersections and narrow widths ;

x. Rubbing down and making concrete surface good after removal of formwork ;

xi. All fillets, to form grooves, rebates and throats, splays or chamfers, raking and circular cutting, and cutting around all pipes, sleeves, conduits, ducting, metal sections and fittings ;

xii. Providing samples as required by the Engineer of the different formed finishes specified.

REINFORCEMENT:

a. Standard length of reinforcing bar for the purpose of measurement shall be 6.0 m. or 12.0 m
i.

ii. Payment for bar reinforcement shall be to be nearest Kilogram.

b. Rates for reinforcement shall include for -

i. Rolling margin ;

ii. Preparation of bar bending schedules ;

iii. Straightening as required and cleaning of bars ;

iv. Cutting, bending and binding ;

v. Hoisting and placing in position at any height or depth ;

vi. Binding wires, and cover blocks.

vii. Necessary spacers. (inevitable laps & chairs paid separately)

viii. Aligning and supporting in position during concreting.

This BSR is for Construction works only

PRECAST CONCRETE WORKS:

a. Rates for precast concrete works shall include for -

i. Moulds and for formwork with the required finish to all exposed surfaces in accordance with the specifications, hacking surfaces to form key for rendering etc, and hoisting to any height or depth including providing any lifting holes or other devices to the approval of the Engineer,building in, including bedding and jointing in mortar as required, and any necessary strutting and supporting.

ii. The requirements of the Pricing Preamble clauses which refer to Concrete Work,Reinforcement and Formwork.

iii. Loading, transporting to Site, unloading, handling and stacking.

iv. Hoisting and fixing in position at any height or depth.

4. MASONRY WORK

a. In the calculation of the volumes of brick wall which are not multiples of the size of standard bricks, the thickness of such walls shall be taken as the thickness of full bricks from which they can be cut. The same principle of calculation of volume shall be used for all brickwork of which the cross-sectional dimensions are not multiple of brick sizes.

b. Rates for brickwork/Block work shall include for -

i. Plumbing, angles,straight cutting,forming rebates,reveals and raking out joints for plastering;

ii. Splay cutting, rough cutting, fair cutting, forming chases or grooves for slabs, partitions,staircases, roofs and the like, bonding ends of walls, building in or cutting and pinning in and making goods on lintels, timber and steel works ;

iii. Building at any level or height of slabs or beams, additional labour in kerbs, isolated and attached piers, all cutting, bonding at angles and intersections, building into or against adjacent work, wedging and pinning up to soffits;

iv. Supplying and fixing metal clamps, Galvanized, steel boundary ties, and brick reinforcement etc;

v. Necessary cutting required in walls which are not multiples of brick size ;

vi. Preparing existing walls for raising and pinning new brickwork ;

vii. Bonding new walls to concrete faces and old walls where necessary, and materials to be used for such bonding.

Damp Proof Course

a. Rates for Damp Proof Course shall include for -

i. Necessary leveling screed and trimming top of rubble/block/brick plinth wall ;

ii. Fair edges, rounded edges, drips and arises, angle fillets ;

iii. Turning nibs of asphalt into grooves ;

iv. Cutting to line and jointing new to old asphalt.

STONE WORK

a **Generally**

Stones are defined as consolidated aggregates of one or more minerals and includes all types of rock used in the construction industry.

b **Rubble work**

Rubble Stone masonry built of stones either irregular in shape as quarried or shaved and only hammer dressed and having comparatively thick joints.

Rates for Rubble Masonry shall include for -

i. All joggles, cramps, dowels, ties, templates ;

ii. Plumbing, angles, fair returns, setting, jointing, eaves filling, pointing and fixing in position, hoisting to any given height or depth ;

iii. Bonding ends of walls, rough cutting and fair cutting ;

iv. Leveling up in walling for Damp Proof Courses, sills, thresholds, string courses, copings and the like ;

v. Forming straight vertical joints next to dressings, panels, brickwork etc ;

vi. Forming openings and dressed margins ;

vii. Forming chases, throats, rebates, margin flutes, sinking, chamfered and rounded edges, and all labour connected therewith.

c **Ashlar Stone masonry using dressed stone blocks of given dimensions having faces perpendicular to each other and laid in courses.**

Rates for stone work shall include for:-

i. Extra material for curved work
ii. All rough and fair cutting
iii. Dressing

iv. Forming rough and fair grooves, throats, mortices, chases, rebates, holes, stops and mitres.

This BSR is for Construction works only

v. Raking out joints for key
vi. Labours in eaves filling
vii. Dressed margins to rubble work
iix. Leveling uncoursed work
ix. Rough and fair square cutting
x. Centering
xi. Wedging up and pinning to concrete soffits and steel work
xii. Building in frames, flashing, damp proof courses including filling hollows of corner blocks with mortar
xiii. Building in ties, lugs, plates, lintels, pipe sleeves, inserts, switch boxes and the like. As the work proceeds.

d **Stone Veneering work (Face rubble work)**

i. Stone lining upto 80mm along planes parallel to natural bed. The natural bed may be masonry of brickwork or rubbel work, concrete surface.
ii. Stones cut into slabs of required thickness.
iii. Dressed to very close tolerances.

5. WATER PROOFING

a. Rates for Water Proofing shall include for ;

i. For necessary leveling and trimming top of rubble/block/brick plinth wall ;

ii. Fair edges, rounded edges, drips and arises, angle fillets ;

iii. Forming internal and external angles, bonding bricks/blocks and the like ;

iv. Turning nibs of asphalt into grooves and asphalting around brackets ;

v. Cutting to line and jointing new to old asphalt ;

vi. Temporary screeds, ground and rules.

6. STRUCTURAL STEELWORK

a. Rate shall include for :

All shop fabrication work, including cutting, drilling, bolting, riveting, welding, grinding, delivering, unloading, hoisting, erecting and fixing.

7. METAL WORKS

a. All Aluminium sections shall be fully treated extruded Aluminium alloy sections in accordance with BS 1470,1471, 1473, 1474 or latest relevant EN Standed

b. Contractor to prepare shop drawings for approval of the Engineer.

c. Rates for Metal Work shall include for anchors, screws, dissimilar metals and providing thermal movement and the preamble clauses for Structural Steel Work where relevant and they shall apply equally to relevant items of this section.

Aluminum components

d. Fabrication & fixing of Aluminum components shall be carried out by experienced tradesman.The Contractor shall furnish particulars of Aluminum fabricator through the engineer for his approval.

The Contractor will be required to furnish a guarantee on material and workmanship for a period of 8 years from the date of handing over of Works in the form required by the employer, binding the Aluminum manufacturer and the Contractor jointly and severally

Material: As described under section A (Additions to specifications)

8. ROOF COVERING AND ROOF PLUMBING

a. Rates for roof covering and roof plumbing shall include for :

i. Hoisting, placing and fixing in position ;

ii. Straight cutting, raking cutting, circular cutting, notching, and working around obstructions and waste ;

iii. Nails, screws and the like ;

iv. Drilling and making holes or opening and the like;

b. Rates for flashings shall include for the following in addition to the requirement of "a" above -

i. Bending and cutting to required shape and forming roll edges ;

ii. Angles, edges and ends ;

iii. Notching over roofing ribs or dressing into roof cover/concrete as the case may be ;

iv. Forming and dressing into or around walls at obstructions and the like ;

v. Stepping up ;

vi. Sealing with sealant materials.

This BSR is for Construction works only

9. CARPENTRY(Roof and ceiling frame)

a. Sizes of all timber given are finished sizes.

b. All timber shall be well seasoned and treated against insect and termite attack before fixing in position

c. Rates for carpentry shall include for -

i. Any type of cutting required, sawing, notching, drilling, trimming, framing, jointing, splayed edges and the like, hoisting and fixing in position with nails, spikes, plugs, screws, and gluing and priming to joints and ends ;

ii. Forming splayed edge, grooves, chamfers, scribed and rounded edge, beveling,molding and the like ;

iii. Plugging, wedging, nuts and washers with bolts,sprockets and pins and the like ;

iv. Nogging or solid bridging, cut between studs or joints for structural timber.

v. Rebating, singings, grooving, mortising ;

vi. Additional timber lengths required for carpentry jointing ;

vii. Protection and keeping clean for staining, polishing or painting where applicable ;

d. Rates for roof decking shall include for machine sanding, protecting and preparing in addition to the requirements c above.

e. Rates for walls and ceiling lining shall include for jointing and fixing to walls/ ceiling/ eaves etc. all cover and joint strips, in addition to the requirements c above.

f. Rates for timber paneling/wall lining shall include for cover moldings, sills, stiles and head moldings to openings as relevant.

10. JOINERY

a. Sizes of all timber given are finished sizes.

b. All timber shall be well seasoned and treated against insect and termite attack before fixing.

c. Timber used for joinery works shall be well seasoned well treated and in one species of special class timber recommended for the particular class of Joinery works as specified in the Specification.

d. Rates for Joinery shall include for -

i. Any type of cutting required, sawing, notching, drilling, trimming, planing, forming and jointing and the like, fixing in position complete with nails, spikes, plugs, screws and gluing and priming to joints and ends ;

This BSR is for Construction works only

ii. Forming splayed and tongued edges, rebates mortises, grooves, chamfers, scribed and rounded edges, beveling, moulding, margin and the like and rounded corners, sinkings ;

iii. Working to stated sizes, for all short lengths making mitres, joints and ends ;

iv. Necessary bolts, dowels metal clips, anchors, grips and fixing joinery ;

v. Glueing, dowelling, plugging, wedging pining and the like ;

vi. Punching heads and filling with approved filler if nails or pins are used for fixing ;

vii. Countersinking and filling heads with approved filler, if brass screws are used for fixing ;

viii. Painting rebates of frames before fixing glass ;

ix. Bedding in cement mortar filling and hanging to frame lining ;

x. Keeping clean for staining, polishing or painting;

xi. Painting, Laquering or Varnishing as specified.

e. Preambles for Glazing section and a, b and c under Painting and Decorating section shall equally apply to Joinery works.

f. Ironmongary

i. All cutting, fitting, sinking, boring, mortising ;

ii. Matching screws for ironmongery

iii. Removing during decoration, refixing after decoration, leaving oil and in proper working order on completion and supplying and labeling all keys and handing over to Employer.

11. WALL,FLOOR AND CEILING FINISHES

a. i. All works under this trade shall be measured after deduction for voids,openings, doors and windows

ii. All other small quantities/panels/narrow widths/ arises/ reveals/ angles/ ends/short lengths including those of tiling work on door and window jambs and reveals are measured together with the respective tiling item and labour in such work shall be included in the rate for the main finishing item and they shall not be measured/paid separately.

b. <u>Rates for wall, floor, ceiling finishings and wall floor screed and bedding shall include for -</u>

i. All temporary rules, screeds, templates and supports, curing and cleaning off on completion and exact thickness required to finish ;

ii. Caulked joints and making good and cutting around bolts, pipes conduits,sleeves, ducting, fittings, sections, obstructions and the like ;

iii. Tamping and compacting ;

iv. Raking out joints of new brickwork/Block work or hacking concrete to form key, including brushing, cleaning off and dampening ;

v. Forming internal and external angles and arises ;

vi. Any extra thickness required to finish to true levels ;

vii. Any additional dubbing out required to plastered surfaces of brickwork and to the finished surface of concrete to obtain the requisite standard of finish ;

viii. Samples to be submitted for the approval of the Engineer.

c. Rates for tile slab or block finishing to floor and wall shall also include for the following in addition to the above -

i. Straight raking and circular cutting ;

ii. Dubbing out or packing to concrete surface to correct deviations within specified tolerance ;

iii. Laying or finishing to falls or cross falls ;

iv. Expansion joints at perimeter and between bays where required in case of floor tile paving ;

v. Sand blasting, cleaning, waxing and appropriate floor finishings.

d. Rates for ceiling lining shall include for the following

i. Working to sides and soffits of attached or isolated beams and soffit of staircases where relevant;

ii. Additional forming required for lighting and air-conditioning grills ;

iii. Straight, raking and circular cutting ;

iv. Neoprene sealing for air tightness around hatches if any ;

v. Matching edges where cutting occurs and for filling the heads of fixings with approved filler where relevant ;

vi. Painted mild steel hanging rods.

This BSR is for Construction works only

12. GLAZING

a. Type of Glazing shall be as specified.

i.

ii. Thickness of glazing shall be as per the design of the approved specialist contractor who will be engaged by the Contractor. However, the minimum thickness shall be 6mm.

b. Rates for Glazing shall include for -

i. Glazing, fixing, bedding priming and panel pins and other materials and labour for same and cutting to size ;

ii. Templates, straight cutting, circular cutting, grinding edges or special type of edges required and sand blasting ;

iii. Glazing beads, washlether or neoprene strip, glazing sealant, weather stripping, caulking joint silicone joint ;

iv. Replacing cracked or broken glass ;

v. Making holes where necessary ;

vi. Samples to be submitted for the approval of the Engineer.

13. PAINTING AND DECORATING

Note
Colour and the quality of all paint and other painting materials shall be approved by the Engineer prior to use.

a. Rates for painting shall include for -

i. Preparation of surfaces, cleaning down, smoothing, etc ;

ii. Submission of samples for the approval of the Engineer ;

iii. Protection of floors, walls and fittings etc ;

iv. Working to returns, painting in any colour, multi- colour works, cutting into line at junctions of different colours at angles or plain surfaces, painting in small quantities ;

v. Cleaning down upon completion

b. Rates for work to isolated general surfaces shall include for working on door frames, linings,window subframes (where of a differing material to the window), skirting, rails, architrave's, bars,posts, balusters and the like.

c. Rates for work to glazed general surfaces, glazed windows and the like (measured both sides,flat over glass, irrespective of size and panes) shall include for work to edges and glazing rebates, returns and moldings of frames, mullions, transoms, architaves and the like.

This BSR is for Construction works only

d. Rates for work to pipes and conduits (which shall include trunking, ducting and the like) shall include for all work on hangers, supports, brackets and the like.

14. PLUMBING

a. <u>The rates for Plumbing shall include for :</u>

i. Refer specifications for full description of materials and workmanship.

ii. Screws, nails, sockets, connectors, backnuts, nipples, and standard pipe fixing or supporting clips, saddles, brackets straps, screws, nails, solder rivets connectors, flanges pipe sleeves, brackets, made bend holder bats and the like.

iii. Short lengths, joints connections and couplers in running length.

iv. Sealing, fixing and support with holder bats or pipe clips cut and pinned built in wall or slabs.

v. Plugging screwing to walls or ceiling

vi. All laps, straight cutting and waste

vii. The fittings including bends, tees, collars, reducers elbows, valve sockets, junctions, caps and the like for pipe less than or equal 50mm dia pipe.

viii. Jointing compound, solvent cement and incidental materials and labour.

ix. Connecting pipes to sanitary fixtures and appliances.

x. Standard and special pipe fixing arrangement where necessary fittings, supporting clips,saddles,brackets, holder bats straps etc.

xi. All builders works such as chasing and forming holes through brick work/ blockwork/ foundations and concrete slabs beams columns floor slabs manholes and like and making good all damages.

xii. Testing and disaffection after completion.

b. <u>Rates for sanitary fittings shall include for</u>

i. Fittings such as taps, waste water outlet, flushing cistern, internal overflows and the like and supporting brackets, incidental materials for fixing.

ii. Assembling, jointing together, fixing components parts and jointing to pipes including necessary coupling and for leaving perfectly clean undamaged and in perfect working order as on completion.

c. Jointing and or connecting pipes to sanitary fittings.

This BSR is for Construction works only

Any special water supply and drainage fittings such as bends, tees, reducers etc. unless otherwise specified separately in the Bill of Quantities, shall be deemed to have been included in the relevant items and such items should accordingly be rated to include for such specials etc. and for any extra work involved and the satisfactory completion of such items.

Where pipes pass through walls or slabs these shall be wrapped with a layer of inert materials. For pipes exceeding 50 mm dia sleeve pipes shall be used for the full thickness of slabs, walls or beams through which the pipes pass.

DRAINAGE WORK

a. The provisions and the clauses of precedence trades shall equally apply to relevant item of this trade.

b. The rates for trench excavation for pipes shall include for depending and widening the trench as necessary to enable the barrels of pipes of rest on firm and to facilitate jointing.

c. The rates for rock excavation in trench excavations shall include for importing selected materials to replace any excavated rock which is unsuitable for back filling and for all additional rock excavation and appropriate filling beyond the maximum measurable in accordance with the specification.

d. The rates for concrete beds and surrounds to pipes shall include for flexible joints and any necessary formwork where required by the specification.

15. ELECTRICAL INSTALLATIONS

a. The execution of Electrical Installation shall every respect comply with the current Regulations of the Institute of Electrical Engineers, London, requirements of Ceylon Electricity Board and the area Authority.

b. The rates for equipment and control area, distribution boards, meters, switches, fuses, etc. shall include for connecting up, fixings and supports for the complete installation and for suitable mounting boards, frames, supports, housings and cabinets where required.

c. The rates for cables, tape, bus-bar trunking etc. (except where included in sub circuits or electrical points) and the like shall include for joints in the running length, all allowances for sagging snaking, for drawings through conduits,laying in trunking of surface fixing where retired with cable supports, clears, hangers, channels, insulators and the like.

d. i. The rates for cables and the like laid in benches shall include for drawing through conduits or ducts where required.

ii. The rates for cable terminations shall include for all connections point boxes, insulating and jointing materials, cable terminations glands, lock nuts, bushes and the like.

This BSR is for Construction works only

e. i. The rates for conduits trunking cable tray etc. (except where included in sub circuits of electrical points) and the like shall include for all short lengths, joints and couplers in the running length, and for all fixings and supports with approved saddles, crumpets, clips and the like cut and pinned, built-in or plugged and screwed to walls or ceilings including chasing brick work, block work, concrete slab beams walls columns and the like and make good.

ii. The rates for conduits and the like shall include for all bends, tees, socket and the like,cutting, screwing, threading, jointing and providing all conduit boxes, junction boxes and the like.

f. The rates for the installation of sub main circuits, lighting points switched points, socket outlets, fused spur outlets, isolators, etc. (other than those applicable to the distribution switch gear) shall include where applicable, for all conduit, trunking, cable tray, cabling, terminations, fixings and connections from the distribution
switched gear to and including the point (accessories measured separately) and shall be deemed to include for any item mentioned in the Electrical installation Specification but not shown on the drawings and vice-versa.

g. The rates for lighting fittings, fittings such as ceiling fans and extract fans, and for appliances such as air- conditioning units shall include for assembly, fixing and connection from the spur outlet or isolator to the fitting or appliance with all necessary additional wiring earthing and outlet roses and leaving perfectly clean and undamaged on completion.

h. The rates for fixing only fittings and appliances provided by the employer should include in addition to the foregoing for accepting delivery, storing and handling the fittings and providing any additional materials and internal wiring.

j. The rates for connections only to fittings and appliances such as pumps, water heaters, air conditioning units and extract fans shall include for connection from the isolator or spur outlet to the fitting or appliance (these being measured separately) , with all necessary additional wiring, earthing and outlet roses.

k. The rates for power outlets shall include for mounting boxes and frames.

l. The rates for power switched with remote outlets shall include for the additional outlet plates and boxes.

m. The rates for switched socket outlets shall include for 1 No fused plug top and 4 No fuse links.

n. The preceding preambles shall apply equally to auxiliary installations such as TV installations, telephone installations, and bell signal systems.

o. Painting of timber work and metal work.

p. If the items of electrical installation are measured as sub circuit point wiring or in electrical points, the rates for such items shall include for :

i. The preceding clauses of this trade where relevant.

This BSR is for Construction works only

ii. Preparation of asbuilt drawings to be submitted to Employer at the handing over/ practical completion.

iii. All items and accessories required for proper installation as per specification and regulation up to load point and labour connected therewith.

iv. All wiring, conduiting and cables and labour connected therewith if not measured separately.

v. Items specified in the specification but not shown in the drawings.

vi. Disconnecting and refixing of electrical fitting and appliances as required for the convenience of other trades.

vii. Painting of timber work metal work executed under this trade.

q. Rate to include submission of Megar Test report of the building Elactrical Installation from Charted Elactrical Engineer

DOB
Build Future ..... Restore Past

Construction BSR 2024

for

Department of Buildings ***(Metric Version)***

Item Code	Item Description	Unit	Basic Rate 2024
	C - DEMOLISHER		
C001	Demolishing brickwork in cement stacking brick and clearing debris away	**m^3**	**1,074**
C002	Demolishing brickwork in lime stacking brick and clearing debris away	**m^3**	**1,018**
C003	Removing existing Ceiling, stacking materials and clearing debris away.	**m^2**	**111**
C004	Demolishing Cement mass concrete in floors of 150mm thick, and clearing debris away.	**m^3**	**5,297**
C005	Demolishing reinforced cement concrete in suspended floors of 100mm thick, removing reinforcement and clearing debris away.	**m^2**	**1,130**
C006	Removing and stacking corrugated sheets, G.I., asbestos or Zn/Al from roof , or walls and clearing debris away.	**m^2**	**167**
C007	Removing and stacking Door or Window, size upto 3.75 m2 from existing walls	**Nos**	**2,025**
C008	Removing and stacking Door or Window, size over 3.75 m2 from existing walls	**Nos**	**1,683**
C009	Removing and stacking Door or Window, sash only up to 3.75 m2 from existing walls	**Nos**	**294**
C010	Demolishing floors brick paved, 100mm thick and clearing debris away.	**m^2**	**133**
C011	Demolishing rubble masonry in cement, stacking rubble and clearing debris away.	**m^3**	**1,610**
C012	Removing and stacking tiles Calicut or half round, from roof of single storeyed buildings and clearing debris away.	**m^2**	**121**
	Transporting debris		
C013	Transporting debris cleared away from site by tractor (app 16Km away). Rate to include loading & unloading.	**Load**	**6,264**

Construction BSR 2024

for

Department of Buildings ***(Metric Version)***

Item Code	Item Description	Unit	Basic Rate 2024
	D - EARTH WORK		
	Site Clearing		
D001	Clearing site vegetation including removal of bushes, shrub under growth hedges and tree stumps upto 300mm girth measured at height upto 1.0 m above ground level ,removing rubbish upto a distance of 50m beyond the outer walls of the proposed building.	**m^2**	**36**
	Removing Trees		
D002	Removing trees and stumps size of girth varies from 300mm and upto 600mm and girths are measured at 1.0 m height above ground level including cutting of trunks and branches, grubbing up roots, staking of serviceable materials and disposal of unserviceable materials.(aveg. 150mm dia. and aveg. ht 3.0m)	**Nos**	**945**
D003	Removing trees and stumps size of girth varies beyond 600mm and upto 1200mm and girths are measured at 1.0 m height above ground level including cutting of trunks and branches, grubbing up roots, staking of serviceable materials and disposal of unserviceable materials.(aveg. 300mm dia. and aveg. ht 4.5m)	**Nos**	**3,785**
D004	Removing trees and stumps size of girth varies beyond 1.2m and upto 2.4m and girths are measured at 1.0 m height above ground level including cutting of trunks and branches, grubbing up roots, staking of serviceable materials and disposal of unserviceable materials.(aveg. 600mm dia. and aveg. ht.7.0m)	**Nos**	**22,683**
D005	Removing trees and stumps size of girth varies beyond 2.4m and girths are measured at 1.0 m height above ground level including cutting of trunks and branches, grubbing up roots, staking of serviceable materials and disposal of unserviceable materials.(aveg. 1.0m dia. and aveg. ht.10.0m)	**Nos**	**29,115**
	Removing Top Soil		
D006	Removing top soil to a depth not exceeding 150mm & depositing as directed within site	**m^2**	**148**
	Excavation		
D007	Excavation over site to reduce level in any material except rock requiring blasting including depositing and levelling as directed upto a distance not exceeding 10.0m	**m^3**	**1,192**
D008	Excavation in trenches for walls/column pits in soft/loose soil from 0 to 1.5 m deep and depositing excavated material to a distance not exceeding 10.0m . (Earth work support to be paid separately).	**m^3**	**795**
D009	Excavation in trenches for walls/column pits in ordinary soil from 0 to 1.5 m deep and depositing excavated material to a distance not exceeding 10.0m . (Earth work support to be paid separately).	**m^3**	**1,391**

Construction BSR 2024

for

Department of Buildings ***(Metric Version)***

Item Code	Item Description	Unit	Basic Rate 2024
D010	Excavation in trenches for walls/column pits in hard dense soil from 0 to 1.5 m deep and depositing excavated material to a distance not exceeding 10.0m . (Earth work support to be paid separately).	m^3	**1,986**
D011	Excavation in trenches for walls/column pits in mud/wet soil from 0 to 1.5 m deep and depositing excavated material to a distance not exceeding 10.0m . (earth work support to be paid separately).	m^3	**1,788**
D012	Excavation in trenches for walls/column pits in soft disintegrated rock (not requiring blasting) up to a depth of 1.5 m and depositing excavated material to a distance not exceeding 10.0m . (earth work support to be paid separately).	m^3	**1,589**
D013	Excavation in trenches for walls/column pits in hard rock requiring blasting up to a depth of 1.5 m and depositing excavated material to a distance not exceeding 10.0m . (earth work support to be paid separately).	m^3	**2,670**
D014	Benching rock in foundation in 1.0m steps.(Blasting prohibited)	m^2	**4,911**
	Earthwork-backfilling		
D015	Backfilling in 150mm layers & compacting pits and trenches with available earth	m^3	**596**
D016	Backfilling in 150mm layers & compacting pits and trenches with imported	m^3	**3,845**
D017	Filling under floors including levelling watering and compacting in *150mm* layers with selected earth available at site	m^3	**1,589**
D018	Filling under floors including levelling watering and compacting in 150mm layers with imported earth.	m^3	**4,838**
D019	Sand filling in Column footing, wall under foundations, watered and well rammed.	m^3	**10,410**
D020	Supplying, spreading, levelling, watering, Graded Quarry dust (4.5mm downward) in 225mm thick layers and compaction using machine Rammer.(loose volume). Rate include hire charges of the machine rammer.	m^3	**5,737**
D021	Supplying, spreading, levelling, watering, Dense graded Aggrigate Base Course(A.B.C) in 225mm thick layers and compaction using machine Rammer.(loose volume). Rate include hire charges of the machine rammer.	m^3	**5,737**
	Earth work support		
D022	Earth work support (open planking) in trenches upto a depth of *1.5m.*	m^2	**937**
D023	Earth work support (close planking) in trenches upto a depth of *1.5m.*	m^2	**1,598**
D024	Earth work support (close planking) in deep excavation in trenches upto *5m* depth.	m^2	**3,213**
	Anti-termite Treatment		
D025	Anti-termite treatment for the new construction with applying Biflex 10Tc or approved equivalent as per manufacturer's specification including horizontal & vertical barriers with 10 years warranty on application.	m^2	**850**

Construction BSR 2024

for

Department of Buildings ***(Metric Version)***

Item Code	Item Description	Unit	Basic Rate 2024
	F - CONCRETE		
	(Reinforcement and shuttering paid for separately)		
	Mixing Concrete *(Excluding Placing)(In-Situ Concrete)*		
F001	Mixing concrete 1:3:6 (40mm) using mixer	m^3	**16,416**
F002	Mixing concrete 1:2½:5 (25mm) using mixer	m^3	**18,597**
F003	Mixing concrete 1:2:4 (20mm) using mixer	m^3	**21,457**
F004	Mixing concrete 1: 1½ :3 (20mm) using mixer	m^3	**23,267**
F005	Mixing concrete 1: 1: 2 (20mm) using mixer	m^3	**28,061**
	Mass Concrete (Including Placing)		
	Site Mixed Concrete 1:3:6 (40mm) -(Gr.15 Mix)		
	In Foundation		
F006	50mm thick cement concrete 1:3:6(40mm) screed in foundation at depths Not exceeding 1.5 m.	m^2	**983**
F007	50mm thick cement concrete 1:3:6(40mm) screed in foundation at depths Exceeding 1.5 m & upto 3.0m	m^2	**1,005**
F008	75mm thick cement concrete 1:3:6(40mm) screed in foundation at depths Not exceeding 1.5 m.	m^2	**1,274**
F009	75mm thick cement concrete 1:3:6(40mm) screed in foundation at depths Exceeding 1.5 m & upto 3.0m	m^2	**1,334**
	Site Mixed Concrete 1:2:4 (20mm)-(Gr.20 Mix)		
	In Foundations		
F010	75mm thick cement concrete 1:2:4 (20mm) in foundation at depths Not exceeding 1.5 m.	m^2	**1,826**
F011	75mm thick cement concrete 1:2:4 (20mm) in foundation at depths Exceeding 1.5 m & upto 3.0m	m^2	**1,839**
F012	150mm thick cement concrete(mass concrete) 1:2:4 (20mm) in floor including placing and curing.	m^2	**3,630**
	Reinforced Concrete (Including Placing, Vibrating and Curing)		
	Site Mixed Concrete 1:2:4(20mm)-Grade 'C - 20'		
	In Column shafts/Walls- upto 1st floor level		
F013	Cement concrete with 1:2:4 (20mm), in 113mmx150mm column in ground floor.	**m**	**415**
F014	Cement concrete with 1:2:4 (20mm), & 150mmx150mm Columns in ground floor	**m**	**551**
F015	Cement concrete with 1:2:4 (20mm) ,& 225mmx225mm Columns in ground floor	**m**	**1,242**
F016	Cement concrete 1:2:4(20mm) & 300mmx300mm Column shafts in ground floor, using mixer and vibrator.	**m**	**2,209**

Construction BSR 2024

for

Department of Buildings ***(Metric Version)***

Item Code	Item Description	Unit	Basic Rate 2024
F017	Cement concrete with 1:2:4(20mm), in 350mmx350mm column in ground floor	m	3,043
F018	Cement concrete with 1:2:4 (20mm),225mmx150mm beam upto 1st floor level	m	813
F019	Cement concrete with 1:2:4 (20mm),225mmx225mm beam upto 1st floor level	m	1,214
F020	Cement concrete with 1:2:4 (20mm),225mmx300mm beam upto 1st floor level	m	1,602
	In Floor Slabs		
F021	125mm thick R.C.C. floor slab with 1:2:4 (20mm), in 1st floor, rate inclusive of placing vibrating and curing.	m^2	3,323
F022	150mm thick R.C.C. floor slab with 1:2:4 (20mm) ,in 1st floor, rate inclusive of placing vibrating and curing.	m^2	3,986
	In Lintols		
F023	Cement concrete with 1:2:4 (20mm), in 113mmx150mm lintols in ground floor, rate inclusive of placing vibrating and curing.	m	438
F024	Cement concrete with 1:2:4 (20mm), in 225mmx225mm lintols in ground floor, rate inclusive of placing vibrating and curing.	m	1,292
F025	Cement concrete with 1:2:4 (20mm), in 225mmx300mm lintols in ground floor, rate inclusive of placing vibrating and curing.	m	1,821
F026	Cement concrete with 1:2:4 (20mm), in 300mmx375mm, lintols in ground floor, rate inclusive of placing vibrating and curing.	m	2,913
	Site Mixed Concrete 1:1½:3(20mm)-Grade 'C - 25'		
	In Floors		
F027	150 mm thick cement concrete 1: 1½ :3 (20mm)Ground floor (mass concrete), rate inclusive of placing, vibrating and curing.	m^2	3,855
F028	125mm thick R.C.C. floor slab with 1:1½ :3 (20mm) ,in 1st floor, rate inclusive of placing, vibrating and curing.	m^2	3,330
F029	150mm thick R.C.C. floor slab with 1:1½:3 (20mm), in 1st floor, rate inclusive of placing, vibrating and curing.	m^2	3,990
	In Column shafts		
F030	Cement concrete with 1: 1½ :3 (20mm),in 150mmx150mm columns in ground floor, rate inclusive of placing, vibrating and curing.	m	583
F031	Cement concrete with 1: 1½ :3 (20mm), in 225mmx225mm column in ground floor 1: 1½ :3 (20mm), rate inclusive of placing, vibrating and curing.	m	1,322
F032	Cement concrete with 1: 1½ :3 (20mm), in 300mmx300mm column in ground floor, rate inclusive of placing, vibrating and curing.	m	2,346
F033	Cement concrete with 1: 1½ :3 (20mm), in 350mmx350mm column in ground floor, rate inclusive of placing, vibrating and curing.	m	3,246
	In Beams		
F034	Cement concrete with 1: 1½ :3 (20mm) ,150mmx150mm beam upto 1st floor level, rate inclusive of placing, vibrating and curing.	m	648

Construction BSR 2024

for

Department of Buildings ***(Metric Version)***

Item Code	Item Description	Unit	Basic Rate 2024
F035	Cement concrete with 1:1½:3 (20mm),225mmx150mm beam upto 1st floor level, rate inclusive of placing, vibrating and curing.	m	972
F036	Cement concrete with 1:1½:3 (20mm),225mmx225mm beam upto 1st floor level, rate inclusive of placing, vibrating and curing.	m	1,465
F037	Cement concrete with 1:1½:3 (20mm),225mmx300mm beam upto 1st floor level, rate inclusive of placing, vibrating and curing.	m	1,949
	In Lintols		
F038	Cement concrete with 1:1½:3 (20mm), in 113mmx150mm lintols in ground floor, rate inclusive of placing, vibrating and curing.	m	487
F039	Cement concrete with 1:1½:3 (20mm) , & 225mmx225mm lintols in ground floor, rate inclusive of placing, vibrating and curing.	m	1,466
F040	Cement concrete with 1:1½:3 (20mm) , & 225mmx300mm lintols in ground floor, rate inclusive of placing, vibrating and curing.	m	1,948
F041	Cement concrete with 1:1½:3 (20mm) ,in 300mmx 375mm lintols in ground floor, rate inclusive of placing, vibrating and curing.	m	3,259
	Ready mixed Concrete (Including Placing ,Vibrating and Curing)		
F042	Supplying and laying Ready Mixed concrete Grade 20 (First floor slab)..	m^3	27,912
F043	Supplying and laying Ready Mixed concrete Grade 25 (First floor slab).	m^3	28,892
F044	Supplying and laying Ready Mixed concrete Grade 30 (First floor slab).	m^3	29,274
F045	Supplying and laying Ready Mixed concrete Grade 35 (First floor slab).	m^3	30,918
F046	Hiring charges for concrete pump Truck (Up to 30m3)	Item	42,212
F047	Hiring charges for concrete pump Truck (For every 1m3 above 30m3)	m^3	1,589
	Timber Formwork		
	Form work (For Column in ground floor)		
F048	Sawn timber formwork to 225mmx225mm cement concrete column in ground floor including making mould, assembling ,dismantling ,cleaning and repairing after use.	m^2	3,201
	Form work (Untreated Non-structural Category A)		
F049	Shuttering for floor slab concrete including 100mmx50mm (untreated non-structural category A) timber joists and necessary props. upto 3.6m height. (Rate to include for dismantling same when required).	m^2	1,892
F050	Shuttering for column shaft 225mm x 225mm including (untreated non-structural category A) timber joists and necessary props etc. (Rate to include for dismantling same when required)	m^2	3,124
F051	Shuttering for beam sides & soffit in (untreated non-structural category A) timber, joists and necessary props etc. (Rate to include for dismantling same when required)	m^2	2,601

Construction BSR 2024

for

Department of Buildings ***(Metric Version)***

Item Code	Item Description	Unit	Basic Rate 2024
	20mm thick plywood form work		
F052	20mm thick plywood form work for concrete beams in ground floor consider 225 mmx 300 mm beam to 6 m, long contact area 5 m2.	**m^2**	**2,155**
F053	Supplying and fixing 20mm thick plywood form work in column ground floor consider area 1.4 m2. (1.5 m high 225 mmx 225 mm column.)	**m^2**	**3,127**
F054	Supplying and fixing 20mm thick plywood timber formwork for underside of fist floor slab. consider 6m x 3m area - 18 m2.	**m^2**	**3,637**
	Sawn timber formwork		
F055	Sawn timber formwork for concrete beam in ground floor including timber joist and necessary props (Rate to include for dismanteling same when required).	**m^2**	**2,202**
F056	Sawn timber formwork for underside of first floor slab including timber joist and necessary props (Rate to include for dismanteling same when required).	**m^2**	**2,159**
	Reinforcement		
F057	Tor steel reinforcement to slabs, beams, columns or lintols bent to shape laid in position and tied with G I wire as directed	**Mt**	**397,073**
F058	Tor steel rods in foundation bending to shape, laying in position and tying with G.I wire as directed.	**Mt**	**372,569**
F059	Mild steel reinforcement to slabs, beams, columns or lintols bent to shape laid in position and tied with G I wire as directed	**Mt**	**398,723**

Construction BSR 2024

for

Department of Buildings ***(Metric Version)***

Item Code	Item Description	Unit	Basic Rate 2024
	G-MASONRY WORK		
	Brick Work *and* Block Work		
	Brick Work		
G001	Brick work in cement sand 1:5 in foundation upto D P C	m^3	22,935
G002	Brick work in cement sand 1:8 in foundation upto D P C	m^3	22,433
G003	Brick work in cement sand 1:5 in *112.5mm* (4½") thick walls in ground floor	m^2	2,607
G004	225mm (9") thick brick wall cement sand 1:5 in superstructure/ walls in ground floor	m^2	5,378
G005	Brick work 350mm (13½") thick in cement sand 1:5 in superstructure in ground floor	m^2	7,464
G006	225mm (9") thick brick wall cement sand 1:8 in superstructure/walls in in ground floor	m^2	4,941
G007	112.5mm (4½") thick brick wall (wire cut) in cement sand 1:5 in ground floor	m^2	3,372
G008	225mm (9") thick in cement and sand 1:5 with wire cut brick	m^2	6,419
G009	Extra over for facing including raised pointing 3mm thick in cement sand 1:1 mixture in ground floor	m^2	2,464
G010	75mm thick floor paved in lime mortar 2:5 in ground floor	m^2	2,321
G011	75mm thick floor paved in cement mortar 1:8 in ground floor	m^2	2,348
G012	Steps 338mm x150mm in brick in cement and sand 1:5 with 16mm thick cement and sand 1:2 rendering including necessary excavation	m	2,428
	Hollow block masonry		
G013	100mm thick Hollow block masonry in cement and sand mortar 1:5 with cavities unfilled in ground floor.3.0mx3.0m area (size of each block 400mmx200mmx100mm) (Min com/st 3.0 N/mm2)	m^2	2,331
G014	150mm thick hollow block work in cement and sand mortar 1:5 with cavities unfilled in ground floor.3.0mx3.0m area (size of each block 400mmx200mmx150mm) (Min com/st 3.0 N/mm2)	m^2	3,028
G015	200mm thick Hollow block masonry in cement and sand mortar 1:5 with cavities unfilled in ground floor. 3.0mx3.0m area (size of each block 400mmx200mmx200mm) (Min com/st 3.0 N/mm2)	m^2	3,907
	Solid block masonry		
G016	100mm thick solid block masonry in cement and sand mortar 1:5 in ground floor. 3.0mx3.0m area (size of each block 400mmx200mmx100mm) (Min com/st 3.0 N/mm2)	m^2	2,806
G017	150mm thick solid block masonry in cement and sand mortar 1:5 in ground floor.3.0mx3.0m area (size of each block 400mmx200mmx150mm) (Min com/st 3.0 N/mm2)	m^2	3,575

Construction BSR 2024

for

Department of Buildings ***(Metric Version)***

Item Code	Item Description	Unit	Basic Rate 2024
G018	200mm thick solid block masonry in cement and sand mortar 1:5 in ground floor. 3.0mx3.0m area (size of each block 400mmx200mmx200mm) (Min com/st 3.0 N/mm2)	m^2	4,543
	Stone Work		
G019	Random rubble (150mm-250mm) masonry in cement mortar 1:5 in foundation	m^3	18,217
G020	Random rubble (150mm-250mm) masonry in cement mortar 1:5 in superstructure	m^3	19,525
	Paste rubble		
G021	Supplying & Laying pointed (50mm-75mm thick) or Paste rubble masonry in cement and sand 1:2 in ground Floor.(Including hire chargers of Grinder)	m^2	12,668

Construction BSR 2024

for

Department of Buildings ***(Metric Version)***

Item Code	Item Description	Unit	Basic Rate 2024
	H-WATER PROOFING		
H001	*20mm* thick DPC in cement sand 1:2 finished with 2 coats hot tar and blinded with sand	m^2	**1,929**
H002	Concrete waterproofing treatment by using Crystallization technology according to Manufacturers specification's. (***"Xypex"*** or equivalent approved product including preparation of surface)	m^2	**4,296**
H003	Waterproofing treatment using cement based, micro-porous (breathing), coating according to Manufacturers Specifications. (***"Thoroseal"*** or equivalent approved product including preparation of surface),	m^2	**4,497**
H004	Waterproofing treatment by using flexible polymer cement slurry according to Manufacturers specification's. (***"Masterseal 540"(Barralastic)*** or equivalent approved product including preparation of surface)	m^2	**4,306**
H005	Waterproofing and crack isolation membrane type treatment to slab (area less than $300m^{2)}$ according to Manufacturers specification's. (***"Mapelastic"*** or equivalent approved product including preparation of surface)	m^2	**#VALUE!**
H006	Waterproofing treatment to external walls by using acrylic elastomeric high flexible bituminous coating according to Manufacturers specification's. (***"Synroof"*** or equivalent approved product including preparation of surface)	m^2	**3,014**
H007	Supply & Laying Gauge 700 Polythene damp proof membrane with 150mm laps laid under floors.	m^2	**75**
H008	Supply & Laying Gauge 1000 Polythene damp proof membrane with 150mm laps laid under floors.	m^2	**105**

Construction BSR 2024

for

Department of Buildings ***(Metric Version)***

Item Code	Item Description	Unit	Basic Rate 2024
	J-STRUCTURAL METAL WORKS		
	"C" channel		
J001	Supplying & Fixing of a structural steel channel purlin 127mm x 64mm (14.9 Kg/m) fixed as a purlin on roof trusses / roof beams with necessary bolts/cleat connecting arrangement (Cleats and Bolts Paid separately). Rate shall include for applying two coats of enamel paint (C.I.C. or equivalent) after treating with a coat of anticorrosive paint to all exposed faces of purlin.	**m**	**6,720**
	Wire mesh		
J002	Wire netting, hexagonal mesh 12mm supplying and fixing (beading to be paid for separately)	**m^2**	**1,824**
	Weld mesh		
J003	50mmx50mm Weld mesh No.12, supplying and fixing to existing frames with staples (fillets and beadings to be paid for separately)	**m^2**	**1,850**
J004	50mm x 50mm Weld mesh No.10 supplying and fixing to window frames with 50mm x 12mm (Group 2) timber beadings, and painting weld mesh with 2 coats anti-corrosive paint, and beadings with primer, undercoat and 2 coats enamel paint to approved. Rate to include for making openings for bolts, casement stays etc.	**m^2**	**8,425**
J005	50mmx50mm Weld mesh No.12 supplying and fixing to window frames with 50mm x 12mm (Group 2) timber beading, and painting weld mesh with 2 coats anti-corrosive paint, and beadings with primer, undercoat and 2 coats enamel paint to approved tint Rate to include for making openings for bolts, casement stays etc.	**m^2**	**7,984**
	Web Truss - (Angle between 15^0 - 45^0)		
J006	Fabricating & Fixing Steel web Truss , Span less than 8m consist of 38mmx38mmx6mm top chord and bottom chord with 16mm mild steel bracings. Including all , gusset plates , cleats , rivets , nuts, washers, rag bolts, separators etc.. (Rate shall include for painting of two coats of anticorrosive paint & one coat of enamel paint.) (Hoisting charges paid separately)	**Kg**	**744**

Construction BSR 2024

for

Department of Buildings ***(Metric Version)***

	K-METAL WORK		
	Aluminium		
	**** Aluminium window ****		
	70mm (1.2mm thick) Aluminium Casement Double Sash Window		
	Supplying, Fabricating & Installing of 1.2mm thick 70mm deep double sashed Aluminium Casement window frame and 1.2mm thick 40mm X 35mm (depth) window sashes . Rate to include for 5mm thick glass pans, EPDM rubber beadings, weather strips, casement locks, Hinges, rawl plugs, fasteners & etc. (Alumex extrusion Nos. CA-2005, CA 1011 & CA 1012 or equivalent)		
K001	-DO- Matt Finished Aluminium	**m^2**	**36,510**
K002	-DO- Natural Anodized Aluminium	**m^2**	**39,187**
K003	-DO- Bronzed Anodized Aluminium	**m^2**	**39,519**
K004	-DO-Powder Coated Aluminium	**m^2**	**40,034**
K005	-DO-Wood Finished Aluminium	**m^2**	**46,226**
	70mm (1.2mm thick) Aluminium Casement Double Sash Window with Top Fixed Panel		
	Supplying, Fabricating & Installing of 1.2mm thick 70mm deep double sashed Aluminium Casement window frame and 1.2mm thick 40mm X 35mm (depth) window sashes with fixed glass panels on top. Rate to include for 5mm thick glass pans, EPDM rubber beadings, weather strips, casement locks, Hinges, rawl plugs, fasteners & etc. (Alumex extrusion Nos. CA-2005, CA 1011 & CA 1012 or equivalent)		
K006	-DO- Matt Finished Aluminium	**m^2**	**32,381**
K007	-DO- Natural Anodized Aluminium	**m^2**	**34,820**
K008	-DO- Bronzed Anodized Aluminium	**m^2**	**40,355**
K009	-DO-Powder Coated Aluminium	**m^2**	**35,533**
K010	-DO-Wood Finished Aluminium	**m^2**	**41,667**
	1.3mm thick 70mm Double Sashed Aluminium Sliding window		
	Supplying, Fabricating & Fixing Aluminium window with 1.3mm thick ,70mm depth Aluminium framed (max. width 32.0mm) Double sash(max. width 36.2mm)Sliding Window including 5mm clear glass pans, necessary/ EPDM rubber beadings, sliding lock etc. (Alumex extrusion No. 70S-1001, 70S-1201-1, 70S-1101-1, 70S-1401, 70S-1501, 70S-1601, 70S-1701 & etc. or equivalent)		
K011	-DO- Matt Finished Aluminium	**m^2**	**15,937**
K012	-DO- Natural Anodized Aluminium	**m^2**	**16,955**

Construction BSR 2024 *for* Department of Buildings			*(Metric Version)*
K013	-DO- Bronzed Anodized Aluminium	**m^2**	**17,193**
K014	-DO-Powder Coated Aluminium	**m^2**	**17,328**
K015	-DO-Wood Finished Aluminium	**m^2**	**19,780**
	1.3mm thick 70mm Double Sashed Aluminium Sliding window with 2 Fixed Panels at Top or Bottom		
	Supplying, Fabricating & Fixing Aluminium Window with 1.3mm thick ,70mm depth Aluminium Framed (max. width 61.0mm) Double sash (max. width 56.2mm) Sliding Window with Two fixed panels on top or bottom including 5mm clear glass pans, necessary/EPDM beadings, sliding lock etc.(Alumex extrusion No. 70S-1012, 70S-1201-1, 70S-1101-1, 70S-1401, 70S-1501, 70S-1601, 70S-1701 & etc. or equivalent)		
K016	-DO- Matt Finished Aluminium	**m^2**	**17,576**
K017	-DO- Natural Anodized Aluminium	**m^2**	**18,796**
K018	-DO- Bronzed Anodized Aluminium	**m^2**	**19,052**
K019	-DO-Powder Coated Aluminium	**m^2**	**19,178**
K020	-DO-Wood Finished Aluminium	**m^2**	**21,668**
	1.3mm thick 70mm 4 Sashed Aluminium Sliding window with 4 Sliding Panels at Top or Bottom		
	Supplying, Fabricating & Fixing Aluminium Window with 1.3mm thick ,70mm depth Aluminium Framed (max. width 60.0mm) Four Sliding Sashes(max. width 30.0mm) with Four Sliding panels on Top or Bottom including 5mm thick clear glass pans, necessary/EPDM beadings, sliding locks etc.(Alumex extrusion No. 70S-1201-1, 70S-1001-1, 70S-1006, 70S-1914, 70S-1401, 70S-1501, 70S-1601, 70S-1701 & etc. or equivalent)		
K021	-DO- Matt Finished Aluminium	**m^2**	**17,151**
K022	-DO- Natural Anodized Aluminium	**m^2**	**18,453**
K023	-DO- Bronzed Anodized Aluminium	**m^2**	**18,707**
K024	-DO-Powder Coated Aluminium	**m^2**	**18,876**
K025	-DO-Wood Finished Aluminium	**m^2**	**21,065**

Construction BSR 2024

for

Department of Buildings ***(Metric Version)***

	1.5mm thick 80mm 6 Sashed Aluminium Sliding window		
	Supplying, Fabricating & Fixing Aluminium Window with 1.5mm thick ,80mm depth Aluminium Framed (max. width 37.6mm) Six Sashes Sliding Window(max. width 63.0mm) including 5mm clear glass pans, necessary/EPDM beadings, sliding lock etc. (Alumex extrusion No. 80S-2001, 80SFL-1001, 80S-2201, 80S-2301, 80S-2101, 80S-2501, 80S-2601, 80S-2701, 80S-2101 & etc. or equivalent)		
K026	-DO- Matt Finished Aluminium	**m^2**	**23,179**
K027	-DO- Natural Anodized Aluminium	**m^2**	**25,156**
K028	-DO- Bronzed Anodized Aluminium	**m^2**	**25,476**
K029	-DO-Powder Coated Aluminium	**m^2**	**25,856**
K030	-DO-Wood Finished Aluminium	**m^2**	**29,883**
	Fixed glass Windows		
	70mm (1.2mm thick) Aluminium Fixed Glass Window		
	Supplying, Fabricating & Installing of 1.2mm thick 70mm deep Aluminium fixed glass window with 5mm thick clear glass pan. Rate to include for rubber/EPDM beadings, rawl plugs, fasteners etc. (Alumex extrusion Nos. CA 1011 & CA 1012 or equivalent)		
K031	-DO- Matt Finished Aluminium	**m^2**	**16,899**
K032	-DO- Natural Anodized Aluminium	**m^2**	**18,236**
K033	-DO- Bronzed Anodized Aluminium	**m^2**	**18,360**
K034	-DO-Powder Coated Aluminium	**m^2**	**18,653**
K035	-DO-Wood Finished Aluminium	**m^2**	**23,340**
	Aluminium doors		
	1.6mm thick Aluminium 100mm double door		
	Supplying, Fabricating and Installing of Aluminium Double sashed 100mm door with 5mm thick glass pans. Rate inclusive of necessary fasteners suitable wool felt and hinges (Union or equivalent 102x76x2 mm) etc.(Door closers, door locks and door handles paid separately)		
K036	-DO- Matt Finished Aluminium	**m^2**	**26,871**
K037	-DO- Natural Anodized Aluminium	**m^2**	**29,116**
K038	-DO- Bronzed Anodized Aluminium	**m^2**	**29,574**
K039	-DO-Powder Coated Aluminium	**m^2**	**30,542**
K040	-DO-Wood Finished Aluminium	**m^2**	**36,892**

Construction BSR 2024

for

Department of Buildings ***(Metric Version)***

	1.6mm thick Aluminium 100mm single door		
	Supplying, Fabricating and Installing of Aluminium Single sashed 100mm door with 5mm thick glass pans. Rate inclusive of necessary fasteners, wool felt and hinges (Union or equivalent 102x76x2 mm) etc.(Door closers, door locks and door handles paid separately)		
K041	-DO- Matt Finished Aluminium	**m^2**	**38,586**
K042	-DO- Natural Anodized Aluminium	**m^2**	**43,147**
K043	-DO- Bronzed Anodized Aluminium	**m^2**	**43,785**
K044	-DO-Powder Coated Aluminium	**m^2**	**44,544**
K045	-DO-Wood Finished Aluminium	**m^2**	**52,925**
	Aluminium Sliding Door		
	80mm (1.5 mm thick) Aluminium Sliding Door		
	Supplying, Fabricating and Installing 1.5mm thick 33.7mmX80mm (depth) Aluminium framed two sliding door sashes with 5mm thick glass pans, suitable/EPDM rubber beadings, necessary fastners, rollers & etc.(door locks and door handles paid separately) (Alumex extrusion Nos. 80S-2001, 80S-2002, 80S2101 and etc. or equivalent)		
K046	-DO- Matt Finished Aluminium	**m^2**	**27,220**
K047	-DO- Natural Anodized Aluminium	**m^2**	**29,233**
K048	-DO- Bronzed Anodized Aluminium	**m^2**	**29,556**
K049	-DO-Powder Coated Aluminium	**m^2**	**29,944**
K050	-DO-Wood Finished Aluminium	**m^2**	**34,432**
	100mm (1.5 mm thick) Aluminium Sliding Door		
	Supplying, Fabricating and Installing 1.5mm thick 30mmX98mm (depth) Aluminium framed one half fixed & Single Sliding Door sash with 5mm thick glass, suitable/EPDM rubber beadings, necessary fastners, rollers & etc. (Door closers, door locks and door handles paid separately) (Alumex extrusion Nos. SD-1001, DS-1101, SD1501 and etc. or equivalent)		
K051	-DO- Matt Finished Aluminium	**m^2**	**27,142**
K052	-DO- Natural Anodized Aluminium	**m^2**	**29,396**
K053	-DO- Bronzed Anodized Aluminium	**m^2**	**29,835**
K054	-DO-Powder Coated Aluminium	**m^2**	**33,305**
K055	-DO-Wood Finished Aluminium	**m^2**	**34,191**

Construction BSR 2024

for

Department of Buildings ***(Metric Version)***

	100mm (1.5 mm thick) Aluminium Sliding Door with top fixed panel		
	Supplying, Fabricating and Installing 1.5mm thick 30mmX98mm (depth) Aluminium framed one half fixed & Single Sliding Door sash with top fixed panels. Rate to include for 5mm glass pans, suitable/EPDM rubber beadings, necessary fastners, rollers & etc.(Door closers, door locks and door handles paid separately) (Alumex extrusion Nos. SD-1001, DS-1101, SD1501 and etc. or equivalent)		
K056	-DO- Matt Finished Aluminium	**m^2**	**29,554**
K057	-DO- Natural Anodized Aluminium	**m^2**	**31,209**
K058	-DO- Bronzed Anodized Aluminium	**m^2**	**31,211**
K059	-DO-Powder Coated Aluminium	**m^2**	**31,674**
K060	-DO-Wood Finished Aluminium	**m^2**	**36,640**
	100mm (1.6 mm thick) Aluminium 3 track Sliding Door		
	Supplying, Fabricating and Installing 1.5mm thick 30mmX98mm (depth) Aluminium framed one half fixed & Single Sliding Door sash with top fixed panels. Rate to include for 5mm glass pans, suitable rubber beadings, necessary fastners, rollers & etc.(Door closers, door locks and door handles paid separately) (Alumex extrusion Nos. SD-1001, DS-1101, SD1501 and etc. or equivalent)		
K061	-DO- Matt Finished Aluminium	**m^2**	**27,440**
K062	-DO- Natural Anodized Aluminium	**m^2**	**28,718**
K063	-DO- Bronzed Anodized Aluminium	**m^2**	**29,399**
K064	-DO-Powder Coated Aluminium	**m^2**	**29,842**
K065	-DO-Wood Finished Aluminium	**m^2**	**32,830**
	Zn/Alu Roller door		
K066	Supplying and fixing of a Zn/Alu Roller door, having a maximum clear width of 6.0m and consisting of 0.6mm thick Zn/Al covering sheet, center bar pulleys, side plates with necessary racers, fabricating mechanical winding box with m.s square tube and covering the box with metallic sheets, fixing on site with bottom bars and G.I, u-channels for vertical guides at two vertical edges, which are painted with two coats of anticorrosive paint and two coats of enamel paint to match the colour of door sheeting, and sound reduction rubber beading embedded in the guide bars. Pulling rod and chain to be provided for manual rolling operation. (Additional length of 225mm to two sides horizontally and 450mm to upper end inside the mechanical box as initial winding vertically to be added to the clear opening area).	**m^2**	**13,003**

Construction BSR 2024 *for* Department of Buildings *(Metric Version)*			
	Roller door motor		
K067	Suppling roller shutter door moter, 0.5Hp, 300w, 2.5A sing-phase, 1780 rpm and 54:1 gear ratio, with two remote controllers for auto operation.	**Nos**	**94,500**

Construction BSR 2024

for

Department of Buildings ***(Metric Version)***

Item Code	Item Description	Unit	Basic Rate 2024
	L-WOOD WORK		
	L1-Carpentry		
L001	Prepare and apply two coat of Wood preservative (clear type) to structural timber including touching up out ends etc. after fixing	m^2	520
	Timber treatment		
L002	Structural Timber treated by Vacuum Pressure Impregnation Technique with approved wood preservatives such as CCB that are registered by register of pesticides, for protection against wood destroying agents such as wood bores, fungi and termites. (Execution according to the Manufacturers specifications) (By "Finlay Celurised treated " or equivalent system)	m3	30,971
L003	Reepers 50mm x25mm in (Group3, Category A) timber supplying and fixing with iron nails, upto 30m (Shifting of tiles to be paid for separately)	m	606
L004	Supply and fixing 50mm x50mm (Group3,Category A) timber Battons, including two coats of Wood preservative (clear) applied in roof work, with nails over 30m.	m	636
L005	Supply and fixing 100mm x50mm (Group3,Category A) timber rafters, including two coats of Wood preservative (clear) applied for roof work.	m	1,770
L006	Supply and fixing 175mm x50mm (Group3,Category A) timber ridge plate, including two coats of Wood preservative (clear) applied in roof work.	m	5,535
L007	Supply and fixing 100mm x75mm (Group3,Category A) timber wall plate, including two coats of Wood preservative (clear) applied in roof work.	m	2,907
L008	Supply and fixing 125mm x75mm (Group3,Category A) timber perlin in roof work.	m	3,946
L009	Supply and fixing 100mm x75mm (Group3,Category A) timber Struts, upto 1800mm height in roof structure, including forming necessary Timber joints at both ends.600mm Timber bearer provided at Bottom.	m	2,976
L010	Class 1 timber frame work for Calicut pattern tile hip roof in single storey building consisting of wall plate beam ridge plate rafters etc.. (Preservative treatment to be measured separately)	m^2	6,794
L011	Class 1 timber frame work for corrugated asbestos sheet roof in single storeyed building	m^2	3,392

Construction BSR 2024

for

Department of Buildings ***(Metric Version)***

Item Code	Item Description	Unit	Basic Rate 2024
	L2-Joinary		
	Boards, barge, valance, fascia		
L012	Boards, barge, valance, fascia, 200mm wide and 25mm thick in (Group 5,Category A), timber fixing complete with necessary screws new or renewing, above .028 m3	**m**	**1,735**
L013	Boards, barge, valance, fascia, 200mm wide and 25mm thick in (Group 5,Category A), timber supplying and fixing complete with necessary screws new or renewing, upto .028 m3	**m**	**1,796**
L014	Boards, barge, valance, fascia, 200mm wide and 25mm thick in (Group 5,Category B), timber supplying and fixing complete with necessary screws new or renewing, above .028 m3	**m**	**1,009**
L015	Boards, barge, valance, fascia, 200mm wide and 25mm thick in (Group 5,Category B), timber supplying and fixing complete with necessary screws new or renewing, upto .028 m3	**m**	**986**
L016	20mmx225mm high Valance/barge board in (Group 5,Category A), timber fixed with with necessary screws/wire nails to rafters	**m**	**2,743**
L017	20mmx225mm high Valance/barge board in (Group 5,Category B), timber fixed with necessary screws/wire nails to rafters	**m**	**797**
	Ceiling / Partition		
L018	Ceiling, asbestos, flat fixing with clout headed nails to 100mm x 50mm joists and 50mm bearers of (Group 4,Category A) timber including 37.5mm x 12mm cover fillets and 62.5mm x 37.5mm coves of Halmilla timber. Rate to include 2 coats of wood preservatives to joists and bearers. Primer undercoating and two coats of emulsion paint to Asbestos sheets.	**m2**	**7,805**
L019	Flat asbestos horizontal eaves ceiling comprising 50mm x 50mm bearers in(Group 4,Category A) timber asbestos sheet supplied and fixed with beadings & cove moulding, rate to include for applying wood preservative to timber frame, two coats enamel paint for beadings, and two coats emulsion paint for asbestos ceiling.	**m^2**	**7,401**
L020	Ceiling or partition, Lunumidella, 12mm planning, lapping and nailing to existing frames or underside of rafters, above 9.3m2 (Fillets and beadings paid for separately)	**m^2**	**1,662**
L021	Ceiling or partition, Lunumidella, 12mm planning, lapping and nailing to existing frames or underside of rafters, upto 9.3 m2 (Fillets and beadings paid for separately)	**m^2**	**1,804**
L022	Ceiling or partition, Lunumidella, 12mm beading and rebating, nailing to underside of existing joists, rafters or frames, above one square (Fillets and beadings, paid for separately)	**m^2**	**1,494**

Construction BSR 2024

for

Department of Buildings ***(Metric Version)***

Item Code	Item Description	Unit	Basic Rate 2024
L023	Ceiling or partition, Lunumidella, 16mm beading and rebating, nailing to underside of existing joists, rafters or frames, upto one square (Fillets and beadings, paid for separately)	**m^2**	**2,595**
L024	Ceiling openings 600mm x 450mm approx., forming complete with 50mm x 50mm bearers. (Glass tiles or sheets paid for separately)	**Nos**	**3,692**
L025	Ceiling Lunumidella 12mm planks lapping and nailing to framework consisting of 100mm x 50mm joists and 50mm x 50mm bearers in (Group 4,Category A) timber, Rate to include for 2 coats of tar nap to joists and bearers.	**m^2**	**6,254**
L026	Ceiling Lunumidella 20mm thick planks lapping and nailing to framework consisting of 100mm x 50mm joists and 50mm x 50mm bearers in (Group 4,Category A) timber, Rate to include for 2 coats of tar nap to joists and bearers.	**m^2**	**7,387**
	Beading		
L027	Beading, Burma Teak, 37.5mm to 50mm x 12mm plain chamfering, supplying and fixing complete with brass screws.	**m**	**781**
L028	Beading, Burma Teak, 25mm x 20mm plain chamfering, supplying and fixing complete with brass screws.	**m**	**436**
L029	Beading, Alstonia or local timber 37.5mm to 50mm x 12mm plain chamfering, supplying and fixing complete with brass screws.	**m**	**167**
L030	Beading, Halmilla, 37.5mm to 50mm x 12mm, plain chamfering, supplying and fixing complete with brass screws.	**m**	**507**
L031	Beading or filleting in Ginisapu or local timber for glass panes supplying and fixing complete with brass springs or brass panel pins.	**m**	**259**
	Cove, mouldings		
L032	Cove, mouldings, Alstonia or equivalent 62.5mm x 37.5mm fixing with brass screws and plugs new or renewing.	**m**	**590**
	Fillets, quadrant		
L033	Fillets, quadrant 20mm x 20mm supplying and fixing with springs or nails, in (Group 6, Category A) timber.	**m**	**288**
L034	Fillets, quadrant 25mm x 25mm in (Group 6, Category A) timber supplying and fixing with springs or nails.	**m**	**404**
	Doors or Windows		
L035	Doors or windows, ledging, bracing and battening with groove and tongue joints, 100mm x 75mm frames and 20mm to 22mm thick sashes in (Group 2,Category A) local timber complete with brass furniture (Rim lock, Hinges).	**m^2**	**30,477**
L036	Doors or windows, ledging, bracing and battening with groove and tongue joints, 100mm x 75mm frames and 20mm to 22mm thick sashes in (Group 2,Category B) local timber complete with brass furniture.	**m^2**	**22,602**

Construction BSR 2024

for

Department of Buildings ***(Metric Version)***

Item Code	Item Description	Unit	Basic Rate 2024
L037	Doors or windows, framing and battening, with 100mm x 75mm frames and 25mm to 28mm sashes in (Group 2,Category A) local timber complete with brass furniture.	m^2	**32,366**
L038	Doors or windows, framing and battening, with 100mm x 75mm frames and 25mm to 28mm sashes in (Group 2,Category B) local timber complete with brass furniture.	m^2	**24,690**
L039	Doors or windows, framing and battening, with 100mm x 75mm frames and 32mm to 37.5mm sashes in (Group 2,Category A) local timber complete with brass furniture.	m^2	**31,121**
L040	Doors or windows, framing and battening, with 100mm x 75mm frames and 32mm to 37.5 mm sashes in (Group 2,CategoryB) local timber complete with brass furniture.	m^2	**26,162**
L041	Doors or Windows, framing and battening, sash only 25mm to 28mm thick in (Group 2,Category A) timber supplying and fixing complete with available furniture.	m^2	**19,405**
L042	Doors for garages, framing and battening in (Group 2,Category A) timber with 125mm x 100mm frames and 37.5mm thick sashes supplying and fixing complete with iron pintoles and strap hinges.	m^2	**20,815**
L043	Doors or Windows, glazing and/or paneling with 100mm x 75mm frames and 28mm to 32mmsashes in (Group 2,Category A) local timber supplying and fixing complete with brass furniture.	m^2	**27,602**
L044	Doors or Windows, glazing and/or paneling with 100mm x 75mm frames and 28mm to 32mm sashes in (Group 2,Category B) local timber supplying and fixing complete with brass furniture.	m^2	**23,207**
	Door frame		
L045	Door frame 100mm x 75mm in (Group 2,Category A) timber supplying & fixing in position.	**m**	**2,988**
L046	Door frame 100mm x 50mm in (Group 2,Category B) timber supplying and fixing in position.	**m**	**1,765**
	Plywood Door ** *Note:(Brand - MACKPY or equivalent)*		
L047	Door,32mm thick plywood ordinary (Moisture Resistant) single sash, size 825mmx 2025mm, hung on finished size 100mmx 75mm frame in (Group 2,Category A) timber and complete with brass furnitures. .(Door Lock paid Separately)	m^2	**22,670**
L048	Door,32mm thick plywood ordinary (Moisture Resistant) single sash, size 825mmx 2025mm, hung on finished size 100mmx 75mm frame in (Group 2,Category B) timber and complete with brass furnitures. .(Door Lock paid Separately)	m^2	**20,900**

Construction BSR 2024

for

Department of Buildings ***(Metric Version)***

Item Code	Item Description	Unit	Basic Rate 2024
L049	Supplying and fixing plywood door 32mm thick (Moisture Resistant) single sash, size 825mmx 2025mm,hung to the existing frame including necessary brass fittings.(Door Lock paid Separately) data 2ft 9"x6ft 9"=18.56s.ft	m^2	**12,704**
L050	Supplying & fixing 32mm thick Ply wood door, Both Side Luxury finish (Moisture Resistant) ,size 825mmx 2025mm, single sash, hung to existing frame including necessary brass fittings.(Door Lock paid Separately) data 2ft 9"x6ft	m^2	**19,111**
	Door PVC		
L051	Door PVC supply and fixing to existing opening, (with out frame), Lock, complete with altered size with out preparing reveals. (Size 750mmx1025mm)	m^2	**12,769**
L052	Door PVC supply and fixing to existing opening, with frame, Lock, complete with altered size with out preparing reveals. (Size 750mmx1025mm)	m^2	**19,788**
L053	Supplying and fixing **PVC step nosing** to stairway step edges using approved adhesive.	**m**	**985**
	Louver blades		
L054	Louvre blades 10mm minimum thickness in (Group 1, Category A) timber up to 100mm width supplying and fixing.	**m**	**1,016**
L055	Louvre blades 10mm minimum thickness in (Group 1, Category A) timber over 100mm and up to150mm.	**m**	**1,115**
L056	Louvre blades 10mm minimum thickness in (Group 1, Category A) timber over 150mm and up to 225mm.	**m**	**1,485**
	Wooden Posts		
L057	Posts, verandah, 125mm x 125mm tapering to 100mm x 100mm in (Group3, Category A) local timber, supplying and fixing on spur stones (spur stones paid for separately)	**m**	**5,165**
L058	Posts, verandah 150mm x 150mm tapering to 125mm x 125mm in (Group3, Category A) local timber supplying and fixing on spur stones (spur stones paid for separately)	**m**	**7,176**
L059	Posts, Wooden, round jungle timber 125mm minimum and average 150mm dia. supplying and fixing.	**m**	**448**
	Skirting		
L060	Skirting in Teak (225mm x 25mm moulding and beading supplying and fixing complete to wooden frame.	**m**	**2,843**
L061	Supplying and fixing Skirting in Lunumedella board 150mm x 20mm on walls.	**m**	**1,452**

Construction BSR 2024

for

Department of Buildings ***(Metric Version)***

Item Code	Item Description	Unit	Basic Rate 2024
	Pantry cupboards units		
L062	Supplying and fixing pantry cupboards top unit with (Group 2,Category A) timber 25mm thick apx.2700mmx800mmx300mm (high) outer frame and shashes.Applying two coats of woodsheen to exposed outer surface complete with handles,conceal hinges,anchor bolts etc and painting 2 coats of varnish to internal surface.	**m**	**70,268**
L063	Supplying and fixing pantry cupboards bottom unit with (Group 2,Category A) timber 25mm thick apx.2700mmx825mmx600mm (high) including Perstop laminated worktop and drawers with runners, conceal hinges and handles fixed. Applying two coats of woodsheen to exposed outer surface complete with handles,conceal hinges,anchor bolts etc and painting 2 coats of varnish to internal surface. (Rate excluding sink, taps and other accessories)	**m**	**87,716**

Construction BSR 2024

for

Department of Buildings ***(Metric Version)***

Item Code	Item Description	Unit	Basic Rate 2024
	Iron Mongary - L3		
	Cabin Hooks (Iron)		
L064	Cabin Hooks and eyes, 50mm Iron, supplying and fixing.	set	116
L065	Cabin Hooks and eyes, 75mm Iron, supplying and fixing.	set	127
L066	Cabin Hooks and eyes, 150mm Iron, supplying and fixing.	set	171
L067	Cabin Hooks and eyes, 200mm Iron, supplying and fixing.	set	213
L068	Cabin Hooks and eyes, 225mm Iron, supplying and fixing.	set	220
	Cabin Hooks (Brass)		
L069	Cabin Hooks 50mm polished, brass, heavy quality supplying and fixing with brass screws.	Nos	579
L070	Cabin Hooks 75mm polished, brass, heavy quality supplying and fixing with brass screws.	Nos	600
L071	Cabin Hooks150mm polished, brass, heavy quality supplying and fixing with brass screws.	Nos	642
L072	Cabin Hooks 200mm, polished, brass heavy Quality supplying & fixing with brass screws.	Nos	673
L073	Cabin Hooks, 225mm, polished, brass heavy quality supplying & fixing with brass screws.	Nos	768
L074	Cabin Hooks, 250mm, polished, brass heavy quality supplying & fixing with brass screws.	Nos	883
L075	Cabin Hooks, 300mm, polished, brass heavy quality supplying & fixing with brass screws.	Nos	930
	Casement fasteners, brass		
L076	Casement Stays, Iron 250mm heavy quality, supplying and fixing.	Nos	1,515
L077	Casement Stays, Iron 300mm heavy quality, supplying and fixing.	Nos	1,652
	Casement fasteners, brass		
L078	Casement fasteners, brass with mortice plate, polished heavy quality supplying and fixing with brass screws.	Nos	1,130
L079	Casement stays, polished 250mm heavy quality supplying and fixing.	Nos	1,954
L080	Casement stays, polished 300mm heavy quality supplying and fixing.	Nos	2,059
L081	Fanlight Catches, brass heavy quality, supplying and fixing with brass screws complete.	Nos	999
L082	Handles, door, brass, polished heavy quality supplying and fixing with brass screws complete.	Nos	914
	Hasp and staple, brass		
L083	Hasp and staple 10mm iron, safety type of approved heavy quality, supplying and fixing with iron screws.	Nos	510

Construction BSR 2024

for

Department of Buildings ***(Metric Version)***

Item Code	Item Description	Unit	Basic Rate 2024
L084	Hasp and staple 150mm iron, safety type of approved heavy quality, supplying and fixing with iron screws complete.	**Nos**	**552**
L085	Hasp and staple 300mm x 50mm iron, specially made out of 6mm iron plate and fixing with 6mm x 50mm bolts and nuts complete.	**Nos**	**4,590**
	Hasp and staple, brass		
L086	Hasp and staple, Safety type, 150mm brass, polished heavy quality supplying and fixing with brass screws, complete.	**Nos**	**1,125**
L087	Hasp and staple, Safety type, 100mm brass, polished heavy quality supplying and fixing with brass screws, complete.	**Nos**	**925**
L088	Hat Hooks, brass, supplying and fixing with brass screws.	**Nos**	**615**
	Hinges (Iron)		
L089	Hinges, butt, 50mm iron of approved heavy quality supplying and fixing with iron screws.	**pairs**	**851**
L090	Hinges, butt, 75mm iron of approved quality supplying and fixing with iron screws.	**pairs**	**877**
L091	Hinges, butt, 100mm iron of approved quality supplying and fixing with iron screws.	**pairs**	**1,060**
L092	Hinges, butt, 125mm iron of approved quality supplying and fixing with iron screws.	**pairs**	**1,692**
L093	Hinges supplied by Dept. fixing complete with screws.	**pairs**	**457**
L094	Hinges, strap iron 37mm x 6mm, 300mm long supplying & fixing with necessary bolts and nuts (excluding pintols)	**Nos**	**2,177**
L095	Hinges, strap iron 50mm x 6mm, 900mm long supplying and fixing with necessary bolts and nuts (excluding pintols)	**Nos**	**3,698**
L096	Hinges, spring, Japanese Helical, door supplying and fixing with iron screws complete.	**Nos**	**1,947**
	Hinges, brass		
L097	Hinges, butt, 50mm brass, polished heavy quality supplying and fixing with brass screws complete.	**pairs**	**1,237**
L098	Hinges, butt, 75mm brass polished heavy quality supplying and fixing with brass screws complete.	**pairs**	**1,527**
L099	Hinges, butt, 87.5mm brass polished heavy quality supplying and fixing with brass screws complete.	**pairs**	**2,062**
L100	Hinges, butt, 100mm brass polished heavy quality supplying and fixing with brass screws complete.	**pairs**	**2,097**
L101	Hinges, butt, 125mm brass polished heavy quality supplying and fixing with brass screws complete.	**pairs**	**2,453**
L102	Hinges center pivoted (consisting of 2 pieces) brass, polished heavy quality supplying and fixing with brass screws complete.	**pairs**	**1,242**

Construction BSR 2024

for

Department of Buildings ***(Metric Version)***

Item Code	Item Description	Unit	Basic Rate 2024
L103	Hinges, gravity, brass supplying and fixing with brass screws complete.	**pairs**	**1,436**
L104	Hinges, Parliamentary, 100mm brass, polished heavy quality supplying and fixing with brass screws complete.	**pairs**	**4,633**
L105	Hinges, Parliamentary, 125mm brass, polished heavy quality supplying and fixing with brass screws complete.	**Nos**	**2,406**
L106	Hinges, Parliamentary, 150mm brass, polished heavy quality supplying and fixing with brass screws complete.	**Nos**	**2,717**
L107	Hinges, spring, double acting, brass 100mm supplying and fixing.	**Nos**	**2,945**
	Hinges (Stainless Steel) for Timber Doors		
L108	Supplying and fixing UNION- Butt Hinges, 100mmx75mmx 3mm (thick) stainless steel, for wooden doors with brass screws.	**pairs**	**5,726**
	Hinges (Stainless Steel) for Aluminium Doors		
L109	Supplying and fixing UNION- Butt Hinges,100mmx75mmx 2mm (thick) stainless steel, for Aluminium doors with pop rivets. *Prime Cost of, UNION Butt Hinges, , 4"x3"x 2mm (thick) stainless steel, for Aluminium doors=2441*	**pairs**	**5,251**
	Holdfast		
L110	Holdfast 3.2mm x 50mm x 225mm flat iron supplying and fixing complete. per no *Prime Cost of, Flat iron 2"x⅛"=389*	**Nos**	**951**
L111	Locks, rim, 100mm iron, superior quality, heavy type supplying and fixing with iron screws complete.	**Nos**	**3,981**
L112	Locks, rim, 150mm iron, superior quality, heavy type supplying and fixing with iron screws complete.	**Nos**	**4,821**
L113	Locks, mortice, 100mm iron, superior quality, heavy type supplying and fixing with iron screws complete.	**Nos**	**4,361**
L114	Locks, mortice, 150mm iron, superior quality, heavy type supplying and fixing with iron screws complete.	**Nos**	**5,391**
L115	Locks, Bird type supplying and fixing with iron screws complete.	**Nos**	**3,156**
	Locks (Brass)		
L116	Locks, cupboards, 62.5mm brass, 4 levers with brass screws supplying and fixing complete.	**Nos**	**1,309**
L117	Locks, rim 150mm polished brass, 2 levers, superior quality and English make, supplying and fixing.	**Nos**	**4,286**
L118	Locks, rim 125mm single lever of best quality local manufacture, supplying and fixing.	**Nos**	**3,218**
L119	Supplying and fixing ,night latch/Rim Lock (Duplicate/Local), with duplicate keys.	**Nos**	**3,168**

Construction BSR 2024

for

Department of Buildings ***(Metric Version)***

Item Code	Item Description	Unit	Basic Rate 2024
L120	Supplying and fixing , Yale or Union, night latch Lock (Rim Lock), with duplicate keys. (Nos: 1022C,1027 or 1028),(Imported, British or south African make)	**Nos**	**8,479**
L121	Door rings, brass 37.5mm to 44mm supplying and fixing to doors and windows with brass screws.	**Nos**	**394**
L122	Lock Mortice (local) single supplying & fixing.	**Nos**	**5,256**
L123	Lock Mortice (local) double, supplying and fixing.	**Nos**	**8,289**
L124	Supplying and fixing two Lever single door UNION Motice Lock (No2295),(Imported, British or south African make).	**Nos**	**4,764**
L125	Supplying and fixing two Lever double door UNION Motice Lock (No2242), (Imported, British or south African make).	**Nos**	**9,502**
L126	Supplying and fixing UNION Cylindrical Motice Lock (No:X985) including Door handle pair,(Imported, British or south African make).	**Nos**	**15,679**
L127	Supplying and fixing UNION Nob set Lock (No:X96300) (Imported, British or south African make).	**Nos**	**6,743**
L128	Supplying and fixing UNION Nob set Lock for Toilets (No:X96350) (Imported, British or south African make).	**Nos**	**9,349**
	Door lock for Aluminium Doors		
L129	Supplying and Fixing UNION Door lock (No-X 920,X925 or X930) for Aluminium Door with necessary accessories to working order. *Prime Cost of, UNION Door lock (No-X 920,X925 or X930) for Aluminium Door=7082*	**Nos**	**7,832**
L130	Supplying and Fixing Door lock(No-VR50101B) for Aluminium Door with necessary accessories to working order. *Prime Cost of, Door lock-VR50101B=7613*	**Nos**	**8,303**
L131	Supplying and Fixing Door lock(No-VR50101C) for Aluminium Door with necessary accessories to working order. *Prime Cost of, Door lock-VR50101c=7823*	**Nos**	**8,513**
	Stainless Steel Door Handle for Aluminium Doors		
L132	Supplying and Fixing lock for Aluminium Sliding door with necessary accessories . *Prime Cost of, Sliding door Lock=383*	**Nos**	**833**
	Stainless Steel Door Handle for Aluminium Doors		
L133	Supplying and Fixing Stainless Steel Door Handle for Aluminium door with necessary accessories . *Prime Cost of, Stainless Steel Door handle=1622*	**Nos**	**2,072**

Construction BSR 2024

for

Department of Buildings ***(Metric Version)***

Item Code	Item Description	Unit	Basic Rate 2024
	Floor hinge		
L134	Supplying and Fixing of UNION floor hinge (No: 8300) with necessary accessories .(Imported, British or south African make) *Prime Cost of, UNION floor hing (No: 8300)=28418*	**Nos**	**31,333**
L135	Supplying and fixing imported floor hinges (new star) of approved quality including chipping of existing floors and making good after completion. *Prime Cost of, Floor hinge=12542*	**Nos**	**16,074**
	Door Closer		
L136	Supplying and fixing door closer Japanese make of approved heavy quality *Prime Cost of, Door closer (new star)=6001*	**Nos**	**6,817**

Construction BSR 2024

for

Department of Buildings ***(Metric Version)***

Item Code	Item Description	Unit	Basic Rate 2024
	M-CLADDING		
M001	Supplying, fabricating and installing of 4.0mm thick Aluminium composite cladding panel (Alucobond or equivalent European make) with open joint tray panel system using non corrosive 50x81x3mm tk. Aluminium "T" channel section (al 217), non corrosive 50x50x3mm pressed aluminium "U" wall bracket sub frame and AL 201 & AL 202 profiles on tray panel, Rate to include for ss nut and bolts, ss screws, blind rivets, U channels, Nylon resistant, Anchor bolts, and other necessary accessories. Bird mesh to be provided in side of vent areas, all complete as per manufacture's specifications.	m^2	41,958

Construction BSR 2024

for

Department of Buildings ***(Metric Version)***

Item Code	Item Description	Unit	Basic Rate 2024
	N-PARTITIONS & SUSPENDED CEILING		
	Aluminium Partitions		
	Aluminium Partition Frame Work (max. height 3600mm) - with Fully Fabric Board, 1.2mm thick, 76mm depth (max. width 23.0mm) extrusions		
	Supplying, Fabricating and Installing FULLY Fabric board (both sides) ALUMINIUM PARTITION consist of 1.2mm thick, 76mm depth (max. width 23.0mm) Aluminium extrusions and GI channel stiffener frame work enclosed in Aluminium frame work with an appropriate grid pattern, span not exceeding 1200mm in both vertical & horizontal directions suited to the available space and additional GI channel bracings placed in 600mm centers at vertical direction. Rate inclusive of Aluminium beadings (including necessary rubber beadings) necessary fasteners etc.		
N001	-DO- Matt Finished Aluminium	**m^2**	**15,617**
N002	-DO- Natural Anodized Aluminium	**m^2**	**15,883**
N003	-DO- Bronzed Anodized Aluminium	**m^2**	**15,974**
N004	-DO-Powder Coated Aluminium	**m^2**	**16,062**
N005	-DO-Wood Finished Aluminium	**m^2**	**16,925**
	Aluminium Partition Frame Work - top & bottom with Fabric Boards & middle panel with Glass Pans (max. height 3600mm), 1.2mm thick, 76mm depth (max. width 23.0mm) extrusions		
	Supplying, Fabricating and Installing Glass & Fabric Board ALUMINIUM PARTITION frame work with 1.2mm thick, 76mm depth (max. width 23.0mm) Aluminium extrusions. And top & Bottom panels consist of 3mm thick Fabric Board (both sides) with GI channel stiffener frame work enclosed in appropriate grid pattern, span not exceeding 1200mm in both vertical & horizontal directions, suited to the available space and additional GI channel bracings placed in 600mm centers at vertical direction. Middle panel consists of 5mm thick glass pans, span not exceeding 1200mm in both directions. Rate inclusive of Aluminium beadings (including necessary rubber beadings) necessary fasteners etc.		
N006	-DO- Matt Finished Aluminium	**m^2**	**14,787**
N007	-DO- Natural Anodized Aluminium	**m^2**	**15,137**
N008	-DO- Bronzed Anodized Aluminium	**m^2**	**15,250**
N009	-DO-Powder Coated Aluminium	**m^2**	**15,316**
N010	-DO-Wood Finished Aluminium	**m^2**	**16,571**

Construction BSR 2024

for

Department of Buildings ***(Metric Version)***

Item Code	Item Description	Unit	Basic Rate 2024
	Aluminium Partition Frame Work - top & bottom with PVC Boards & middle panel with Glass Pans (max. height 3600mm), 1.2mm thick, 76mm depth (max. width 23.0mm) extrusions		
	Supplying, Fabricating and Installing Glass & PVC Board ALUMINIUM PARTITION frame work with 1.2mm thick, 76mm depth (max. width 23.0mm) Aluminium extrusions. Top & Bottom panels consist of 3mm thick PVC Board (both sides) with GI channel stiffener frame work enclosed in appropriate grid pattern, span not exceeding 1200mm in both vertical & horizontal directions, suited to the available space and additional GI channel bracings placed in 600mm centers at vertical direction. Middle panel consists of 5mm thick glass pans, span not exceeding 1200mm in both directions. Rate inclusive of Aluminium beadings (including necessary rubber beadings) necessary fasteners etc.		
N011	-DO- Matt Finished Aluminium	**m^2**	**12,123**
N012	-DO- Natural Anodized Aluminium	**m^2**	**11,588**
N013	-DO- Bronzed Anodized Aluminium	**m^2**	**11,701**
N014	-DO-Powder Coated Aluminium	**m^2**	**11,766**
N015	-DO-Wood Finished Aluminium	**m^2**	**13,021**
	Aluminium Partition Frame Work (max. height 3600mm) - with Fully PVC Board, 1.2mm thick, 76mm depth (max. width 23.0mm) extrusions		
	Supplying, Fabricating and Installing 3mm thick Fully PVC board (both sides) ALUMINIUM PARTITION consist of 1.2mm thick, 76mm depth (max. width 23.0mm) Aluminium extrusions and GI channel stiffener frame work enclosed in Aluminium frame work with an appropriate grid pattern, span not exceeding 1200mm in both vertical & horizontal directions suited to the available space and additional GI channel bracings placed in 600mm centers at vertical direction. Rate inclusive of Aluminium beadings (including necessary rubber beadings) necessary fasteners etc.		
N016	-DO- Matt Finished Aluminium	**m^2**	**12,294**
N017	-DO- Natural Anodized Aluminium	**m^2**	**11,317**
N018	-DO- Bronzed Anodized Aluminium	**m^2**	**11,429**
N019	-DO-Powder Coated Aluminium	**m^2**	**11,495**
N020	-DO-Wood Finished Aluminium	**m^2**	**12,750**

Construction BSR 2024

for

Department of Buildings ***(Metric Version)***

Item Code	Item Description	Unit	Basic Rate 2024
	Aluminium Partition Frame Work - 5 mm thick fully Glass (max. height		
N021	-DO- Matt Finished Aluminium	**m^2**	**11,984**
N022	-DO- Natural Anodized Aluminium	**m^2**	**12,335**
N023	-DO- Bronzed Anodized Aluminium	**m^2**	**12,447**
N024	-DO-Powder Coated Aluminium	**m^2**	**12,513**
N025	-DO-Wood Finished Aluminium	**m^2**	**13,768**
	Aluminium Partition Frame Work - (max. height 3600mm) Fully Louvered. 1.2mm thick, 76mm depth (max. width 23.0mm) Aluminium extrusions		
	Supplying, Fabricating and Fixing FULLY ALUMINIUM LOUVERED PARTITION with 1.2mm thick, 76mm depth (max. width 23.0mm) Aluminium extrusions to form an appropriate grid pattern, span not exceeding 1200mm in both vertical & horizontal directions, suited to the available space and all panels consist of Louvers enclosed with Aluminium louver frame. Rate inclusive of Aluminium beadings (including necessary rubber beadings) necessary fasteners etc. (Rate for DG-01 & DG-101 louver extrusions)		
N026	-DO- Matt Finished Aluminium	**m^2**	**32,560**
N027	-DO- Natural Anodized Aluminium	**m^2**	**35,754**
N028	-DO- Bronzed Anodized Aluminium	**m^2**	**37,020**
N029	-DO-Powder Coated Aluminium	**m^2**	**37,107**
N030	-DO-Wood Finished Aluminium	**m^2**	**48,821**
	Aluminium 76mm Shopfront		
	Supplying, Fabricating and Installing fully glass 1.2 mm thick,76mm Aluminium Shopfront, frame work fixed as an appropriate grid pattern not exceeding 1200mm in both vertical & horizontal directions, suit to the available space including 5mm thick glass pans necessary rubber beadings, fasteners etc.		
N031	-DO- Matt Finished Aluminium	**m^2**	**16,523**

Construction BSR 2024

for

Department of Buildings ***(Metric Version)***

Item Code	Item Description	Unit	Basic Rate 2024
N032	-DO- Natural Anodized Aluminium	**m^2**	**17,204**
N033	-DO- Bronzed Anodized Aluminium	**m^2**	**17,359**
N034	-DO-Powder Coated Aluminium	**m^2**	**17,474**
N035	-DO-Wood Finished Aluminium	**m^2**	**19,693**
	Aluminium Curtain Wall (1.5mm thick)		
	Supplying, Fabricating and Fixing Aluminium Curtain Wall with 1.5mm thick,85mm depth extrusions, frame work fixed as an appropriate grid pattern, span not exceeding 1200mm in both vertical & horizontal directions, suit to the available space including 5mm thick glass pans, necessary rubber beadings, fasteners etc.		
N036	-DO- Matt Finished Aluminium	**m^2**	**23,776**
N037	-DO- Natural Anodized Aluminium	**m^2**	**26,599**
N038	-DO- Bronzed Anodized Aluminium	**m^2**	**27,070**
N039	-DO-Powder Coated Aluminium	**m^2**	**27,068**
N040	-DO-Wood Finished Aluminium	**m^2**	**28,909**
	Partitioning (Gypsum board)		
N041	Supplying and fixing gypsum board partitioning with GI channel member frame work fixed onto walls and floors , 12mm. thick gypsum board fixed to both sides of frame work complete with making joints using joint tape and gypsum compound to get wall finish .	**m^2**	**14,176**
	Hot dip GI interlocking ceiling frame work only		
N042	The frame members for suspended ceiling are in a standard kit (CKM or equivalent). Main runners (38mmx24mmx3660mm) are fixed at 1220 centers securely suspended using 4mm dia. GI hanging rod to the structural soffit or timber roof, using an appropriate suspension at 1220mm centers, Cross Tees (27mmx24mmx1220mm) of 1220mm length to be fixed between the main runners at 610mm centers and another cross tees (27mmx24mmx610mm) fixed at mid span between 610mm to form a grid structure of 610mmx 610mm in size. wall angles (24mmx24mmx3050mm) are fixed at wall edges. (Edge molding and painting paid separately)	**m^2**	**5,019**

Construction BSR 2024

for

Department of Buildings ***(Metric Version)***

Item Code	Item Description	Unit	Basic Rate 2024
	(Mineral fiber / Stone wool) acoustic ceiling suspended ceiling		
N043	Supplying & fixing of 600mm x600mm & 15mm thick (Mineral fiber / Stone wool) Acoustic ceiling boards (Rockfon or equivalent-Provides sound insulation from top and sound absorption within room level) lay on hot dip GI pre engineered interlocking ceiling frame work. The frame members for suspended ceiling are in a standard kit (CKM or equivalent). Main runners (38mmx24mmx3660mm) are fixed at 1220 centers securely suspended using 4mm dia adjustable GI hanging rod with spring clips to the structural soffit or existing roof structure, using an appropriate suspension at 1220mm intervals along each Main runners. Cross Tees (27mmx24mmx1220mm) of 1220mm length to be fixed between the main runners at 610mm centers and another cross tees (27mmx24mmx610mm) fixed at mid span between 610mm to form a grid structure of 610mmx 610mm in size. wall angles (24mmx24mmx3050mm) are fixed at wall edges.	m^2	**11,635**
N044	Supplying & fixing 1200mm x 600mm x 15mm thick Mineral fiber acoustic ceiling boards lay on Existing interlock type ceiling frame work , forming a panel side of 600mm X 600mm, and at the average elevation of 3600mm from the working floor, (for 12 nos or 9m2)	m^2	**2,278**
N045	Supplying and installing mineral fiber Japanese make suspended exposed ceiling system, using 1200mm x 600mm X 15 mm thick ceiling boards, lay on white colour interlock type, hot dip GI grid system , forming a panel side of 1200mm x 600mm, and suspended on 4mm rods with spring clip to soffit of concrete or timber roofs. (Edge molding paid separately)	m^2	**7,186**
N046	Supplying and installing mineral fiber Japanese make suspended exposed ceiling (Reaveal edge) system, using 605 mm X 605 mm X 15 mm white colour ceiling boards lay on white colour interlock type hot dip GI grid system , forming a panel side of 610mmx610mm,and suspended on 4mm rods with spring clip to soffit of concrete or timber roofs. . (Edge molding & Painting paid separately)	m^2	**10,439**
	Super Flex Suspended ceiling		
N047	Supplying and installing Super Flex (Plain) suspended ceiling system, using 2400mm X 1200mm X 4.5 mm ceiling boards lay on white colour interlock type hot dip GI grid system , forming a panel side of 600mm X 600mm , and suspended on 4mm rods with spring clip to soffit of concrete or timber roofs. (Edge molding & Painting paid separately)	m^2	**4,864**

Construction BSR 2024

for

Department of Buildings ***(Metric Version)***

Item Code	Item Description	Unit	Basic Rate 2024
N048	Supplying and installing Super Flex (with design) suspended ceiling system, using 1200mm X 1200mm X 3.2 mm ceiling boards in white colour interlock type hot dip GI grid system , forming a panel side of 600mm X 600mm, and suspended suspended on 4mm rods with spring clip to soffit of concrete or timber roofs (Edge molding & Painting paid separately)	m^2	**3,001**
	Gypsum board suspended ceiling		
N049	Supplying and fixing gypsum board suspended ceiling . using 600mm x 600mm X 9 mm. thick ceiling boards in white colour interlock type hot dip GI grid system , forming a panel side of 600mmx600mm, and suspended suspended on 4mm GI hanging rods with spring clip to soffit of concrete or timber roofs (Edge molding & Painting paid separately)	m^2	**10,212**
	Metal ceiling		
N050	Supply and installation of concealed type metal false ceiling, Including revel edge of 600mm x 600mm size 0.7mm minimum thickness, epoxy powder painted steel Tiles (paint film thickness of average 80microns) suspended to the roof frame work with, 0.3 mm thick pre painted hot dip galvanized, 15mm x 38mm plain TEE-grid bars and 20mm x 24mm wall angles, suspended with adjustable burrerfly clip, 4mm dia. surface treated galvanized steel hanger rods, complete with necessary anchor bolts and any other accessories. (All in accordance with the approved shop drawings, to the Engineers' satisfaction.)	m^2	**11,699**
N051	Supply and installation of lay in type "E-Metallic Aluminum ceiling, Including revel edge of 600mmx600mm size 0.7mm average thickness, 80 microns high quality powder coated Aluminum perforated or plain ceiling panels,. Suspended to the roof frame work with hot dip galvanized "T" bars of 14mm x 38mm and wall angles of 19mm x 24mm suspended with, adjustable burrerfly clip, 04mm GI hanging roads, anchor bolts and all other accessories. (All in accordance with the approved shop drawings, to the Engineers' satisfaction.)	m^2	**11,699**
	Ceiling panels (Pinholes)		
N052	Supplying, fixing aluminium 600mmx600mm ceiling panels (Pinholes) with aluminium frame work and adjustable.	m^2	**7,985**

Construction BSR 2024

for

Department of Buildings ***(Metric Version)***

Item Code	Item Description	Unit	Basic Rate 2024
	P-ROOF COVERING AND ROOF PLUMBING		
	Tiles, Calicut pattern, flat		
P001	Tiles Calicut pattern, supplying and laying in any building on existing roof frame.	**m^2**	**1,682**
	Tiles half round		
P002	Tiles half round, supplied and laid in any building on existing roof frame.	**m^2**	**4,311**
P003	Supplying and laying half round tiles on the existing asbestos roof.	**m^2**	**2,267**
	Zinc Aluminium Colour bonded Steel Roofing		
P004	Supplying and fixing Zinc Aluminium colour bonded steel roofing sheets (0.47 gauge)on existing frame work using nut & bolt / self tapping screws or fasteners.	**m^2**	**6,580**
P005	12mm thick heat and sound installation sheet (double side luminary aluminium foil) laying on 75mm x 75mm GI mesh under roof covering.	**m^2**	**1,225**
	Corrugated Asbestos sheets		
P006	Corrugated asbestos sheet roofing on category A timber purlins supplied and fixed complete including treating timber with wood preservative (Ridging measured separately).	**m^2**	**5,704**
P007	Corrugated asbestos sheets supplied and fixed to roof or wall on existing framework with necessary coach screws and limpet washers or hook bolts.	**m^2**	**2,624**
	Ridging		
P008	Ridging, Calicut pattern, bedded in cement and lime mortar 1:1:4, coloured to match tiles.	**m**	**1,263**
P009	Ridging, **half round** tiles, bedded in lime, cement mortar 1:1:4 and coloured to match tiles.	**m**	**1,219**
P010	Ridging, **Galvanized iron** 24 B.W.G 18" wide overall supplied and fixed complete.	**m**	**2,390**
P011	Supplying and fixing Zinc Aluminium colour bonded standard steel ridge cap to existing sheet roof using new fasteners or st /screws.	**m**	**2,989**
P012	0.47mm thick ,width 450mm Zink aluminium sheet ridging and fixing to roofing sheet with self trapping screws	**m**	**2,164**
P013	Ridging with **asbestos** cement close fitting ridges supplied and fixed complete with roofing screws or hook bolts.	**m**	**2,554**

Construction BSR 2024

for

Department of Buildings ***(Metric Version)***

Item Code	Item Description	Unit	Basic Rate 2024
	G.I Flashing		
P014	Flashing, G.I 22 B.W.G 450mm wide, supplying and fixing with 150mm turning up along, and top edge tucking well into wall in cement and lime mortar.	**m**	**2,878**
P015	18 BWG (1.2mm) galvanized iron flashing 450mm girth overall 3 times bent with end laps not less than 150mm lead soldered turned and tucked up to not less than 6" into chase out in wall and pointed in cement mortar 1:2 lower end dressed over roof covering.	**m**	**3,762**
	Valley gutter		
P016	Gutters valley, 18 B.W.G 900mm wide, renewing including timber 25mm thick boarding, sheet t be tarred, joints to be soldered and cement lime filleting complete.	**m**	**15,516**
P017	Supplying and fixing Zinc Aluminium sheet valley gutter (0.47mm) thick ,width 457mm and fixing to roof with self trapping screws.(Excluding timber boarding) Hi-tensile (Grade-550) Colour	**m**	**3,816**
P018	Supplying and fixing Zinc Aluminium sheet valley gutter (0.47mm) thick ,width 914mm and fixing to roof with self trapping screws.(Excluding timber boarding). Hi-tensile (Grade-550) Colour	**m**	**6,184**
	G.I semicircular Gutters		
P019	Gutters, eaves 150mm G.I semicircular 22 B.W.G making and fixing with hooks or brackets and screws, and joints to be soldered complete.	**m**	**2,715**
P020	Gutter, eaves 150mm moulded, G.I 22 B.W.G making and fixing complete including brackets.	**m**	**3,377**
P021	Gutters, existing, making opening to receive 100mm to 150mm down pipe, attaching spigot piece, joints to be soldered and making good.	**Nos**	**2,089**
P022	Gutter heads, 250mm x 250mm x 600mm making of G.I Sheets 22 B.W.G and fixing.	**Nos**	**8,882**
P023	Making and fixing Gutter heads, 225mm x 225mm x 300mm of G.I Sheets 22 B.W.G .	**Nos**	**6,027**
P024	Gutter hooks or brackets 20mm x 3mm supplying and fixing complete with Iron screws.	**Nos**	**594**
	Aluminium, Zn/Alu high tensile down pipes		
P025	Supplying, fixing 0.47mm tk., Zn/Alu high tensile down pipe (914mm girth) with brackets.	**m**	**6,129**
P026	Supplying, fixing 0.47mm tk., Zn/Alu high tensile down pipe (457mm girth) with brackets.	**m**	**3,361**
	Zn/Alu gutters		
P027	Supplying, fixing 0.47mm tk., Alu gutters (914mm girth) with brackets & specials.	**m**	**6,857**

Construction BSR 2024

for

Department of Buildings ***(Metric Version)***

Item Code	Item Description	Unit	Basic Rate 2024
P028	Supplying, fixing 0.47mm tk., Alu gutters (457mm girth) with brackets & specials.	m	3,699
	Zn/Alu Down pipe Bends		
P029	Supplying, fixing 0.47mm tk., Zn/Alu high tensile. Down pipe Bend (for 914mm girth gutter) with brackets & specials.	Nos	5,938
P030	Supplying, fixing 0.47mm tk., Zn/Alu high tensile. Down pipe Bend (for 457mm girth gutter) with brackets & specials.	Nos	2,428
	Elbows for down pipe.		
P031	Supplying & fixing 90mm P.V.C. elbows for down pipe.	Nos	832
	Running head.		
P032	Supplying & fixing , only a P.V.C. running head.	Nos	1,151
	Gutter end.		
P033	Supplying & fixing , only a square type P.V.C. gutter ends.	Nos	746
	Gutter Joint.		
P034	Supplying & fixing , only a square type P.V.C. gutter joints.	Nos	773
	Eves gutters (PVC)		
P035	Supplying and fixing eves gutters square type PVC with necessary specials, including running heads, mitre joints, gutter joints, gutter brackets, gutter ends etc.	m	1,840
P036	150mm diameter half round PVC eaves gutter fixed to timber valance board including gutter joiner and brackets fixed at 450mm centers.(other specials paid separately)	m	892
	Down pipes 100mm (3 ½") dia. P.V.C		
P037	Supplying & fixing rain water down pipes 100mm (3½") dia. P.V.C to wall, with necessary specials, including elbows, sockets, clips etc.	m	1,188
	Skylight glass		
P038	Skylight glass 600mm x 600mm, 6mm thick ribbed, supplied & fixed to roof including necessary lime cement filleting.	Nos	4,870

Construction BSR 2024

for

Department of Buildings ***(Metric Version)***

Item Code	Item Description	Unit	Basic Rate 2024
	Q-PLUMBER		
	Ball valve-UPVC		
Q001	Supplying & fixing UPVC ball valve 20mm dia. (S-Lon or equivalent)	**Nos**	**577**
Q002	Supplying & fixing UPVC ball valve 25mm dia. (S-Lon or equivalent)	**Nos**	**751**
Q003	Supplying & fixing UPVC ball valve 32mm dia. (S-Lon or equivalent)	**Nos**	**898**
Q004	Supplying & fixing UPVC ball valve 40mm dia. (S-Lon or equivalent)	**Nos**	**1,276**
	Ball valve-Brass		
Q005	Supplying & fixing Brass Ball valve ½" or 20mm-(Peglar or equivalent.)	**Nos**	**4,261**
Q006	Supplying & fixing Ball valve Brass ¾" or 25mm-(Peglar or equivalent.)	**Nos**	**4,849**
Q007	Supplying & fixing Ball valve Brass 1" or 32mm-(Peglar or equivalent.)	**Nos**	**7,781**
Q008	Supplying & fixing Ball valve Brass 1½" or 50mm -(Peglar or equivalent.) with necessary fittings.	**Nos**	**18,831**
	Concealed Taps/Valves-Chromium plated		
Q009	Supply and fixing concealed valve20mm dia. *Prime Cost of, Concealed Valve (plumber), ½"dia.=7665*	**Nos**	**8,056**
	Flush valve		
Q010	Supplying and fixing wall Urinal Flush Valve(FM 3A903)-High Quality *Prime Cost of, Urinal Flush Valve(Rocell)-High Qaulity=11414*	**Nos**	**11,805**
	Gate valve brass for Max. 17.5 bars (Pegler 1065 or equivalent)		
Q011	Supplying and fixing 15mm dia: gate valve brass imported (Pegler or equivalent, approved quality).	**Nos**	**1,495**
Q012	Supplying and fixing 20mm dia: gate valve brass imported (Pegler or equivalent, approved quality).	**Nos**	**3,117**
Q013	Supplying and fixing 25mm dia: gate valve brass imported (Pegler or equivalent, approved quality).	**Nos**	**3,918**
Q014	Supplying and fixing 32mm dia: gate valve brass imported (Pegler or equivalent, approved quality).	**Nos**	**5,315**
Q015	Supplying and fixing 40mm dia: gate valve brass imported (Pegler or equivalent, approved quality).	**Nos**	**10,894**
Q016	Supplying and fixing 50mm dia: gate valve brass imported (Pegler or equivalent, approved quality).	**Nos**	**12,707**
Q017	Supplying and fixing 63mm dia: gate valve brass imported (Pegler or equivalent, approved quality).	**Nos**	**21,527**

Construction BSR 2024

for

Department of Buildings ***(Metric Version)***

Item Code	Item Description	Unit	Basic Rate 2024
	Float valve (Pegler 855 or equivalent)		
Q018	Supplying & fixing 20mm dia. brass float valve with necessary fittings	**Nos**	**4,129**
Q019	Supplying & fixing 25mm dia. brass float valve with necessary fittings	**Nos**	**5,244**
Q020	Supplying & fixing 32mm dia. brass float valve with necessary fittings	**Nos**	**5,998**
Q021	Supplying & fixing 40mm dia. brass float valve with necessary fittings	**Nos**	**23,905**
	Foot valve - Copper		
Q022	Supplying & fixing 32mm dia. Copper foot valve with necessary fittings	**Nos**	**12,793**
Q023	Supplying & fixing 50mm dia. Copper foot valve with necessary fittings	**Nos**	**22,343**
Q024	Supplying & fixing 63mm dia. Copper foot valve with necessary fittings	**Nos**	**30,939**
	Foot valve PVC		
Q025	Supplying & fixing 32mm dia. PVC foot valve with necessary fittings (L/D or equivalent)	**Nos**	**2,225**
Q026	Supplying & fixing 40mm dia. PVC foot valve with necessary fittings (L/D or equivalent)	**Nos**	**2,429**
Q027	Supplying & fixing 50mm dia. PVC foot valve with necessary fittings (L/D or equivalent)	**Nos**	**4,220**
Q028	Supplying & fixing 63mm dia. PVC foot valve with necessary fittings (L/D or equivalent)	**Nos**	**5,028**
Q029	Supplying & fixing 75mm dia. PVC foot valve with necessary fittings (L/D or equivalent)	**Nos**	**7,107**
Q030	Supplying & fixing 90mm dia. PVC foot valve with necessary fittings (L/D or equivalent)	**Nos**	**8,157**
	Close coupled water closet suite (white) -Imported		
Q031	Supplying & fixing, close coupled water closet suite, white, (4/2.6 Lit) with water closet Pan, Cistern, Seat & Seat cover and trap etc.: complete. (BECA-American standards) *Prime Cost of, Close coupled water closet suite,white (BECCA-Amarican standerds)=129360*	**Nos**	**136,532**
	Close coupled water closet suite (white)-Manufactured in Sri Lanka.		
Q032	Supplying & fixing, Vitreous china floor standing close coupled, Water Closet (toilet) suite (white / Colour) with wash down 6/3 liter dual flushing. Has a horizontal outlet and cistern with water inlet from bottom. Complete with Seat, Seat cover and concealed trap etc. . (Make: Rocell , Model: URBAN-D) *Prime Cost of, Close coupled water closet suite,white (Urban D-Rocell)=42915*	**Nos**	**50,087**

Construction BSR 2024

for

Department of Buildings ***(Metric Version)***

Item Code	Item Description	Unit	Basic Rate 2024
Q033	Supplying & fixing, Vitreous china floor standing close coupled, Water Closet (toilet) suite(White/ Colour) with wash down 6/3 liter dual flushing. Has a horizontal outlet and cistern with water inlet from bottom. Complete with Seat, Seat cover and concealed trap etc. . (Make: Rocell , Model: DUNE) *Prime Cost of, Close coupled water closet suite,white (Dune-Rocell)=51133*	**Nos**	**58,305**
Q034	Supplying & fixing, Vitreous china floor standing close coupled, Water Closet (toilet) suite with wash down 6/3 liter dual flushing. Has horizontal outlet and two lateral holes for bottom water connection. Cistern with water inlet from bottom. Complete with Seat, Seat cover and concealed trap etc. . (Make: Rocell , Model: INTENCE) *Prime Cost of, Close coupled water closet suite,white (Intence-Rocell)=55514*	**Nos**	**62,686**
Q035	Supplying & fixing, Vitreous china floor standing close coupled, Water Closet (toilet) suite with wash down 6/3 liter dual flushing. Has horizontal outlet and two lateral holes for bottom water connection. Cistern with water inlet from bottom. Complete with Seat, Seat cover and concealed trap etc. . (Make: Rocell , Model: Elements Aqua) *Prime Cost of, Element aqua water closet with seat cover (Rocell)=75053*	**Nos**	**82,225**
Q036	Supplying & fixing, Vitreous china floor standing close coupled, Water Closet (toilet) suite with wash down 6/3 liter dual flushing. Has horizontal outlet and two lateral holes for bottom water connection. Cistern with water inlet from bottom. Complete with Seat, Seat cover and concealed trap etc. . (Make: Rocell , Model: Aqua+) *Prime Cost of, Aqua + water closet with seat cover (Rocell)=82448*	**Nos**	**89,620**
Q037	Supplying & fixing, Vitreous china floor standing close coupled, Water Closet (toilet) suite with wash down 6/3 liter dual flushing. Has horizontal outlet and two lateral holes for bottom water connection. Cistern with water inlet from bottom. Complete with Seat, Seat cover and concealed trap etc. . (Make: Rocell , Model: Summer Blue) *Prime Cost of, Summer Blue closet with seat cover (Rocell)=155402*	**Nos**	**162,574**

Construction BSR 2024

for

Department of Buildings ***(Metric Version)***

Item Code	Item Description	Unit	Basic Rate 2024
Q038	Supplying & fixing, Vitreous china floor standing close coupled, Water Closet (toilet) suite with wash down 6/3 liter dual flushing. Has horizontal outlet and two lateral holes for bottom water connection. In-Wall Tank Cistern with water inlet from bottom. Complete with Seat, Seat cover and concealed trap etc. . (Make: Rocell , Model: Eternity) *Prime Cost of, Eternity water closet with seat cover (Rocell)=132028*	**Nos**	**143,137**
Q039	Supplying & fixing, Vitreous china floor standing close coupled, Water Closet (toilet) suite with wash down 6/3 liter dual flushing. Has horizontal outlet and two lateral holes for bottom water connection. In-Wall Tank Cistern with water inlet from bottom. Complete with Seat, Seat cover and concealed trap etc. . (Make: Rocell , Model: Urbanity) *Prime Cost of, Urbanity water closet with seat cover (Rocell)=132758*	**Nos**	**143,867**
Q040	Supplying & fixing, Vitreous china floor standing close coupled, Water Closet (toilet) suite with wash down 6/3 liter dual flushing. Has horizontal outlet and two lateral holes for bottom water connection. In-Wall Tank Cistern with water inlet from bottom. Complete with Seat, Seat cover and concealed trap etc. . (Make: Rocell , Model: Escape) *Prime Cost of, Escape closet with seat cover (Rocell)=97697*	**Nos**	**108,806**
	Bidet, pedestal type, Manufactured in Sri Lanka.		
Q041	Supplying & fixing Vitreous china floor standing bidet (white colour), Nominal size (560mm x 370mm) floor to Rim height 407mm, complete with overflow hole, deck mounted single hole center set bidet faucet. (Dune-Rocell) Faucets not included *Prime Cost of, Floor standing bidet (white colour),(22" x 14½") (Dune-Rocell)=20453*	**Nos**	**22,859**
Q042	Supplying & fixing Vitreous china floor standing bidet (white colour), Nominal size (560mm x 394mm) floor to Rim height 420mm, complete with overflow hole, deck mounted single hole center set bidet faucet.(Urband D-Rocell) Faucets not included *Prime Cost of, Floor standing bidet (white colour),(22"x15½") (Urband D-Rocell)=20453*	**Nos**	**22,859**
	Closet-squatting type		
Q043	Supplying & fixing closet, squatting type, with trap. *Prime Cost of, Squatting pan and trap (Indian)=4410*	**Nos**	**10,917**

Construction BSR 2024

for

Department of Buildings ***(Metric Version)***

Item Code	Item Description	Unit	Basic Rate 2024
	Squatting pan- European		
Q044	Supplying and fixing foot rest type squatting pan and trap colour to working order.(American standards) *Prime Cost of, Squtting Pan & Trap -(American standerds)-S.No:100F=57131*	**Nos**	**63,687**
	Closet squatting type (Indian or equivalent)		
Q045	Supplying & fixing closet squatting type with trap complete with cistern plastic flush pipe etc. *Prime Cost of, Closet squatting type with foot rest -Indian =4725*	**Nos**	**24,752**
	Urinal Imported- Twyford		
Q046	Supplying and fixing (New wash brook) urinal.(American standards) *Prime Cost of, New wash brook urinal.(American standerds)=116340*	**Nos**	**119,631**
Q047	Supplying & fixing Wall urinal with brackets.(American standards) *Prime Cost of, Wall urinal with brackets.(American standerds)=62717*	**Nos**	**63,449**
	Urinal - Manufactured in Sri Lanka.		
Q048	Supplying & fixing Wall urinal with Flush Valve.(Flo Point Urinal - Rocell) *Prime Cost of, Flo point urinal with F.V (Rocell)=47663*	**Nos**	**48,395**
Q049	Supplying & fixing Wall urinal with Flush Valve.(Dew Point Urinal - Rocell) *Prime Cost of, Dew point urinal with F.V (Rocell)=36980*	**Nos**	**37,712**
Q050	Supplying & fixing Wall urinal with Sensor.(Flo Point Urinal - Rocell) *Prime Cost of, Flo point urinal withSensor (Rocell)=75053*	**Nos**	**75,785**
Q051	Supplying & fixing Wall urinal with Sensor.(Dew Point Urinal - Rocell) *Prime Cost of, Dew point urinal withSensor (Rocell)=57523*	**Nos**	**58,255**
	Sink		
Q052	Supplying & fixing sink, glazed, earthenware 762mm x 508mm x 203mm with waste plug, brackets etc. complete. *Prime Cost of, Sink, glazed, earthenware 30" x20"x8" waste plug, chain=11156*	**Nos**	**15,739**
Q053	Supplying & fixing sink, glazed earthenware 610mm x 458mm x 203mm with waste plug, brackets etc., complete. *Prime Cost of, Sink, glazed earthenware 24" x 18" x 8" waste plug, chain =9608*	**Nos**	**14,191**

Construction BSR 2024

for

Department of Buildings ***(Metric Version)***

Item Code	Item Description	Unit	Basic Rate 2024
	Stainless steel kitchen sink		
Q054	Supplying & fixing approved quality, stainless steel kitchen sink with single bowl & draining board with necessary waste plug, brackets etc.: *Prime Cost of, Stainless steel kitchen sink with single bowl & draining board with necessary waste plug, brackets etc:=13808*	**Nos**	**15,147**
Q055	Supplying & fixing approved quality, stainless steel kitchen sink with double bowl & draining board with necessary waste plug, brackets etc.: *Prime Cost of, Stainless steel kitchen sink with double bowl & draining board with necessary waste plug, brackets etc:=35175*	**Nos**	**36,842**
Q056	Supplying & fixing 800mm X510mm stainless steel kitchen sink with single bowl & draining board with necessary waste plug, brackets etc.: (Teka or Equivalent) *Prime Cost of, SS kitchen sink with single bowl teka=32099*	**Nos**	**33,438**
Q057	Supplying & fixing 1600mm X 510mm stainless steel kitchen sink with double bowl & draining board with necessary waste plug, brackets etc.: (Teka or Equivalent) *Prime Cost of, SS kitchen sink with doubl bowl teka=51592*	**Nos**	**53,259**
	Wash Basin		
Q058	supplying and fixing Lavatory wash basin with pedestal (American Standard or equivalent) *Prime Cost of, wash basin & pedastal (American Standerd)=53771*	**Nos**	**56,610**
	Wash Basin (local Bath wear)		
Q059	Supplying & fixing Vitreous China floor standing wash basin (white colour) having nominal side of (584mm x 457mm) with universal height pedestal of floor to Rim height 838mm, over flow hole and single tap hole in center, including pedestal, Wash basin fixing kit. (Urband D-Rocell) □ Cupling, Faucets, waste pipe, paid separately *Prime Cost of, Wash basin (white colour), (23"x 18") with universal height pedestal (Urband D-Rocell)=22644*	**Nos**	**26,407**
Q060	Supplying & fixing Vitreous China floor standing wash basin (white colour) having nominal side of (622mm x 483mm) with universal height pedestal of floor to Rim height 825mm, over flow hole and single tap hole in center, including pedestal, Wash basin fixing kit. (Dune-Rocell) □ Cupling, pipe, paid separately *Prime Cost of, Wash basin(24½"x 19") with universal height pedestal (Dune-Rocell)=22736*	**Nos**	**26,499**

Construction BSR 2024

for

Department of Buildings ***(Metric Version)***

Item Code	Item Description	Unit	Basic Rate 2024
Q061	Supplying & fixing Vitreous China floor standing wash basin (white colour) having nominal side of (622mm x 483mm) with universal height pedestal of floor to Rim height 825mm, over flow hole and single tap hole in center, including pedestal, Wash basin fixing kit. (Intense-Rocell) □ Cupling, pipe, paid separately *Prime Cost of, Wash basin (white), (24½"x 19") with universal height pedestal (Intense-Rocell)=30314*	**Nos**	**34,077**
Q062	Supplying & fixing Vitreous China floor standing wash basin (white colour) having nominal side of (622mm x 483mm) with universal height pedestal of floor to Rim height 825mm, over flow hole and single tap hole in center, including pedestal, Wash basin fixing kit. (Elements Aqua-Rocell) □ Cupling, pipe, paid separately *Prime Cost of, Element aqua wash basin with pedestal (Rocell)=34058*	**Nos**	**37,821**
Q063	Supplying & fixing Vitreous China floor standing wash basin (white colour) having nominal side of (622mm x 483mm) with universal height pedestal of floor to Rim height 825mm, over flow hole and single tap hole in center, including pedestal, Wash basin fixing kit. (Aqua+ -Rocell) □ Cupling, pipe, paid separately *Prime Cost of, Aqua + wash basin with pedestal (Rocell)=34423*	**Nos**	**38,186**
Q064	Supplying & fixing Vitreous China floor standing wash basin (white colour) wall mounted brackets, over flow hole and single tap hole in center, Wash basin fixing kit. (Summer Blue-Rocell) □ Cupling, pipe, paid separately *Prime Cost of, Summer Blue wash basin (Rocell)=62543*	**Nos**	**66,306**
Q065	Supplying & fixing Vitreous China floor standing wash basin (white colour) wall mounted brackets, over flow hole and single tap hole in center, Wash basin fixing kit. (Eternity-Rocell) □ Cupling, pipe, paid separately *Prime Cost of, Eternity wash basin with wall mount kit(Rocell)=29491*	**Nos**	**33,254**
Q066	Supplying & fixing Vitreous China floor standing wash basin (white colour) wall mounted brackets, over flow hole and single tap hole in center, Wash basin fixing kit. (Urbanity-Rocell) □ Cupling, pipe, paid separately *Prime Cost of, Urbanity wash basin with wall mount kit(Rocell)=36522*	**Nos**	**40,285**
	Corner wash basin (local Bath wear)		
Q067	Supplying & fixing corner wash basin with one tap, waste plug, new brackets etc.(Aqua Corner - Rocell) *Prime Cost of, Aqua Corner basing with wall mount kit(Rocell)=13422*	**Nos**	**17,516**

Construction BSR 2024

for

Department of Buildings ***(Metric Version)***

Item Code	Item Description	Unit	Basic Rate 2024
	Vanity basin		
Q068	Supplying and fixing Vanity basin 35mm x 406mm white.(Refresh-Twyford or equivalent approved quality) *Prime Cost of, Vanity Basin 25"x16" White-Twyford or equivalent=31605*	**Nos**	**35,058**
	Rubber plugs		
Q069	Supplying & fixing plugs, rubber 32mm to 40mm for wash basins and sinks.	**Nos**	**225**
Q070	Supplying & fixing plugs, rubber 50mm to 63mm for wash basins and sinks.	**Nos**	**262**
	Wooden plugs		
Q071	Bedding in cement mortar 1:2, plugs, wooden, in (Group 6 category A) timber 100mm long, tapered 75mm to 50mm square section, including making holes in walls, floor etc.	**Nos**	**302**
	Bottle traps		
Q072	Supplying & fixing 40mm dia: plastic bottle trap *Prime Cost of, Bottle trap,1¼"dia: plastic . (Indian or eqivalent, approved quality)=854*	**Nos**	**1,042**
Q073	Supplying & fixing 50mm dia: plastic bottle trap *Prime Cost of, Bottle trap,1½"dia: plastic (Indian or eqivalent, approved quality)=845*	**Nos**	**1,033**
Q074	Supplying & fixing 63mm dia: plastic bottle trap *Prime Cost of, Bottle trap, 2" dia: plastic.=1155*	**Nos**	**1,343**
Q075	Supplying & fixing 40mm dia: bottle trap stainless steel approved quality. *Prime Cost of, Bottle trap,1¼" dia: stainless steel =5775*	**Nos**	**5,963**
Q076	Supplying & fixing 50mm square bottle trap stainless steel approved quality. *Prime Cost of, Bottle trap, 1½"dia: stainless steel =7875*	**Nos**	**8,063**
	Bib Taps (Metallic)		
Q077	Supplying & fixing brass (Chromium plated), bib taps, 20mm (Rocell or equivalent, approved quality) *Prime Cost of, Bib tap,½" dia: brass (Chinees or eqivalent, approved quality)=1743*	**Nos**	**2,006**

Construction BSR 2024

for

Department of Buildings ***(Metric Version)***

Item Code	Item Description	Unit	Basic Rate 2024
	Bib Taps (Plastic)		
Q078	Supplying & fixing Plastic Bib Tap 20mm dia. (T- Handle) (S-Lon or Equivalent.) *Prime Cost of, Plastic Bib Tap ½" dia. (T- Handle) (S-Lon or Equi.) =602*	**Nos**	**834**
Q079	Supplying & fixing Plastic Bib Tap 20mm dia. (Round- Handle)(S-Lon or Equivalent.) *Prime Cost of, Plastic Bib Tap ½" dia. (Round- Handle) (S-Lon or Equi.)=789*	**Nos**	**1,021**
Q080	Supplying & fixing Plastic Bib Tap 25mm dia. (T- Handle) (S-Lon or Equivalent.) *Prime Cost of, Plastic Bib Tap ¾" dia. (T- Handle) (S-Lon or Equi.)=898*	**Nos**	**1,130**
Q081	Supplying & fixing Plastic Bib Tap 25mm dia. (Round- Handle)(S-Lon or Equivalent.) *Prime Cost of, Plastic Bib Tap ¾" dia. (Round- Handle) (S-Lon or Equi.) =1017*	**Nos**	**1,249**
Q082	Supplying & fixing Plastic long, Neck Bib Tap 20mm dia. (T- Handle) (S-Lon or Equivalent.) *Prime Cost of, Plastic Bib Tap long Neck ½" dia. (T- Handle) (S-Lon or Equi.) =591*	**Nos**	**823**
Q083	Supplying & fixing Plastic Bib Tap, long Neck 20mm dia. (Round- Handle)(S-Lon or Equivalent.) *Prime Cost of, Plastic Bib Tap long Neck ½" dia. (Round- Handle) (S-Lon or Equi.)=713*	**Nos**	**945**
	Swan-Neck tap-(Metallic)		
Q084	Supplying & fixing chromium plated swan-neck tap 20mm with necessary specials. *Prime Cost of, Chromium plated swan-neck tap ½" (Dura Life Plumber)=13125*	**Nos**	**13,661**
	Swan-Neck tap-(Plastic)		
Q085	Supplying & fixing Plastic Swan- tap 20mm dia. (T- Handle) (S-Lon or Equivalent.) *Prime Cost of, Plastic Swan Tap ½" dia. (S-Lon or Equi.)(T- Handle)=2896*	**Nos**	**3,432**

Construction BSR 2024

for

Department of Buildings ***(Metric Version)***

Item Code	Item Description	Unit	Basic Rate 2024
Q086	Supplying & fixing Plastic Swan-Neck tap 20mm dia. (Round- Handle)(S-Lon or Equivalent.) *Prime Cost of, Plastic Swan Neck Tap ½" dia. (S-Lon or Equi.) (Round-Handle)=2896*	**Nos**	**3,432**
	Chromium plated angle Valves 20mm		
Q087	Supplying & fixing chromium plated angle tap 20mm with necessary specials, imported, approved quality. (Rocell or equivalent). *Prime Cost of, Chromium plated Angle valve ½" (Duro)=3413*	**Nos**	**3,949**
Q088	Supplying & fixing chromium plated angle tap 20mm with necessary specials, imported, approved quality. (Plumber or equivalent). *Prime Cost of, Chromium plated Angle valve ½" (Plumber) nectar=6090*	**Nos**	**6,626**
	Angle Valves (Plastic)		
Q089	Supplying & fixing Plastic Angle Tap 20mm dia. (T- Handle) (S-Lon or Equivalent.) *Prime Cost of, Plastic Right Angle Tap ½" dia. (T- Handle) (S-Lon or Equi.)=899*	**Nos**	**1,435**
Q090	Supplying & fixing Plastic Angle 20mm dia. (Round- Handle)(S-Lon or Equivalent.) *Prime Cost of, Plastic Right Angle Tap ½" dia. (Round- Handle) (S-Lon or Equi.) =1017*	**Nos**	**1,553**
	Chromium plated basin tap 20mm		
Q091	Supplying and fixing basin tap. *Prime Cost of, Basin tap ½" dia.(Twyford or equi)=13519*	**Nos**	**13,878**
	Self Closing taps		
Q092	Supplying & fixing self closing tap - 20mm chromium plated. *Prime Cost of, Self closing tap 20mm Chromium finish. (Rocell or equivalent) .=12691*	**Nos**	**12,954**
	Sensor taps		
Q093	Supplying & fixing sensor taps, 20mm Chromium plated. *Prime Cost of, Sensor tap 20mm Chromium finish (Rocell or equivalent) .=26752*	**Nos**	**27,015**
	Stop Taps (Plastic)		
Q094	Supplying & fixing Plastic Stop Taps 20mm dia. (T- Handle) (S-Lon or Equivalent.) *Prime Cost of, Plastic Stop Tap ½" dia. (T- Handle) (S-Lon or Equi.)=654*	**Nos**	**1,073**

Construction BSR 2024

for

Department of Buildings ***(Metric Version)***

Item Code	Item Description	Unit	Basic Rate 2024
Q095	Supplying & fixing Plastic Stop Taps 20mm dia. (Round- Handle)(S-Lon or Equivalent.) *Prime Cost of, Plastic Stop Tap ½" dia. (Round- Handle) (S-Lon or Equi.)=899*	**Nos**	**1,318**
Q096	Supplying & fixing Plastic Stop Taps 25mm dia. (T- Handle) (S-Lon or Equivalent.) *Prime Cost of, Plastic Stop Tap ¾" dia. (T- Handle) (S-Lon or Equi.)=997*	**Nos**	**1,416**
Q097	Supplying & fixing Plastic Stop Taps 25mm dia. (Round- Handle)(S-Lon or Equivalent.) *Prime Cost of, Plastic Stop Tap ¾" dia. (Round- Handle) (S-Lon or Equi.) =1320*	**Nos**	**1,739**
Q098	Supplying & fixing Plastic Stop Taps 32mm dia. (T- Handle) (S-Lon or Equivalent.) *Prime Cost of, Plastic Stop Tap 1" dia. (T- Handle) (S-Lon or Equi.)=1359*	**Nos**	**1,778**
Q099	Supplying & fixing Plastic Stop Taps 32mm dia. (Round- Handle)(S-Lon or Equivalent.) *Prime Cost of, Plastic Stop Tap 1" dia. (Round- Handle) (S-Lon or Equi.)=1616*	**Nos**	**2,035**
	Garden Taps (brass)		
Q100	Supplying & fixing garden tap 20mm dia: brass, heavy quality, with necessary specials, imported, approved quality. *Prime Cost of, Garden tap ½" brass,heavy quality imported=6899*	**Nos**	**7,131**
	Garden Taps (Plastic)		
Q101	Supplying & fixing Plastic Garden Tap 20mm dia. (T- Handle) (S-Lon or Equivalent.) *Prime Cost of, Plastic Garden Tap ½" dia. (T- Handle) (S-Lon or Equi.) =831*	**Nos**	**1,063**
Q102	Supplying & fixing Plastic Garden Tap 20mm dia. (Round- Handle)(S-Lon or Equivalent.) *Prime Cost of, Plastic Garden Tap ½" dia. (Round- Handle) (S-Lon or Equi.)=1017*	**Nos**	**1,249**
	Pillar cocks		
Q103	Supplying & fixing pillar cocks 20mm Chromium plated, to basins. (Plumber or equivalent) *Prime Cost of, Pillar cocks ½" Chromium plated, =4410*	**Nos**	**4,946**

Construction BSR 2024

for

Department of Buildings ***(Metric Version)***

Item Code	Item Description	Unit	Basic Rate 2024
	Pillar taps		
Q104	Supplying and fixing 20mm dia: chromium plated Pillar tap. (T- handle) *Prime Cost of, Chromium plated Pillar tap, ½" dia:. (Amarican Standerd)-4604=12369*	**Nos**	**12,601**
Q105	Supplying and fixing 25mm dia: chromium plated Pillar tap. (Round- handle) *Prime Cost of, Pillar cocks ¾"Chromium plated,(Plumber or eqivalent) =8295*	**Nos**	**8,831**
	Basin Piller Taps (Plastic)		
Q106	Supplying & fixing Plastic Basin Piller tap 20mm dia. (Round- Handle)(S-Lon or Equivalent.) *Prime Cost of, Plastic Basin Piller Tap ½" dia. (S-Lon or Equi.) =1754*	**Nos**	**2,290**
	Stop cock		
Q107	Supplying & fixing stop cock, brass 20mm dia.	**Nos**	**2,394**
Q108	Supplying & fixing stop cock, brass 25mm dia.	**Nos**	**3,260**
Q109	Supplying & fixing stop cock, brass 32mm dia.	**Nos**	**3,837**
Q110	Supplying & fixing stop cock, brass 40mm dia.	**Nos**	**4,415**
Q111	Supplying & fixing stop cock, brass 50mm dia.	**Nos**	**5,897**
Q112	Supplying & fixing stop cock, brass 63mmdia.	**Nos**	**9,155**
Q113	Supplying & fixing stop cock, chromium plated 20mm dia .	**Nos**	**3,606**
	Hooks for pipes		
Q114	Hooks for 20mm pipes, supplying and fixing.	**Nos**	**40**
Q115	Hooks for 25mm pipes, supplying and fixing.	**Nos**	**42**
Q116	Hooks for 32mm pipes, supplying and fixing.	**Nos**	**49**
Q117	Hooks for 40mm pipes, supplying and fixing.	**Nos**	**60**
Q118	Hooks for 50mm pipes, supplying and fixing.	**Nos**	**64**
Q119	Hooks for pipes, available, fixing.	**Nos**	**38**
	Jam Nuts		
Q120	Jam Nuts, G.I 1/2"(12.5mm) supplying and fixing.	**Nos**	**98**
Q121	Jam Nuts, G.I 3/4"(20mm) supplying and fixing.	**Nos**	**103**
Q122	Jam Nuts, G.I 1"(25mm) supplying and fixing.	**Nos**	**108**
Q123	Jam Nuts, G.I 1 1/4"(31.25mm) supplying and fixing.	**Nos**	**114**
Q124	Jam Nuts, G.I 1 1/2"(37.5mm) supplying and fixing.	**Nos**	**119**

Construction BSR 2024

for

Department of Buildings ***(Metric Version)***

Item Code	Item Description	Unit	Basic Rate 2024
Q125	Jam Nuts, G.I 2"(50mm) supplying and fixing.	**Nos**	**135**
	Nipples, G.I		
Q126	Nipples, G.I 1/2"(12.5mm) Supplying & fixing.	**Nos**	**375**
Q127	Nipples, G.I 3/4"(20mm) Supplying & fixing	**Nos**	**427**
Q128	Nipples, G.I 1"(25mm) Supplying & fixing.	**Nos**	**480**
Q129	Nipples, G.I 1 1/4"(31.25mm) Supplying & fixing.	**Nos**	**690**
Q130	Nipples, G.I 1 1/2"(37.5mm) Supplying & fixing.	**Nos**	**795**
Q131	Nipples, G.I 2"(50mm) Supplying & fixing.	**Nos**	**1,057**
	Pipes G.I		
Q132	Pipes G.I 1/2"(12.5mm) heavy quality supplying and fixing (fittings to be paid for separately) including any necessary trenching, backfilling and making good, or fixing to walls (pipe hooks to be paid for separately)	**m**	**1,405**
Q133	Pipes G.I 3/4"(20mm) heavy quality supplying and fixing (fittings to be paid for separately) including any necessary trenching, backfilling and making good, or fixing to walls (pipe hooks to be paid for separately).	**m**	**1,674**
Q134	Pipes, G.I 1"(25mm) heavy quality supplying and fixing (fittings to be paid for separately) including any necessary trenching, backfilling and making good, or fixing to walls. (Pipe hooks to be paid for separately)	**m**	**2,235**
Q135	Pipes, G.I 1 1/4"(31.25mm) heavy quality supplying and fixing (fittings to be paid for separately) including any necessary trenching, backfilling and making good, or fixing to walls. (Pipe hooks to be paid for separately)	**m**	**3,064**
Q136	Pipes, G.I 1 1/2"(37.5mm) heavy quality supplying and fixing (fittings to be paid for separately) including any necessary trenching, backfilling and making good, or fixing to walls. (Pipe hooks to be paid for separately)	**m**	**3,255**
Q137	Pipes, G.I 2"(50mm) heavy quality supplying and fixing (fittings paid for separately) including any necessary trenching, backfilling and making good, or fixing to walls. (Pipe hooks to be paid for separately)	**m**	**4,315**
Q138	Pipes, G.I 2 1/2" (60mm) heavy quality supplying and fixing (fittings paid for separately) including any necessary trenching, backfilling and making good, or fixing to walls. (Pipe hooks to be paid for separately)	**m**	**5,493**
Q139	Pipes, G.I 3"(75mm) heavy quality supplying and fixing (fittings to be paid for separately) including any necessary trenching, backfilling and making good, or fixing to walls. (Pipe hooks to be paid for separately)	**m**	**7,452**
	GI Plugs		
Q140	Plugs, G.I 1/2"(12.5mm) supplying and fixing.	**Nos**	**265**
Q141	Plugs, G.I 3/4" (20mm)supplying and fixing.	**Nos**	**370**

Construction BSR 2024

for

Department of Buildings ***(Metric Version)***

Item Code	Item Description	Unit	Basic Rate 2024
Q142	Plugs, G.I 1"(25mm) supplying and fixing.	**Nos**	**423**
Q143	Plugs, G.I 1/4"(31.25mm) supplying and fixing.	**Nos**	**528**
Q144	Plugs, G.I 1 1/2"(37.5mm) supplying and fixing.	**Nos**	**633**
Q145	Plugs, G.I 2"(50mm) supplying and fixing.	**Nos**	**843**
	Socket G.I		
Q146	Socket G.I 1/2"(12.5mm) plain supplying & fixing.	**Nos**	**424**
Q147	Socket, G.I 3/4"(20mm) plain supplying and fixing.	**Nos**	**529**
Q148	Socket, G.I 1" (25mm) plain supplying and fixing.	**Nos**	**687**
Q149	Socket, G.I 1 1/4" (31.25mm) plain supplying and fixing.	**Nos**	**739**
Q150	Socket, G.I 1 1/2"(37.5mm) plain supplying and fixing.	**Nos**	**844**
Q151	Socket, G.I 2"(50mm) plain supplying and fixing.	**Nos**	**1,107**
Q152	Socket, G.I 3"(75mm) plain supplying and fixing.	**Nos**	**1,658**
Q153	Socket, G.I reducing 3/4"(20mm) to smaller sizes supplying and fixing.	**Nos**	**477**
Q154	Socket, G.I reducing 1" (25mm)to smaller size supplying and fixing.	**Nos**	**477**
Q155	Socket, G.I reducing 1 1/4"(31.25mm) to smaller sizes supplying and fixing.	**Nos**	**897**
Q156	Socket, G.I reducing 1 1/2"(37.5mm) to smaller sizes supplying and fixing.	**Nos**	**1,002**
Q157	Socket G.I reducing 2"(50mm) to smaller sizes, supplying and fixing.	**Nos**	**1,290**
Q158	Sockets G.I reducing 3"(75mm) to smaller sizes supplying and fixing.	**Nos**	**1,523**
	Plastishell (Single Layer) water tank (Slon PE+ or Equivalent)		
Q159	Supplying and fixing Plastishell (Single Layer) water tank 350 liter capacity. (fittings paid for separately). *Prime Cost of, Water tank350 literPlastishell.=23119*	**Nos**	**26,682**
Q160	Supplying and fixing Plastishell (Single Layer) water tank 500 liter capacity. (fittings paid for separately). *Prime Cost of, Water tank 500lit Plastishell.=24273*	**Nos**	**27,836**
Q161	Supplying and fixing Plastishell (Single Layer) water tank 750 liter capacity. (fittings paid for separately). *Prime Cost of, Water tank 750 liter Plastishell.=39958*	**Nos**	**44,085**
Q162	Supplying and fixing Plastishell (Single Layer) water tank 1000 liter capacity. (fittings paid for separately). *Prime Cost of, Water tank 1000lit Plastishell.=49535*	**Nos**	**53,662**

Construction BSR 2024

for

Department of Buildings ***(Metric Version)***

Item Code	Item Description	Unit	Basic Rate 2024
	Plastishell (Triple Layer) water tank (Slon PE+ Premium or Equivalent)		
Q163	Supplying and fixing Plastishell (Triple Layer) water tank,5000 liter capacity. (fittings paid for separately). *Prime Cost of, Water tank 5000lit Plastishell.=196949*	**Nos**	**202,949**
	Floater switch		
Q164	Supplying and fixing floater switch with necessary fittings to over head water tank. *Prime Cost of, Floater switch =3500*	**Nos**	**6,125**
	Tees		
Q165	Tees, G.I 1/2"(12.5mm) equal supplying and fixing.	**Nos**	**494**
Q166	Tees, G.I 3/4" (20mm) equal supplying and fixing.	**Nos**	**652**
Q167	Tees, G.I 1"(25mm) equal supplying and fixing.	**Nos**	**757**
Q168	Tees, G.I 1 1/4"(31.25mm) equal supplying and fixing.	**Nos**	**967**
Q169	Tees, G.I 1 1/2"(37.5mm) equal supplying and fixing.	**Nos**	**1,072**
Q170	Tees, G.I 2"(50mm) equal, supplying and fixing.	**Nos**	**1,492**
	Soap tray/dish		
Q171	Supplying and fixing chromium plated soap tray. (American Standard or Equivalent.) *Prime Cost of, Chromium plated soap tray.(American Standerd)-2501=20045*	**Nos**	**20,615**
Q172	Supplying and fixing soap dish (American Standard or Equivalent.) *Prime Cost of, Soap dish (American Standerd)-6582=10616*	**Nos**	**11,186**
	Soap dispenser		
Q173	Supplying & fixing soap dispenser (American Standard or Equivalent.) *Prime Cost of, Soap dispenser 800cc (Amarican Standerd)=77438*	**Nos**	**77,797**
	Towel rail		
Q174	Supplying & fixing chromium plated Towel rail (American Standard or Equivalent.-S. No:6588) , 600mm long and , 25mm dia. with necessary rawl plugs and screws. *Prime Cost of, Towel rail (American Standerd)-6588=18953*	**Nos**	**19,601**
	Paper holder SEVA		
Q175	Supplying & fixing SEVA paper holder (American Standard or Equivalent.) complete to working order. *Prime Cost of, SEVA paper holder (American Standerd)=15330*	**Nos**	**15,606**

Construction BSR 2024

for

Department of Buildings ***(Metric Version)***

Item Code	Item Description	Unit	Basic Rate 2024
	Tooth brush holder		
Q176	Supplying & fixing tooth brush holder (American Standard or Equivalent.) complete to working order. *Prime Cost of, Tooth brushr holder (American Standerd)-6582=20213*	**Nos**	**20,489**
	Robe hook (SEVA)		
Q177	Supplying & fixing SEVA Robe hook (American Standard or Equivalent.) complete to working order. *Prime Cost of, SEVA Robe hook (American Standerd)=13545*	**Nos**	**13,821**
	Bath room mirror,		
Q178	Supplying & fixing mirror, beveled, bath room type, oval shape, 508mm x 406mm Max. and min. dimensions, to wall with Rawl plugs and chromium plated fittings. *Prime Cost of, Mirror with fittings 20"x16"(ovel shaped)=6668*	**Nos**	**8,129**
Q179	Supplying & fixing 610mm x 457mm, 5mm thickness beveled rectangular mirror, to wall with Rawl plugs, noton tape and chromium plated fittings. *Prime Cost of, Mirror with fittings 24"x18"(Rectanguler shaped)=8295*	**Nos**	**9,756**
	Shower rose		
Q180	Supplying & fixing shower Rose 175mm chromium plated.	**Nos**	**3,153**
Q181	Supplying & fixing PVC- 150mm x 20mm shower rose.	**Nos**	**777**
	Plastic Jet Shower rose		
Q182	Supplying & fixing Plastic Jet Shower Rose 20mm dia. (S-Lon or Equivalent.)	**Nos**	**2,114**
Q183	Supplying & fixing Jet shower complete(American Standard or Equivalent.) *Prime Cost of, Jet shower (Amarican Standerd)(modle 6060/6022)=11792*	**Nos**	**12,048**
	Shower head		
Q184	Supplying & fixing Shower head with arm. (American Standard) *Prime Cost of, Shower head with arm (Amarican Standerd) CF 9026=41276*	**Nos**	**41,532**
	Bidet spray imported		
Q185	Supplying and fixing bidet spray - Plastic *Prime Cost of, Bidet spray -Plastic=1612*	**Nos**	**2,175**
Q186	Supplying and fixing bidet spray Chromium Plated (Plumber or equivalent) *Prime Cost of, Bidet spray imported (Plumber)=7140*	**Nos**	**7,783**

Construction BSR 2024

for

Department of Buildings ***(Metric Version)***

Item Code	Item Description	Unit	Basic Rate 2024
	Bends P.V.C		
Q187	Supplying & fixing bends P.V.C 20mm.	**Nos**	**165**
Q188	Supplying & fixing bends P.V.C 25mm.	**Nos**	**203**
Q189	Supplying & fixing bends P.V.C 32mm.	**Nos**	**265**
Q190	Supplying & fixing bends P.V.C 40mm.	**Nos**	**439**
Q191	Supplying & fixing bends P.V.C 50mm.	**Nos**	**652**
Q192	Supplying & fixing bends P.V.C 63mm.	**Nos**	**1,070**
Q193	Supplying & fixing bends P.V.C 90mm.	**Nos**	**3,753**
	Elbows P.V.C		
Q194	Supplying & fixing elbows P.V.C 20mm.	**Nos**	**142**
Q195	Supplying & fixing elbows P.V.C 25mm.	**Nos**	**189**
Q196	Supplying & fixing elbows P.V.C 32mm.	**Nos**	**207**
Q197	Supplying & fixing elbows P.V.C 40mm.	**Nos**	**271**
Q198	Supplying & fixing elbows P.V.C 50mm.	**Nos**	**421**
Q199	Supplying & fixing elbows P.V.C 63mm.	**Nos**	**585**
Q200	Supplying & fixing elbows P.V.C 90mm.	**Nos**	**1,484**
	Reducing sockets & Tees P.V.C		
Q201	Supplying & fixing sockets reducing P.V.C (25mm x 20mm) to smaller sizes.	**Nos**	**165**
Q202	Supplying & fixing sockets reducing P.V.C (32mm x 25mm) to smaller sizes.	**Nos**	**198**
Q203	Supplying & fixing sockets reducing P.V.C (40mm x 32mm) to smaller sizes.	**Nos**	**265**
Q204	Supplying & fixing sockets reducing P.V.C (50mm x40mm) to smaller sizes.	**Nos**	**345**
Q205	Supplying & fixing sockets reducing P.V.C (63mm x 32mm) to smaller sizes.	**Nos**	**434**
Q206	Supplying & fixing sockets reducing P.V.C (63mm x50mm) to smaller sizes.	**Nos**	**447**
	Reducing Tees P.V.C		
Q207	Supplying & fixing tees reducing P.V.C (25mm x 20mm) to smaller sizes.	**Nos**	**204**
Q208	Supplying & fixing tees reducing P.V.C (32mm x 25mm) to smaller sizes.	**Nos**	**218**
Q209	Supplying & fixing tees reducing P.V.C (40mm x32mm) to smaller sizes.	**Nos**	**363**
Q210	Supplying & fixing tees reducing P.V.C (50mm x 40mm) to smaller sizes.	**Nos**	**519**
Q211	Supplying & fixing tees reducing P.V.C (63mm x 50mm) to smaller sizes.	**Nos**	**799**

Construction BSR 2024

for

Department of Buildings ***(Metric Version)***

Item Code	Item Description	Unit	Basic Rate 2024
Q212	Supplying & fixing tees reducing P.V.C (90mm x 63mm) to smaller sizes.	Nos	1,982
Q213	Supplying & fixing reducing tee P.V.C. (110mm x 63mm)	Nos	3,808
	Repair Sockets & Tees P.V.C		
Q214	Supplying & fixing repair socket P.V.C 20mm.	Nos	154
Q215	Supplying & fixing repair socket P.V.C 25mm.	Nos	181
Q216	Supplying & fixing repair socket P.V.C 32mm.	Nos	212
Q217	Supplying & fixing repair socket P.V.C 40mm.	Nos	265
Q218	Supplying & fixing repair socket P.V.C 50mm.	Nos	363
Q219	Supplying & fixing repair socket P.V.C 63mm.	Nos	630
Q220	Supplying & fixing repair socket P.V.C 90mm.	Nos	1,222
	Valve Socket P.V.C		
Q221	Supplying & fixing valve socket P.V.C 20mm.	Nos	156
Q222	Supplying & fixing valve socket P.V.C 25mm.	Nos	176
Q223	Supplying & fixing valve socket P.V.C 32mm.	Nos	207
Q224	Supplying & fixing valve socket P.V.C 40mm.	Nos	278
Q225	Supplying & fixing valve socket P.V.C 50mm.	Nos	332
Q226	Supplying & fixing valve socket P.V.C 63mm.	Nos	421
Q227	Supplying & fixing valve socket P.V.C 90mm.	Nos	1,133
	Faucet Socket P.V.C		
Q228	Supplying & fixing faucet sockets P.V.C 20mm.	Nos	147
Q229	Supplying & fixing faucet sockets P.V.C 25mm.	Nos	185
Q230	Supplying & fixing faucet sockets P.V.C 32mm.	Nos	203
Q231	Supplying & fixing faucet sockets P.V.C 40mm.	Nos	274
Q232	Supplying & fixing faucet sockets P.V.C 50mm.	Nos	350
Q233	Supplying & fixing faucet sockets P.V.C 63mm.	Nos	443
Q234	Supplying & fixing faucet sockets P.V.C 90mm.	Nos	1,161
	Tapered union without thread P.V.C		
Q235	Supplying & fixing tapered union without thread P.V.C 20mm.	Nos	691
Q236	Supplying & fixing tapered union without thread P.V.C 25mm.	Nos	1,038
Q237	Supplying & fixing tapered union without thread P.V.C 32mm.	Nos	1,093
Q238	Supplying & fixing tapered union without thread P.V.C 40mm.	Nos	1,755

Construction BSR 2024

for

Department of Buildings ***(Metric Version)***

Item Code	Item Description	Unit	Basic Rate 2024
Q239	Supplying & fixing tapered union without thread P.V.C 50mm.	**Nos**	**2,271**
Q240	Supplying & fixing tapered union without thread P.V.C 63mm.	**Nos**	**2,996**
Q241	Supplying & fixing tapered union without thread P.V.C 90mm.	**Nos**	**3,268**
Q242	Supplying & fixing tapered union with thread for P.V.C and metal pipe connection 20mm.	**Nos**	**531**
Q243	Supplying & fixing tapered union 25mm with thread for P.V.C & metal pipe connections.	**Nos**	**631**
Q244	Supplying & fixing tapered union 32mm with thread for P.V.C & metal pipe connections.	**Nos**	**767**
Q245	Supplying & fixing tapered union 40mm with thread for P.V.C & metal pipe connections.	**Nos**	**957**
Q246	Supplying & fixing tapered union 50mm with thread for P.V.C & metal pipe connections.	**Nos**	**1,093**
Q247	Supplying & fixing tapered union 63mm with thread for P.V.C & metal pipe connections.	**Nos**	**1,410**
Q248	Supplying & fixing tapered union 90mm with thread for P.V.C & metal pipe connections.	**Nos**	**3,902**
	Equal tees-P.V.C		
Q249	Supplying & fixing tees equal P.V.C 20mm.	**Nos**	**156**
Q250	Supplying & fixing tees equal P.V.C 25mm.	**Nos**	**207**
Q251	Supplying & fixing tees equal P.V.C 32mm.	**Nos**	**265**
Q252	Supplying & fixing tees equal P.V.C 40mm.	**Nos**	**372**
Q253	Supplying & fixing tees equal P.V.C 50mm.	**Nos**	**545**
Q254	Supplying & fixing tees equal P.V.C 63mm.	**Nos**	**723**
Q255	Supplying & fixing tees equal P.V.C 90mm.	**Nos**	**1,941**
	Plugs, sockets-P.V.C		
Q256	Supplying & fixing plugs P.V.C 20mm.	**Nos**	**132**
Q257	Supplying & fixing plugs P.V.C 25mm.	**Nos**	**164**
Q258	Supplying & fixing plugs P.V.C 32mm	**Nos**	**182**
Q259	Supplying & fixing plugs P.V.C 40mm.	**Nos**	**204**
Q260	Supplying & fixing plugs P.V.C 50mm.	**Nos**	**232**
Q261	Supplying & fixing Plugs P.V.C 63mm.	**Nos**	**286**
Q262	Supplying & fixing plugs P.V.C 90mm.	**Nos**	**894**
Q263	Supplying & fixing sockets plain P.V.C 20mm.	**Nos**	**142**
Q264	Supplying & fixing sockets plain P.V.C 25mm.	**Nos**	**165**

Construction BSR 2024

for

Department of Buildings ***(Metric Version)***

Item Code	Item Description	Unit	Basic Rate 2024
Q265	Supplying & fixing sockets plain P.V.C 32mm.	**Nos**	**203**
Q266	Supplying & fixing sockets plain P.V.C 40mm.	**Nos**	**243**
Q267	Supplying & fixing sockets plain P.V.C 50mm.	**Nos**	**314**
Q268	Supplying & fixing sockets plain P.V.C 63mm.	**Nos**	**394**
Q269	Supplying & fixing sockets plain P.V.C 90mm.	**Nos**	**1,007**
	Pipes P.V.C		
Q270	Supplying & fixing pipes P.V.C, 20mm dia.(PNT 14)- PE.(Fittings paid separately).	**m**	**188**
Q271	Supplying & fixing pipes P.V.C, 25mm dia..(PNT 11)- PE (Fittings paid separately).	**m**	**336**
Q272	Supplying & fixing pipes P.V.C, 32mm dia..(PNT 11)- PE(Fittings paid separately).	**m**	**615**
Q273	Supplying & fixing pipes P.V.C, 40mm dia. .(PNT 11)- PE(Fittings paid separately).	**m**	**872**
Q274	Supplying & fixing pipes P.V.C 50mm dia. .(PNT 11)- PE (Fittings paid separately).	**m**	**1,221**
Q275	Supplying & fixing pipes P.V.C, 63mm dia..(PNT 11)- PE (Fittings paid separately).	**m**	**1,802**
Q276	Supplying & fixing pipes P.V.C 90mm dia. .(PNT 11)- PE (Fittings paid separately).	**m**	**2,849**
	Pipes P.V.C (25% pipe cost included for Specials)	**m**	
Q277	Supplying & fixing pipes P.V.C, 20mm dia. .(PNT 14) including specials. (25% pipe cost included for Specials)	**m**	**237**
Q278	Supplying & fixing pipes P.V.C, 25mm dia. .(PNT 11) including specials. (25% pipe cost included for Specials)	**m**	**421**
Q279	Supplying & fixing pipes P.V.C, 32mm dia. .(PNT 11) including specials. (25% pipe cost included for Specials)	**m**	**738**
Q280	Supplying & fixing pipes P.V.C, 40mm dia. .(PNT 11) including specials. (25% pipe cost included for Specials)	**m**	**1,053**
Q281	Supplying & fixing pipes P.V.C, 50mm dia. .(PNT 11) including specials. (25% pipe cost included for Specials)	**m**	**1,488**
Q282	Supplying & fixing pipes P.V.C, 63mm dia. .(PNT 11) including specials. (25% pipe cost included for Specials)	**m**	**2,209**

Construction BSR 2024

for

Department of Buildings ***(Metric Version)***

Item Code	Item Description	Unit	Basic Rate 2024
	Flexible cord (S--Lon or Equivalent))		
Q283	Supplying and fixing flexible cord -300mm (S-lon or equivalent)	**Nos**	**703**
Q284	Supplying and fixing flexible cord -450mm (S-lon or equivalent)	**Nos**	**884**
Q285	Supplying and fixing flexible cord -600mm (S-lon or equivalent)	**Nos**	**1,054**
Q286	Supplying and fixing flexible cord -1200mm (S-lon or equivalent)	**Nos**	**1,440**
Q287	Supplying and fixing flexible cord -1500mm (S-lon or equivalent)	**Nos**	**1,543**
	Flexible hose		
Q288	Supplying and fixing 20mm dia: Flexible hose (American Standard or Equivalent.) 450mm long *Prime Cost of, Flexible hose (Amarican Standerd) - 18"=2363*	**Nos**	**2,589**
	Plastic gully		
Q289	Supplying & fixing plastic gully grating 150mm x150mm.	**Nos**	**815**
Q290	Providing Catch pit 150mm x150mm x75mm in cement mortar.	**Nos**	**1,099**
	Elbows for down pipe.		
Q291	Supplying & fixing P.V.C. elbows for down pipe.	**Nos**	**832**
	Running head.		
Q292	Supplying & fixing P.V.C. running head.	**Nos**	**1,151**
	Gutter end.		
Q293	Supplying & fixing or replacing, only a square type P.V.C. gutter ends.	**Nos**	**746**
	Gutter Joint.		
Q294	Supplying & fixing or replacing, only a square type P.V.C. gutter joints.	**Nos**	**773**
	Eves gutters (PVC)-Square type		
Q295	Supplying and fixing eves gutters square type PVC with necessary specials, including running heads, miter joints, gutter joints, gutter brackets, gutter ends etc.	**m**	**1,840**
	Down pipes P.V.C		
Q296	Supplying & fixing rain water down pipes P.V.C to wall, with necessary specials, including elbows, sockets, clips etc.	**m**	**1,188**

Construction BSR 2024

for

Department of Buildings ***(Metric Version)***

Item Code	Item Description	Unit	Basic Rate 2024
	R-MECHANICAL INSTALLATIONS		
	Unitary Air Conditioning Equipments		
	Air Cooled inverter Type wall mounted split air conditioners such as L.G., Mitsubishi, Daikin or quivelant (refrigerant zero ODP) of cooling capacity as specified (direct expansion) c/w Refrigerant Piping, Drain line, Insulation, control, brackets and Condensing units c/w motors, compressors, condenser, copper tubes and pre-painted anti-corrosion resin coated aluminium fins, blowers, filter drier, refrigerant..(Refrigirat pipe length of 5m considered inclusive to the rate)		
R001	9000 Btu/Hr	**Nos**	**285,319**
R002	12000 Btu/Hr	**Nos**	**305,719**
R003	18000 Btu/Hr	**Nos**	**338,869**
R004	24000 Btu/Hr	**No.**	**381,066**
	Air Cooled non inverter Type wall mounted split air conditioners such as L.G., Mitsubishi, Daikin or quivelant (refrigerant zero ODP) of cooling capacity as specified (direct expansion) c/w Refrigerant Piping, Drain line, Insulation, control, brackets and Condensing units c/w motors, compressors, condenser, copper tubes and pre-painted anti-corrosion resin coated aluminium fins, blowers, filter drier, refrigerant.(Refrigirat pipe length of 5m considered inclusive to the rate.)		
R005	9000 Btu/Hr	**Nos**	**226,414**
R006	12000 Btu/Hr	**Nos**	**237,124**
R007	18000 Btu/Hr	**Nos**	**274,609**
R008	24000 Btu/Hr	**Nos**	**327,516**
	Air Cooled inverter Type Ceiling mounted split air conditioners such as L.G., Mitsubishi, Daikin or quivelant (refrigerant zero ODP) of cooling capacity as specified (direct expansion) c/w Refrigerant Piping, Drain line, Insulation, control, brackets and Condensing units c/w motors, compressors, condenser, copper tubes and pre-painted anti-corrosion resin coated aluminium fins, blowers, filter drier, refrigerant.(Refrigirat pipe length of 5m considered inclusive to the rate.)		
R009	18000 Btu/Hr	**Nos**	**520,939**
R010	24000 Btu/Hr	**Nos**	**600,621**
R011	36000 Btu/Hr	**Nos**	**793,401**

Construction BSR 2024

for

Department of Buildings ***(Metric Version)***

Item Code	Item Description	Unit	Basic Rate 2024
	Air Cooled non inverter Type Ceiling mounted split air conditioners such as L.G., Mitsubishi, Daikin or quivelant (refrigerant zero ODP) of cooling capacity as specified(direct expansion) c/w Refrigerant Piping, Drain line, Insulation, control, brackets and Condensing units c/w motors, compressors, condenser, copper tubes and pre-painted anti-corrosion resin coated aluminium fins, blowers, filter drier, refrigerant.(Refrigirat pipe length of 5m considered inclusive to the rate.)		
R012	18000 Btu/Hr	**Nos**	**408,484**
R013	24000 Btu/Hr	**Nos**	**504,231**
R014	36000 Btu/Hr	**Nos**	**600,621**
	Air Cooled inverter Type Ceiling Suspended 4 Way Cassete split air conditioners such as L.G., Mitsubishi, Daikin or quivelant (refrigerant zero ODP) of cooling capacity as specified (direct expansion) c/w Refrigerant Piping, Drain line, Insulation, built in drain pumps, control, brackets and Condensing units c/w motors, compressors, condenser, copper tubes and pre-painted anti-corrosion resin coated aluminium fins, blowers, filter drier, refrigerant.(Refrigirat pipe length of 5m considered inclusive to the rate.)		
R015	12000 Btu/Hr	**Nos**	**547,714**
R016	18000 Btu/Hr	**Nos**	**553,069**
R017	24000 Btu/Hr	**Nos**	**643,461**
R018	36000 Btu/Hr	**Nos**	**846,951**
	Air Cooled non inverter Type Ceiling Suspended 4 Way Cassete split air conditioners such as L.G., Mitsubishi, Daikin or quivelant (refrigerant zero ODP) of cooling capacity as specified (direct expansion) c/w Refrigerant Piping, Drain line, Insulation, built in drain pumps, control, brackets and Condensing units c/w motors, compressors, condenser, copper tubes and pre-painted anti-corrosion resin coated aluminium fins, blowers, filter drier, refrigerant.(Refrigirat pipe length of 5m considered inclusive to the rate.)		
R019	18000 Btu/Hr	**Nos**	**440,614**
R020	24000 Btu/Hr	**Nos**	**573,846**
R021	36000 Btu/Hr	**Nos**	**638,106**
	Air Cooled inverter Type Ceiling mounted ducted type split air conditioners such as L.G., Mitsubishi, Daikin or quivelant (refrigerant zero ODP) of cooling capacity as specified (direct expansion) c/w Refrigerant Piping, Drain line, Insulation, control, brackets and Condensing units c/w motors, compressors, condenser, copper tubes and pre-painted anti-corrosion resin coated aluminium fins, blowers, filter drier, refrigerant.(Refrigirat pipe length of 5m considered inclusive to the rate.)		
R022	12000 Btu/Hr	**Nos**	**426,691**
R023	18000 Btu/Hr	**Nos**	**507,016**

Construction BSR 2024

for

Department of Buildings ***(Metric Version)***

Item Code	Item Description	Unit	Basic Rate 2024
R024	24000 Btu/Hr	**Nos**	**613,473**
R025	36000 Btu/Hr	**Nos**	**875,868**
	Air Cooled non inverter Type Ceiling mounted ducted type split air conditioners such as L.G., Mitsubishi, Daikin or quivelant (refrigerant zero ODP) of cooling capacity as specified (direct expansion) c/w Refrigerant Piping, Drain line, Insulation, control, brackets and Condensing units c/w motors, compressors, condenser, copper tubes and pre-painted anti-corrosion resin coated aluminium fins, blowers, filter drier, refrigerant.(Refrigirat pipe length of 5m considered inclusive to the rate.)		
R026	12000 Btu/Hr	**Nos**	**421,336**
R027	18000 Btu/Hr	**Nos**	**421,336**
R028	24000 Btu/Hr	**Nos**	**549,213**
R029	36000 Btu/Hr	**Nos**	**634,893**
	Medical Grade Copper Pipes and Fittings		
	Medical grade Phosphorous De-Oxidized, Degreased and Non-Arsenical Copper pipes, Pipe Fittings and valvescompied to BSEN 13348, Joint shall normally be made on site by silver copper phosphate brazing using British Standard 1845 type AG 14 alloy and fittings shall be of the "high duty" type suitable for steam service gauge pressure up to 17 bars.		
	Medical Grade Copper Pipes		
R030	15 mm diameter	**m**	**3,405**
R031	22 mm diameter	**m**	**5,374**
R032	28 mm diameter	**m**	**7,942**
R033	35 mm diameter	**m**	**8,493**
R034	42 mm diameter	**m**	**11,414**
	Lockable Line Valves		
R035	15 mm diameter	**Nos**	**35,021**
R036	22 mm diameter	**Nos**	**41,359**
R037	28 mm diameter	**Nos**	**75,374**
R038	35 mm diameter	**Nos**	**93,075**
R039	42 mm diameter	**Nos**	**117,391**
	90 Degree Elbow		
R040	End Feed 15mm x 90 Degree Elbow	**Nos.**	**561**
R041	End Feed 22mm x 90 Degree Elbow	**Nos.**	**752**
R042	End Feed 28mm x 90 Degree Elbow	**Nos.**	**992**

Construction BSR 2024

for

Department of Buildings ***(Metric Version)***

Item Code	Item Description	Unit	Basic Rate 2024
R043	End Feed 35mm x 90 Degree Elbow	**Nos.**	**2,016**
R044	End Feed 42mm x 90 Degree Elbow	**Nos.**	**3,883**
	Couplings		
R045	End Feed 15mm Coupling	**Nos**	**513**
R046	End Feed 22mm Coupling	**Nos**	**809**
R047	End Feed 28mm Coupling	**Nos**	**1,217**
R048	End Feed 35mm Coupling	**Nos**	**1,093**
R049	End Feed 42mm Coupling	**Nos**	**1,571**
	Equal Tee		
R050	End Feed 15mm Equal Tee	**Nos**	**644**
R051	End Feed 22mm Equal Tee	**Nos**	**1,288**
R052	End Feed 28mm Equal Tee	**Nos**	**2,084**
R053	End Feed 35mm Equal Tee	**Nos**	**2,463**
R054	End Feed 42mm Equal Tee	**Nos**	**3,934**
	Reducing Coupling		
R055	End Feed 22mm x 15mm Fitting Reducer	**Nos**	**1,304**
R056	End Feed 28mm x 15mm Fitting Reducer	**Nos**	**2,368**
R057	End Feed 28mm x 22mm Fitting Reducer	**Nos**	**2,338**
R058	End Feed 35mm x 22mm Fitting Reducer	**Nos**	**2,621**
R059	End Feed 35mm x 28mm Fitting Reducer	**Nos**	**2,740**
R060	End Feed 42mm x 35mm Fitting Reducer	**Nos**	**4,117**
	Reducing Tee		
R061	End Feed 22mm x 15mm Fitting Reducer	**Nos**	**1,663**
R062	End Feed 28mm x 15mm Fitting Reducer	**Nos**	**2,830**
R063	End Feed 28mm x 22mm Fitting Reducer	**Nos**	**3,369**
R064	End Feed 35mm x 22mm Fitting Reducer	**Nos**	**4,393**
R065	End Feed 35mm x 28mm Fitting Reducer	**Nos**	**4,812**
R066	End Feed 42mm x 35mm Fitting Reducer	**Nos**	**4,868**
	Brass Munsen Rings - Single Ring M10		
R067	15mm Brass Munsen Ring Tapped M10	**Nos**	**1,244**
R068	22mm Brass Munsen Ring Tapped M10	**Nos**	**1,399**
R069	28mm Brass Munsen Ring Tapped M10	**Nos**	**1,543**
R070	35mm Brass Munsen Ring Tapped M10	**Nos**	**1,686**
R071	42mm Brass Munsen Ring Tapped M10	**Nos**	**1,902**
	FRESH AIR DUCTING WORK		
	pre-insulated supply air duct works including all bends, reducers, flange joints, silicon sealant for all joints, anti vibration joint, Reinforcements, hangers etc…..		
R072	100 x 100 mm	**m**	**7,531**

Construction BSR 2024

for

Department of Buildings ***(Metric Version)***

Item Code	Item Description	Unit	Basic Rate 2024
R073	150 x 100 mm	**m**	**9,301**
R074	150 x 150 mm	**m**	**11,071**
R075	200 x 150 mm	**m**	**12,842**
R076	500 x 150 mm	**m**	**23,575**
R077	200 x 200 mm	**m**	**14,611**
R078	250 x 200 mm	**m**	**16,019**
R079	300 x 200 mm	**m**	**18,265**
R080	350 x 200 mm	**m**	**20,035**
R081	400 x 200 mm	**m**	**21,805**
R082	500 x 200 mm	**m**	**25,346**
R083	200 x 250 mm	**m**	**16,381**
R084	300 x 250 mm	**m**	**20,035**
R085	400 x 250 mm	**m**	**23,687**
R086	550 x 250 mm	**m**	**28,354**
R087	575 x 250 mm	**m**	**29,893**
R088	650x 250 mm	**m**	**32,548**
R089	675 x 250 mm	**m**	**33,425**
R090	700 x 250mm	**m**	**34,324**
R091	900 x 250 mm	**m**	**41,430**
R092	300x 300 mm	**m**	**21,993**
R093	400 x 300 mm	**m**	**23,850**
R094	500 x 300 mm	**m**	**28,995**
R095	675 x 300 mm	**m**	**35,202**
R096	700 x 300 mm	**m**	**36,205**
	Fire Detection System		
	Conventional Type Fire alarm control/indicating panel((UL/LPCB approved, NFPA 72/EN 54 complied)) c/w contacts/auxiliary contacts(control modules, monitoring modules) for shut down of A/C & ventilation equipment, connection of fire link/lift homing and all necessary accessories (including battery backup, design for the fire alarm control system, training & providing all passwords);		
R097	Panel of 4 zones or less	**Nos**	**336,638**
R098	Panel of 5-8 zones	**Nos**	**438,938**
R099	Panel of 9-12 zones	**Nos**	**364,488**

Construction BSR 2024

for

Department of Buildings ***(Metric Version)***

Item Code	Item Description	Unit	Basic Rate 2024
R100	Panel of 12 zones or more	**Nos**	**669,675**
	Automatic addressable Type Fire alarm control/indicating panel((UL/LPCB approved, NFPA 72/EN 54 complied)) c/w contacts/auxiliary contacts(control modules, monitoring modules) for shut down of A/C & ventilation equipment, connection of fire link/lift homing and all necessary accessories (including battery backup, design for the fire alarm control system, training & providing all passwords)		
R101	Panel of 50 points or less	**Nos**	**630,888**
R102	Panel of 51 points to 100	**Nos**	**657,688**
R103	Panel of 101 points to 200	**Nos**	**1,059,488**
R104	Panel of 201 or higher	**Nos**	**1,583,925**
	Analogue Addressable Type smoke detector with multiple sensitivity (adjustable at site) levels, programmable for timed automatic sensitivity selection with base, Junction box and other accessories as required.		
R105	Ionization Type	**Nos**	**35,531**
R106	Optical Type (Photoelectric Type)	**Nos**	**38,808**
	Conventional Type smoke detector with multiple sensitivity (adjustable at site) levels, programmable for timed automatic sensitivity selection with base, Junction box and other accessories as required.		
R107	Ionization Type	**Nos**	**21,281**
R108	Optical Type (Photoelectric Type)	**Nos**	**24,131**
	Analogue Addressable Type duct detector with multiple sensitivity (adjustable at site) levels, programmable for timed automatic sensitivity selection with base, Junction box and other accessories as required.		
R109	Ionization Type	**Nos**	**88,256**
R110	Optical Type (Photoelectric Type)	**Nos**	**101,006**
	Conventional Type duct detector with multiple sensitivity (adjustable at site) levels, programmable for timed automatic sensitivity selection with base, Junction box and other accessories as required.		
R111	Ionization Type	**Nos**	**81,131**
R112	Optical Type (Photoelectric Type)	**Nos**	**88,256**
	Analogue Addressable Type heat detector with standard base and fixing accessories.		
R113	Rate-of-rise (ROR) Heat Detectors	**Nos**	**22,706**
R114	Fixed Temperature Heat Detectors	**Nos**	**22,706**
	Conventional Type heat detector with standard base and fixing accessories.		
R115	Rate-of-rise (ROR) Heat Detectors	**Nos**	**12,731**

Construction BSR 2024

for

Department of Buildings ***(Metric Version)***

Item Code	Item Description	Unit	Basic Rate 2024
R116	Fixed Temperature Heat Detectors	**Nos**	**12,731**
R117	Automatic/manual fire alarm call points c/w re-programming work of existing addressable fire control panel, if necessary, and all necessary mounting accessories and connected to the fire alarm control panel	**Nos**	**40,663**
R118	Analogue Addressable Type Fault isolator module capable of monitoring shorted loop circuit and automatically restore communications when shorted conditions are corrected.	**Nos**	**41,231**
R119	Addressable Manual pull station having an integrally mounted addressable module that monitors and reports contact status.	**Nos**	**29,118**
R120	Emergency Exit Lights and Emergency Exit Signs with 3hrs battery back up and all necessary accessories.	**Nos**	**21,234**
R121	2 x 2.5 sq. mm, fire resistance screened cable with PVC insulated copper wires confirming to specification with polycon rigid and flexible conduits in inside the walls, floor or ceiling.	**Nos**	**3,833**
R122	2 x 1.5 sq. mm, fire resistance screened cable with PVC insulated copper wires confirming to specification with polycon rigid and flexible conduits in inside the walls, floor or ceiling.	**Nos**	**3,484**

Construction BSR 2024

for

Department of Buildings ***(Metric Version)***

Item Code	Item Description	Unit	Basic Rate 2024
	S-ELECTRICAL INSTALLATION		
	Recommended makes of Electrical Accessories **MCCB:-** *Schneider, ABB, Terasaki, Siemens,EATON or equivalent.* **MCB'S & RCCB'S:-** *Schneider , Siemens, Crabtree, EATON , Hager, Moeller, ABB, TEC, LS or equivalent.* **Cable :-** *ACL, Kelani, Sierra or equivalent.* **Ceiling Fan:-** *K.D.K., National-Japanese origins* **Exhaust Fan:-** *K.D.K., National-Japanese origins* **Switch & socket outlet :-** *Clipsal, Crabtree, Kevilton,CHINT, Legrand, Orange or Equivalent.* **LED Fittings/ Tube:-** *The light should be good quality, Philips, DIMO, OSRAM,NVC,Green Electric or approved equivalent. Minimum efficacy at scotopic condition should be above 100 lumen/W Corelate colour temperature (CCT) should be above 4000K, (Cool White). Colour rendering index (CRI) should be above 80. Rated life time should be above 50,000 hrs.* **Distribution Board:-** *Shall be in surface mount metal enclosure fabricated With Zinc coated sheet metal of gauge not less than 1.8 mm total enclosed, with hinged door with protective cover plate for terminals, finished with powder coating of approved colour and components as specified in the BOQ.* **Energy Saving Bulbs:-** *CFL Builbs should be 5 stars* Recommended Fabricators of Switch boards and Enclosures. Elsteel (Pvt) Ltd K.I.K. Lanka (Pvt) Ltd Pubudu Engineering (pvt) Ltd Richardsons Projects (pvt) Ltd Bentota Power Generators (Pvt) Ltd Aklan International(Pvt) Ltd. OS Project (Pvt) Ltd. (Orange) Electro Metal Pressings (Pvt) Ltd or Similar fabricator		
	In PVC conduit		
	Point wiring to be carried out with 2x1mm^2 PVC/PVC/CU + 2.5mm^2 PVC/CU earth cable terminated in a 3 terminal ceilingrose and sunk switch, wired in concealed conduit in wall and above ceiling to be supplied and installed to working order		
S001	Lamp point wiring	**Nos.**	**7,230**
S002	Water tight lamp point wiring	**Nos.**	**7,424**
S003	Indoor Braacket lamp point wiring	**Nos.**	**7,176**

Construction BSR 2024

for

Department of Buildings ***(Metric Version)***

Item Code	Item Description	Unit	Basic Rate 2024
S004	Stair way lamp point wiring controlled by 2 No. two way switches	**Nos.**	**11,702**
S005	Ceiling fan point wiring complete with hook and sunk switch	**Nos.**	**8,059**
	wiring to be carried out with 2C,2.5mm2 PVC/PVC/CU + 2.5mm2 PVC/CU earth cable wired in concealed conduit in wall and above ceiling to be supplied and installed to working order		
S006	13 AMP switch socket outlet	**Nos.**	**10,328**
S007	13 AMP twin switch socket outlet	**Nos.**	**11,826**
S008	15 AMP switch socket outlet c/w 20A DP Switch with Neon Indicator Lamp	**Nos.**	**15,612**
	In PVC Casing		
	point wiring to be carried out with 2x1mm2 PVC/PVC/CU + 2.5mm2 PVC/CU earth cable terminated in a 3 terminal ceiling rose and sunk switch, wired with PVC casing on wall and on soffit to be supplied and installed to working order.		
S009	Lamp point wiring	**Nos.**	**7,983**
S010	Water tight lamp point wiring	**Nos.**	**8,178**
S011	Indoor Bracket lamp point wiring	**Nos.**	**7,929**
S012	Stair way Lamp point wiring controlled by 2 No. two way switches.	**Nos.**	**12,908**
S013	Ceiling fan point wiring complete with fan hook and sunk switch.	**Nos.**	**8,813**
	Wiring to be carried out with 2C,2.5mm2 PVC/PVC/CU + 2.5mm2 PVC/CU earth cable wired in concealed conduit in wall and above ceiling to be supplied and installed to working order		
S014	13 AMP switch socket outlet (Radial Circuit)	**Nos.**	**11,053**
S015	13 AMP twin switch socket outlet	**Nos.**	**12,656**
S016	15 AMP switch socket outlet c/w 20A DP	**Nos.**	**17,107**
	Distribution Boards		
	Supply, Wiring and Installation of distribution board in surface mount plastic enclosure with the undermentioned switch gears to working order.		
S017	6 way SP & N Distribution board complete with 30AMP 2P MCB and 40A 2P RCD(30mA)	**Nos.**	**23,583**
S018	8 way SP & N Distribution board complete with 30AMP 2P MCB and 40A 2P RCD(30mA)	**Nos.**	**26,602**
S019	10 way SP & N Distribution board complete with 30AMP 2P MCB and 40A 2P RCD(30mA)	**Nos.**	**30,935**
S020	12 way SP & N Distribution board complete with 30AMP 2P MCB and 40A 2P RCD(30mA)	**Nos.**	**34,227**
S021	14 way SP & N Distribution board complete with 30AMP 2P MCB and 40A 2P RCD(30mA)	**Nos.**	**39,055**
S022	16 way SP & N Distribution board complete with 30AMP 2P MCB and 40A 2P RCD(30mA)	**Nos.**	**43,846**
S023	6 way SP & N Distribution board complete with 60AMP 2P MCB and 60A 2P RCD(30mA)	**Nos.**	**31,006**

Construction BSR 2024

for

Department of Buildings ***(Metric Version)***

Item Code	Item Description	Unit	Basic Rate 2024
S024	8 way SP & N Distribution board complete with 60AMP 2P MCB and 60A 2P RCD(30mA)	**Nos.**	**34,026**
S025	10 way SP & N Distribution board complete with 60AMP 2P MCB and 60A 2P RCD(30mA)	**Nos.**	**38,631**
S026	12 way SP & N Distribution board complete with 60AMP 2P MCB and 60A 2P RCD(30mA)	**Nos.**	**42,146**
S027	14 way SP & N Distribution board complete with 60AMP 2P MCB and 60A 2P RCD(30mA)	**Nos.**	**48,250**
S028	16 way SP & N Distribution board complete with 60AMP 2P MCB and 60A 2P RCD(30mA)	**Nos.**	**51,270**
S029	Supplying and Installation of TP & N Distribution board complete with 60 A 4P MCB(10 kA) and 2 No. 32 A 3P MCB (10kA) in surface mount plastic enclosure.	**Nos.**	**47,630**
S030	Supplying and Installation of TP & N Distribution board complete with 60 A 4P MCCB (25 kA) and 4 No. 16 A 3P MCB(10 kA) in surface mount metal enclosure.	**Nos.**	**95,337**
S031	Supplying and Installation of TP & N Distribution board complete with 100 A 4P MCCB (25 kA) and 2 No. 30/60AMP 3P MCCB (25kA) in surface mount metal enclosure.	**Nos.**	**142,045**
S032	Supplying and Installation of TP & N Distribution board complete with 125 A 4P MCCB (25 kA) and 4 No. 30/60AMP 3P MCCB (25 kA) in surface mount metal enclosure.	**Nos.**	**228,388**
S033	Supplying and Installation of 20-100AMP 4P MCCB in surface mount metal enclosure	**Nos.**	**51,810**
S034	Supplying and Installation of 30AMP 2P isolator complete with plastic enclosure.	**Nos.**	**5,166**
S035	Supplying and Installation of 60AMP 2P isolator complete with plastic enclosure.	**Nos.**	**6,044**
S036	Supplying and Installation of 30AMP 4P isolator complete with plastic enclosure.	**Nos.**	**9,404**
S037	Supplying and Installation of 60AMP 4P isolator complete with plastic enclosure.	**Nos.**	**10,001**
S038	Supplying and Installation of 40AMP 2P RCCB (30mA) complete plastic enclosure.	**Nos.**	**14,613**
S039	Supplying and Installation of 60AMP 2P RCCB (30mA) complete plastic enclosure.	**Nos.**	**18,769**
S040	Supplying and Installation of 40AMP 4P RCCB (30mA) complete plastic enclosure.	**Nos.**	**24,127**
S041	Supplying and Installation of 60AMP 4P RCCB (30mA) complete plastic enclosure.	**Nos.**	**27,904**

Construction BSR 2024

for

Department of Buildings ***(Metric Version)***

Item Code	Item Description	Unit	Basic Rate 2024
	Cabling in conduits		
	Cable shall be PVC/PVC/CU unless other wise specified to be supplied and installed in conduit to working order.		
S042	2x1 sq. mm + 2.5 sq. mm E cable	**m**	**539**
S043	2x2.5 sq. mm + 2.5 sq. mm E cable	**m**	**930**
S044	2x4 sq. mm + 2.5 sq. mm E cable	**m**	**1,329**
S045	2x6 sq. mm + 6 sq. mm E cable	**m**	**2,038**
S046	2x10 sq. mm + 10 sq. mm E cable	**m**	**3,230**
S047	2x16 sq. mm + 16 sq. mm E cable	**m**	**5,000**
S048	2x25 sq. mm + 16 sq. mm E cable	**m**	**7,955**
S049	4x2.5 sq. mm + 2.5 sq. mm E cable	**m**	**1,458**
S050	4x4 sq. mm + 4 sq. mm E cable	**m**	**2,201**
S051	4x6 sq. mm + 6 sq. mm E cable	**m**	**3,237**
S052	4x10 sq. mm +10 sq. mm E cable	**m**	**5,355**
S053	4x16 sq. mm +16 sq. mm E cable	**m**	**7,757**
S054	4x25 sq. mm +16 sq. mm E cable	**m**	**13,262**
S055	4x35 sq. mm +16 sq. mm E cable	**m**	**16,615**
	Unarmoured Cabling		
	Cable shall be Cu/PVC/PVC OR Cu/XLPE/PVC supplied and installed in conduit or presure pipe (type 1000) to working order.		
S056	2C Cu/PVC/PVC 1.5 sq. mm + 2.5 sq. mm E cable	**m**	**1,124**
S057	2C Cu/PVC/PVC 2.5 sq. mm + 2.5 sq. mm E cable	**m**	**1,532**
S058	2C Cu/PVC/PVC 4 sq. mm + 2.5 sq. mm E cable	**m**	**2,445**
S059	2C Cu/PVC/PVC 6 sq. mm + 6 sq. mm E cable	**m**	**3,204**
S060	2C Cu/PVC/PVC 10 sq. mm + 10 sq. mm E cable	**m**	**4,415**
S061	2C Cu/PVC/PVC 16 sq. mm + 16 sq. mm E cable	**m**	**5,000**
S062	2C Cu/PVC/PVC 25 sq. mm + 16 sq. mm E cable	**m**	**7,837**
S063	4C Cu/PVC/PVC 10 sq. mm + 10 sq. mm E cable	**m**	**6,515**
S064	4C Cu/PVC/PVC 16sq. mm + 16 sq. mm E cable	**m**	**9,590**
S065	4C Cu/PVC/PVC 25 sq. mm + 16 sq. mm E cable	**m**	**13,321**
S066	4C Cu/XLPE/PVC 35 sq. mm + 16 sq. mm E cable	**m**	**17,383**
S067	4C Cu/XLPE/PVC 50 sq. mm + 25 sq. mm E cable	**m**	**24,129**
S068	4C Cu/XLPE/PVC 70 sq. mm + 35 sq. mm E cable	**m**	**35,148**

Construction BSR 2024

for

Department of Buildings ***(Metric Version)***

Item Code	Item Description	Unit	Basic Rate 2024
S069	4C Cu/XLPE/PVC 95 sq. mm + 50 sq. mm E cable	**m**	**47,636**
	Armoured Cabling		
	Cable shall be Cu/XLPE/SWA/PVC (BS 5467 : 1997 600/1000V) supplied and installed in cable tile with necessary accessories & materials to working order.		
S070	4C Cu/XLPE/SWA/PVC 25 sq. mm	**m**	**14,016**
S071	4C Cu/XLPE/SWA/PVC 35 sq. mm	**m**	**18,420**
S072	4C Cu/XLPE/SWA/PVC 50 sq. mm	**m**	**23,981**
S073	4C Cu/XLPE/SWA/PVC 70 sq. mm	**m**	**33,947**
S074	4C Cu/XLPE/SWA/PVC 95 sq. mm	**m**	**45,171**
S075	4C Cu/XLPE/SWA/PVC 120 sq. mm	**m**	**56,143**
S076	4C Cu/XLPE/SWA/PVC 150 sq. mm	**m**	**68,197**
S077	4C Cu/XLPE/SWA/PVC 185 sq. mm	**m**	**84,121**
	Cabling in PVC Casing		
	Cable shall be PVC/PVC/CU unless other wise specified to be supplied and installed in PVC casing to working order.		
S078	2x1 sq. mm + 2.5 sq. mm E cable	**m**	**636**
S079	2x2.5 sq. mm + 2.5 sq. mm E cable	**m**	**977**
S080	2x4 sq. mm + 2.5 sq. mm E cable	**m**	**1,536**
S081	2x6 sq. mm + 6 sq. mm E cable	**m**	**2,200**
S082	2x10 sq. mm +10 sq. mm E cable	**m**	**3,294**
S083	2x16 sq. mm +16 sq. mm E cable	**m**	**4,985**
S084	2x25 sq. mm +16 sq. mm E cable	**m**	**8,389**
S085	4x2.5 sq. mm + 2.5 sq. mm E cable	**m**	**1,650**
S086	4x4 sq. mm + 4 sq. mm E cable	**m**	**2,512**
S087	4x6 sq. mm + 6 sq. mm E cable	**m**	**3,775**
S088	4x10 sq. mm + 10 sq. mm E cable	**m**	**5,937**
S089	4x16 sq. mm + 16 sq. mm E cable	**m**	**8,430**
S090	4x25 sq. mm + 16 sq. mm E cable	**m**	**13,870**
S091	4x35 sq. mm + 16 sq. mm E cable	**m**	**17,072**
	Lightning Protection System		
S092	Supplying and Installation of earth Electrode c/w 50 mm dia. Of 2 LM to working order complete with forming of a gulley around the pipe.	**Nos.**	**12,326**
S093	Supplying and Installation of 20 mm dia.solid copper earth rod with inspection pit of 300mm x 300mm x 300mm	**Nos.**	**66,897**

Construction BSR 2024

for

Department of Buildings ***(Metric Version)***

Item Code	Item Description	Unit	Basic Rate 2024
S094	Supply and Installation of 25mm x 3mm Cu tape in Air termination system	**m**	**5,159**
S095	Supply and Installation of 25mm x 3mm Cu tape in Down conductor system	**m**	**5,339**
S096	Supply and Installation of test joint mounted in a yellow PVC enclosure	**Nos.**	**3,913**
S097	Supply and Installation of finial type air terminal with minimum 1000mm height and 12mm diameter	**Nos.**	**32,369**
	Luminaire and Fixtures		
	Supplying and Installation of Luminaire and fixtures complete with all fixing accessories, G.I. Chains cup hook 2/3 core cable, conector suspension holder etc. to working order.		
S098	Pendent Lamp C/W 250 mm dia. Conical plastic shade and 12W LED bulb. *Prime Cost of, 250mm dia plastic conical shade =608*	**Nos.**	**3,006**
S099	Pendent Lamp C/W 200 mm dia. Glass globe and 12W LED bulb. *Prime Cost of, 200mm dia glass globe=1257*	**Nos.**	**3,517**
S100	Indoor Bracket lamp C/W ornament shade and 12W LED bulb. *Prime Cost of, Bracket lamp=3650*	**Nos.**	**5,818**
S101	Water tight bracket lamp C/W Clear glass ornament shade and 12W LED bulb. *Prime Cost of, Water tight bracket lamp=6900*	**Nos.**	**8,395**
S102	Recessed type, T8 LED tube light fitting 1200mm x 300mm complete with polished aluminium double parabolic louver and 2x18W LED tube. *Prime Cost of, Recessed type, T8 LED tube light fitting 1200mm x 300mm complete with polished aluminium double parabolic louver and 2x18W LED tube. =10060*	**Nos.**	**11,227**
S103	Recessed type, T8 LED tube light fitting 1200mm x 600mm complete with polished aluminium double parabolic louver and 3x18W LED tube. *Prime Cost of, Recessed type, T8 LED tube light fitting 1200mm x 600mm complete with polished aluminium double parabolic louver and 3x18W LED tube. =15840*	**Nos.**	**17,151**
S104	Recessed type, T8 LED tube light fitting 600mm x 600mm complete with polished aluminium double parabolic louver and 4x9W LED tube. *Prime Cost of, Recessed type, T8 LED tube light fitting 600mm x 600mm complete with polished aluminium double parabolic louver and 4x9W LED tube. =14900*	**Nos.**	**16,188**
S105	Recessed type, T8 LED tube light fitting 600mm x 600mm complete with polished aluminium double parabolic louver and 3x9W LED tube. *Prime Cost of, Recessed type, T8 LED tube light fitting 600mm x 600mm complete with polished aluminium double parabolic louver and 3x9W LED tube. =12800*	**Nos.**	**14,035**

Construction BSR 2024

for

Department of Buildings ***(Metric Version)***

Item Code	Item Description	Unit	Basic Rate 2024
S106	1200mm battern type T8 LED tube light (1x18W tube) fitting. *Prime Cost of, 1200mm battern type T8 LED tube light (1x18W tube) fitting.=4780*	**Nos.**	**5,582**
S107	1200mm battern type T8 LED tube light (2x18W tube) fitting. *Prime Cost of, 1200mm battern type T8 LED tube light (2x18W tube) fitting.=7200*	**Nos.**	**8,329**
S108	600mm battern type T8 LED tube light (1x9W tube) fitting. *Prime Cost of, 600mm battern type T8 LED tube light (1x9W tube) fitting.=3950*	**Nos.**	**4,985**
S109	1200mm Suspension type T8 LED tube light complete with prismatic diffuser and (1x18W tube). *Prime Cost of, 1200mm Suspension type T8 LED tube light complete with prismatic diffuser and (1x18W tube) =4780*	**Nos.**	**5,848**
S110	600mm Suspension type T8 LED tube light complete with prismatic diffuser and (1x9W tube). *Prime Cost of, 600mm Suspension type T8 LED tube light complete with prismatic diffuser and (1x9W tube)=3950*	**Nos.**	**4,832**
S111	1200mm Suspension type T8 LED tube light complete with prismatic diffuser and (2x18W tube). *Prime Cost of, 1200mm Suspension type T8 LED tube light complete with prismatic diffuser and (2x18W tube)=7200*	**Nos.**	**8,163**
S112	Recessed type 6W LED panel light fitting.	**Nos.**	**2,923**
	Prime Cost of, Recessed type 6W LED panel light fitting=2200		
S113	Recessed type12W LED panel light fitting. *Prime Cost of, Recessed type12W LED panel light fitting=3350*	**Nos.**	**4,101**
S114	Recessed type 18W LED panel light fitting. *Prime Cost of, Recessed type 18W LED panel light fitting=4300*	**Nos.**	**5,075**
S115	Recessed mounted 6W Down light. *Prime Cost of, Recessed mounted 6W Down light =2200*	**Nos.**	**2,938**
S116	Recessed mounted 12W Down light. *Prime Cost of, Recessed mounted 12W Down light =3350*	**Nos.**	**4,117**
S117	Bulk head lamp water tight C/W 12W LED bulb (4 star rated). *Prime Cost of, Bulk head lamp fitting=4775*	**Nos.**	**7,383**
S118	10W IP 65 LED flood light	**Nos.**	**6,720**
S119	20W IP 65 LED flood light	**Nos.**	**9,815**
S120	50W IP 65 LED flood light	**Nos.**	**17,657**

Construction BSR 2024

for

Department of Buildings ***(Metric Version)***

Item Code	Item Description	Unit	Basic Rate 2024
S121	100W IP 65 LED flood light	Nos.	27,835
	Switch socket outlet		
	Switch socket outlet 5AMP/13Amp/15AMP to be supplied and installed complete with screws etc. to working order. (Excluding wires & conduits)		
S122	13 AMP switch socket outlet	Nos.	1,528
S123	15 AMP switch socket outlet	Nos.	Deleted
	Supplying and fixing sunk switch		
	Supplying and fixing sunk switch complete with plastic sunk box to be supplied and installed to working order.		
S124	Supplying and fixing 1 gang sunk switch	Nos.	839
S125	Supplying and fixing 2 gang sunk switch	Nos.	1,210
S126	Supplying and fixing 3 gang sunk switch	Nos.	1,642
S127	Supplying and fixing 4 gang sunk switch	Nos.	2,240
S128	Supplying and fixing 5 gang sunk switch	Nos.	2,725
S129	Supplying and fixing fan regulator dimmer type	Nos.	3,994
S130	Supplying and fixing Ceiling fan regulator	Nos.	3,133
S131	Supplying and fixing 20 AMP DP switch with Neon indicator	Nos.	3,283
S132	Supplying and fixing sunk Bell push	Nos.	1,332
S133	Supplying and fixing Cell Bell Ding Dong type excluding wires	Nos.	4,986
	Fans		
S134	Supply & Installation of Ceiling fan 1400mm dia. Complete with 3 speed regulator (Excluding wiring)	Nos.	26,431
	Exhaust Fans		
S135	Supply & Installation of 200mm dia. Exhaust fan with auto shutter (K.D.K or equvalent) (Excluding wiring)	Nos.	33,378
S136	Supply & Installation of 250mm dia. Exhaust fan (reversible louver series) with auto shutter (K.D.K or equvalent) (Excluding wiring)	Nos.	31,554
S137	Supply & Installation of 300mm dia. Exhaust fan (industrial type-shutter series)with auto shutter (K.D.K or equvalent) (Excluding wiring)	Nos.	69,840
S138	Supply & Installation of 450mm dia. Exhaust fan (industrial type-high pressure series) with auto shutter (K.D.K or equvalent) (Excluding wiring)	Nos.	190,164
	Wall Fans		
S139	Supply & Installation of wall fan 450mm dia. Complete with 3 speed regulator (Excluding wiring)	Nos.	37,755

Construction BSR 2024

for

Department of Buildings ***(Metric Version)***

Item Code	Item Description	Unit	Basic Rate 2024
	Conduit Pipe		
	Supplying & installation of conduit pipe clipped in surface		
S140	18mm conduit pipe	**m**	**203**
S141	20mm conduit pipe	**m**	**230**
S142	25mm conduit pipe	**m**	**253**
S143	30mm conduit pipe	**m**	**428**
S144	40mm conduit pipe	**m**	**557**
S145	50mm conduit pipe	**m**	**693**
	PVC Casing		
	Supplying and Installation of PVC casing		
S146	10mmx20mm PVC Casing	**m**	**228**
S147	14mmx24mm PVC Casing	**m**	**307**
S148	16mmx40mm PVC Casing	**m**	**456**
S149	25mmx40mm PVC Casing	**m**	**594**
S150	50mmx25mm PVC Casing	**m**	**616**
S151	50mmX50mm PVC Box Casing	**m**	**1,001**
S152	50mmX75mm PVC Box Casing	**m**	**1,284**
S153	100mmX50mm PVC Box Casing	**m**	**1,731**
S154	100mmx27mm PVC Box Casing	**m**	**1,329**
	Supply and Installation of main cables		
S155	2x1 sq. mm Cu/PVC/PVC Cable	**m**	**317**
S156	2 x 2.5 sq. mm Cu/PVC/PVC Cable	**m**	**702**
S157	2 x 4 sq. mm Cu/PVC/PVC Cable	**m**	**1,019**
S158	2 x 6 sq. mm Cu/PVC/PVC Cable	**m**	**1,453**
S159	2 x 10 sq. mm Cu/PVC/PVC Cable	**m**	**2,228**
S160	2 x 16 sq. mm Cu/PVC/PVC Cable	**m**	**3,451**
S161	2 x 25 sq. mm Cu/PVC/PVC Cable	**m**	**6,295**
S162	2 x 35 sq. mm Cu/PVC/PVC Cable	**m**	**7,723**
	Supply and Installation of Earth cables		
S163	2.5 sq. mm Cu/PVC Earth cable	**m**	**323**
S164	4 sq. mm Cu/PVC Earth cable	**m**	**501**
S165	6 sq. mm Cu/PVC Earth cable	**m**	**798**
S166	10 sq. mm Cu/PVC Earth cable	**m**	**1,247**
S167	16 sq. mm Cu/PVC Earth cable	**m**	**1,859**

Construction BSR 2024

for

Department of Buildings ***(Metric Version)***

Item Code	Item Description	Unit	Basic Rate 2024
S168	25 sq. mm Cu/PVC Earth cable	**m**	**3,427**
S169	35 sq. mm Cu/PVC Earth cable	**m**	**4,335**
S170	50 sq. mm Cu/PVC Earth cable	**m**	**5,644**
S171	70 sq. mm Cu/PVC Earth cable	**m**	**7,697**
S172	95 sq. mm Cu/PVC Earth cable	**m**	**10,328**
S173	120 sq. mm Cu/PVC Earth cable	**m**	**12,892**
	SUPPLY & INSTALLATION OF DOL STARTER		
S174	Single phase DOL starter for 5.5kW motor (without overload)	**Nos.**	**57,396**
S175	Three phase DOL starter for 5.5kW motor (without overload)	**Nos.**	**112,205**
	EXTRA LOW VOLTAGE SYSTEM		
S176	Supply and installation of Cat6 Data Outlet for Data points including Cat6 cables, Cat6 Keystone Jacks, Single face plates, Sunk Box, PVC Conduits/Trunking, Floor Trunking and all other accessories to be supplied and installed to working order	**Nos.**	**21,214**
S177	Supply and Laying of Solid Pure Copper CAT 6 Cable from a relevant Patch Panel to each Camera point	**Nos.**	**14,934**
S178	MM OM3 6-Core Outdoor Armed Fiber Optic Cables supplied and installed in a trench including all required civil works and installation charges	**Nos.**	**4,695**
S179	MM OM3 8-Core Outdoor Armed Fiber Optic Cables supplied and installed in a trench including all required civil works and installation charges	**Nos.**	**5,007**
S180	MM OM3 12-Core Outdoor Armed Fiber Optic Cables supplied and installed in a trench including all required civil works and installation charges	**Nos.**	**5,352**
S181	Supply and Installation of 12 Core Optic Fiber indoor MM 50/125 OM3 through securely fixed PVC Pipes and casings (runs per floor Access switches, starting from Core switches)	**Nos.**	**3,894**
S182	Supply and Installation of 8 Core Optic Fiber indoor MM 50/125 OM3 through securely fixed PVC Pipes and casings (runs per floor Access switches, starting from Core switches)	**Nos.**	**3,334**
S183	Supply and Installation of 6 Core Optic Fiber indoor MM 50/125 OM3 through securely fixed PVC Pipes and casings (runs per floor Access switches, starting from Core switches)	**Nos.**	**2,720**
S184	Supply and Laying of Solid Pure Copper CAT 6 Cable	**Nos.**	**2,153**
S185	Supply and installation of fiber patch cords (1m)	**Nos.**	**6,488**
S186	0.5m Solid Pure Copper CAT 6 Slim Boot Patch Cords.	**Nos.**	**1,421**

Construction BSR 2024

for

Department of Buildings ***(Metric Version)***

Item Code	Item Description	Unit	Basic Rate 2024
S187	1m Solid Pure Copper CAT 6 Slim Boot Patch Cords.	**Nos.**	**1,658**
S188	3m Solid Pure Copper CAT 6 Slim Boot Patch Cords.	**Nos.**	**2,498**
S189	Supply and Installation of 16U 19" wall mounting, glass door, fully loaded rack with the following accessories. 4 way power bar with 13A socket outlets. Thermostatically controlled 3 nos 100mmx100mm size 230Vac, cooling fan plate with finger guard, Vertical & Horizontal cable trays,Gland plates top & bottom, Fixed trays, UK Plug etc.(As per specifications)	**Nos.**	**95,275**
S190	Supply and Installation of 25U 19" wall mounting, glass door, fully loaded rack with the following accessories. 4 way power bar with 13A socket outlets. Thermostatically controlled 3 nos 100mmx100mm size 230Vac, cooling fan plate with finger guard, Vertical & Horizontal cable trays,Gland plates top & bottom, Fixed trays, UK Plug etc.(As per specifications)	**Nos.**	**253,325**
S191	Supply and installation of 12 Port POE 185W, Non blocking, Manageable Switch with 12 x RJ-45 10/100/1000 Mbps Gigabit Ethernet Ports, 2 No. SFP ports as uplinks ,SFP transceivers and any other connecting equipments for uplinks. having auto Crossover Function	**Nos.**	**306,775**
S192	Supply and installation of 24 Port POE 370W, Non blocking, Manageable Switch with 24 x RJ-45 10/100/1000 Mbps Gigabit Ethernet Ports, 2 No. SFP ports as uplinks ,SFP transceivers and any other connecting equipments for uplinks. having auto Crossover Function	**Nos.**	**362,850**
S193	Supply and installation of 48 Port POE 370W, Non blocking, Manageable Switch with 48 x RJ-45 10/100/1000 Mbps Gigabit Ethernet Ports, 2 No. SFP ports as uplinks ,SFP transceivers and any other connecting equipments for uplinks. having auto Crossover Function	**Nos.**	**664,175**
S194	Supply and installation of 16 Port Unmanageable Switch with 16 x RJ-45 10/100/1000 Mbps Gigabit	**Nos.**	**50,363**
S195	Supply and installation of 24 Port Unmanageable Switch with 24 x RJ-45 10/100/1000 Mbps Gigabit	**Nos.**	**66,975**
S196	Supply and installation of 48 Port Unmanageable Switch with 48 x RJ-45 10/100/1000 Mbps Gigabit	**Nos.**	**132,638**
S197	Supply and Installation of 12 port duplex SC port fiber Patch Panel	**Nos.**	**97,673**
S198	Supply and Installation of 12 port Copper Patch Panel	**Nos.**	**29,875**
S199	Supply and Installation of 24 port Copper Patch Panel	**Nos.**	**35,325**
S200	Supply and Installation of 48 port Copper Patch Panel	**Nos.**	**68,025**

Construction BSR 2024

for

Department of Buildings ***(Metric Version)***

Item Code	Item Description	Unit	Basic Rate 2024
	T -FINISHERG & FLOORING		
	T1-Plasterer		
	Plastering *(walls)*		
T001	(15 mm) thick plastering to wall in cement lime and sand 1:1:5 finished semi rough with wooden float.	**m2**	**1,050**
T002	(15 mm thick plastering to wall in cement lime and sand 1:1:5 finished smooth with lime putty floating.	**m2**	**1,215**
T003	(15 mm)) thick plastering 1:5 cement and sand semi rough	**m2**	**941**
T004	15mm thick plastering to wall in cement sand 1:5 including finished smooth with Skim coat.	**m2**	**1,515**
T005	15mm thick plastering to wall in cement sand 1:3 including coloured cement floating.	**m2**	**1,415**
	Plastering (beams, slab soffits)		
T006	10mm thick plastering to R.C.C. beams, slab soffit in cement and sand 1:3 including floating with lime putty.	**m2**	**1,398**
T007	10mm thick plastering to R.C.C. beams, slab soffit in cement and sand 1:3 including finished smooth with Skim coat.	**m2**	**1,511**
T008	Cove moulding 62.5mm x 62.5mm in cement mortar 1:2 built in existing wall.	**m**	**506**
T009	Cresting with broken glass in cement mortar 1:4 on coping of boundary wall.	**m**	**670**
	Moulding		
T010	Moulding 75mm x 12mm in walls in lime and cement mortar 1:1:4 only for replacements to match existing or to be "extra" over rate for plastering.	**m**	**526**
T011	Moulding 150mm x 25mm in walls in lime and cement mortar 1:1:4 only for replacements to match existing or to be "extra" over rate for plastering.	**m**	**788**
T012	Moulding 100mm x 50mm in cement and sand 1:2 built in existing wall.	**m**	**1,062**
T013	Flashing or plaster bands laid over tiles 100mm to 150mm wide on roof in cement and lime mortar 1:1:4.	**m**	**338**
T014	Letters embossed in plaster 20mm thick upto 150mm high in cement and sand 1:2 cement floated and painted complete.	**Nos**	**462**
T015	16mm thick plastering to walls in lime and sand 2:5 including floating, finished smooth with lime putty.	**m2**	**1,131**
T016	Pointing flush in cement 1:2 in surface cracks including raking out joints.	**m**	**214**
T017	Pointing, tuck, projected in cement 1:2 on brick masonry etc.	**m2**	**1,914**
	Rendering Cement		
T018	Rendering Cement 12mm; 1:2 above 9.29m2.	**m2**	**1,037**
T019	Rendering, cement 12mm, 1:2 upto 9.29m2.	**m2**	**1,185**
T020	Rendering, cement 12mm, 1:3 above 9.29m2.	**m2**	**946**
T021	Rendering, cement 12mm 1:3 upto 9.29m2.	**m2**	**1,094**

Construction BSR 2024

for

Department of Buildings ***(Metric Version)***

Item Code	Item Description	Unit	Basic Rate 2024
T022	Rendering, cement 20mm, 1:2 above 9.29 m2.	**m2**	**1,448**
T023	Rendering, cement 20mm, 1:2 upto 9.29m2.	**m2**	**1,643**
T024	Rendering, cement 20mm 1:3 above 9.29 m2 .	**m2**	**1,343**
T025	Rendering, cement 20mm, 1:3 upto 9.29 m2.	**m2**	**1,538**
	Cement floating coat.		
T026	Rendering, cement, floating coat, using neat Cement and finished smooth with Carborandum Stone.	**m2**	**255**
T027	Rendering, cement, floating coat, using Red Cement finished smooth with Carborandum stone.	**m2**	**533**
T028	Rendering, cement, floating coat, using brown or green cement finished smooth with Carborandum Stone.	**m2**	**502**
T029	Rendering, cement, floating coat, using black cement finished smooth with Carborandum Stone.	**m2**	**533**
T030	Rendering cement 20mm 1:2 with Pudlo, 2.25kg to 45kg, cement.	**m2**	**1,523**
	Skirting in cement mortar		
T031	Skirting in cement mortar 1:3, 12mm x 100mm projected or flushed with wall, and including forming groove.	**m**	**679**
T032	Skirting in cement mortar 1:3, 12mm x100mm projected or flushed with wall finished with Red Cement floating, including forming groove.	**m**	**848**
	Plastering (Reveals)		
T033	Plastering external reveals 0mm - 100mm wide finished rough.	**m**	**413**
T034	Plastering internal reveals 0mm - 100mm wide finished smooth.	**m**	**955**

Construction BSR 2024

for

Department of Buildings ***(Metric Version)***

Item Code	Item Description	Unit	Basic Rate 2024
	T2-PAVIOR		
T035	Expansion joints in brick floors, filling with bitumen and sand.	**m**	**138**
T036	Expansion joints in concrete floors filling with bitumen and sand (to full depth of concrete and rendering).6mm tk and 100mm deep.	**m**	**293**
	Floors, gravel		
T037	Floors, gravel 100mm thick, spreading, watering and ramming.	**m2**	**370**
	Floor tiles (Laying only)		
	Fixing tiles on floors with all specials, including raking plaster and bedding in cement mortar 1:3 pointed with tile grout to match the tiles. (Tiles supplied by the client or paid separately.		
T038	--Do-- for, tiles 200mm x 200mm in size.	**m2**	**2,417**
T039	--Do-- for, tiles 300mm x 300mm in size.	**m2**	**2,401**
T040	--Do-- for, tiles 400mm x 400mm in size.	**m2**	**2,296**
T041	--Do-- for, tiles 600mm x 600mm in size.	**m2**	**2,188**
	Floor tiles; (Gloss/Semi Gloss/Matt) - Vitreous Porcelain (Homogenous/ Non Homogenous)-Local		
	Porcelain Homogenous/ Non Homogenous Vitreous, floor tiles with all specials supplying and fixing to floors including raking plaster and bedding in cement mortar 1:3 and pointed with tile grout to match the tiles. (Rocell or equivalent brand)		
T042	'--Do-- for, 300mm x 300mm MATT floor tile *Prime Cost of, 12"x12" MATT floor tile (Rocell or Equivalent)=N/A*	**m2**	**Deleted**
T043	'--Do-- for, 300mm x 300mm GLOSS floor tile *Prime Cost of, 12"x12" GLOSS floor tile (Rocell or Equivalent)=N/A*	**m2**	**Deleted**
T044	--Do-- for, 300mm x 300mm SEMI GLOSS floor tile *Prime Cost of, 12"x12" SEMI GLOSS floor tile (Rocell or Equivalent)=N/A*	**m2**	**Deleted**
T045	--Do-- for, 400mm x 400mm MATT floor tile *Prime Cost of, 16"x16" MATT floor tile (Rocell or Equivalent)=599*	**m2**	**6,339**
T046	--Do-- for, 450mm x 450mm MATT floor tile *Prime Cost of, 18"x18" MATT floor tile (Rocell or Equivalent)=N/A*	**m2**	**Deleted**
T047	--Do-- for, 500mm x 500mm GLOSS floor tile	**m2**	**Deleted**

Construction BSR 2024

for

Department of Buildings ***(Metric Version)***

Item Code	Item Description	Unit	Basic Rate 2024
	Prime Cost of, 20"x20" GLOSS floor tile (Rocell or Equivalent)=N/A		
T048	--Do-- for, 600mm x 300mm MATT floor tile *Prime Cost of, 24"x12" MATT floor tile (Rocell or Equivalent)=875*	**m2**	**7,476**
T049	--Do-- for, 600mm x 300mm GLOSS floor tile *Prime Cost of, 24"x12" GLOSS floor tile (Rocell or Equivalent)=820*	**m2**	**7,123**
T050	--Do-- for, 600mm x 400mm MATT floor tile *Prime Cost of, 24"x16" MATT floor tile (Rocell or Equivalent)=N/A*	**m2**	**Deleted**
T051	--Do-- for, 600mm x 600mm POLISH floor tile *Prime Cost of, 24"x24" POLISH floor tile (Rocell or Equivalent)=2221*	**m2**	**8,814**
T052	--Do-- for, 600mm x 600mm MATT floor tile *Prime Cost of, 24"x24" MATT floor tile (Rocell or Equivalent)=2023*	**m2**	**8,212**
T053	--Do-- for, 900mm x450mm MATT floor tile *Prime Cost of, 36"x18" MATT floor tile (Rocell or Equivalent)=2300*	**m2**	**8,488**
	Floor tiles- Rustic Type (Homogenous)-Local		
	Floor tiles- Rustic Type (Homogenous), with all specials supplying and fixing to floors including raking plaster and bedding in cement mortar 1:3 and pointed with tile grout to match the tiles. (Rocell or equivalent brand)		
T054	--Do-- for, 300mm x 300mm in size. *Prime Cost of, Tiles 12"x12" Rustic Type (Homogenius) (Rocell)=N/A*	**m2**	**Deleted**
T055	--Do-- for, 400mm x 400mm in size. *Prime Cost of, Tiles 16" x 16"Rustic Type (Homogenius) (Rocell)=604*	**m2**	**6,373**
	Tile Skirting		
T056	Vitreous ceramic floor tiles Skirting 12"x4" supplying and fixing to bottom line of wall including raking plaster bedding with cement mortar 1:3 and pointed with tile grout to match the tiles. (Quality approved by the Engineer.) *Prime Cost of, Tiles 12"x12" Rustic Type (Homogenius) (Rocell)=N/A*	**m**	**Deleted**
	Terrazzo tile flooring		
T057	Terrazzo tile flooring supplying and laying.	**m2**	**7,365**
T058	Terrazzo, wall lining with precast walling slabs 37.5mm thick supplying and fixing to complete.	**m2**	**7,143**

Construction BSR 2024

for

Department of Buildings ***(Metric Version)***

Item Code	Item Description	Unit	Basic Rate 2024
	Wall tiles -glazed (Approved Quality)		
T059	Tiles, glazed with all specials, supplying and fixing to walls including raking plaster and backing in cement mortar 1:3. for available tiles (Tiles supplied by the client or paid separately.)	**m2**	**2,308**
	Wall tiles -Local		
	Tiles glazed with all specials , supplying and fixing to walls including raking plaster backing in cement mortar 1:3 and pointed with tile grout to match the tiles.(Lanka wall Tiles or equivalent brand)		
T060	--Do-- for Coloured, white or printed 250mm x 325mm *Prime Cost of, Glazed colour walls Tiles 10"x 13" (Lanka Walltile or equi)=N/A*	**m2**	**Deleted**
T061	--Do-- for Coloured, white or printed 200mm x 200mm *Prime Cost of, Glazed colour walls Tiles 8 "x8" (Lanka Walltile or equi)=310*	**m2**	**10,529**
T062	--Do-- for Coloured, white or printed 200m x 300mm *Prime Cost of, Glazed colour walls Tiles 8"x12" (Lanka Walltile or equi)=N/A*	**m2**	**Deleted**
T063	--Do-- for Coloured, white or printed 200mm x 400mm *Prime Cost of, Glazed colour walls Tiles 8 "x16" (Lanka Walltile or equi)=N/A*	**m2**	**Deleted**
T064	--Do-- for Coloured, white or printed 300mm x 400mm *Prime Cost of, Glazed colour walls Tiles 12"x16" (Lanka Walltile or equi)=N/A*	**m2**	**Deleted**
T065	--Do-- for Coloured, white or printed 300mm x 600mm *Prime Cost of, Glazed colour walls Tiles 12"x24" (Lanka Walltile or equi)=748*	**m2**	**6,853**
	Wall tiles (Fixing only)		
	Fixing tiles on walls with all specials , including raking plaster backing in cement mortar 1:3 and pointed with tile grout to match the tiles. (Tiles supplied by the client or paid separately.)		
T066	--Do-- for size up to 200mm x 400mm.	**m2**	**2,256**
T067	--Do-- for size up to 300mm x 600mm.	**m2**	**2,425**

Construction BSR 2024

for

Department of Buildings ***(Metric Version)***

Item Code	Item Description	Unit	Basic Rate 2024
	Border Tiles for Wall (Decorative)		
T068	Boarder tiles glazed colour 200mm X 75mm, with decorative patterns , supplying and fixing to walls including raking plaster backing in cement mortar 1:3 and pointed with tile grout to match the tiles. *Prime Cost of, Boarder tiles glazed colour 8 "x 3" with decarative paterns=N/A*	**m**	**Deleted**
T069	Boarder tiles glazed colour 200mm X 75mm, with decorative patterns , supplying and fixing to walls including raking plaster backing in cement mortar 1:3 and pointed with tile grout to match the tiles. *Prime Cost of, Boarder tiles glazed colour 8 "x 3" with decorative patterns (extreme design)=N/A*	**m**	**Deleted**
T070	Boarder tiles glazed colour 300mm X 75mm, with decorative patterns , supplying and fixing to walls including raking plaster backing in cement mortar 1:3 and pointed with tile grout to match the tiles. *Prime Cost of, Boarder tiles glazed colour 12 "x 3" with decorative patterns=N/A*	**m**	**Deleted**
T071	Boarder tiles glazed colour 300mm X 75mm, with decorative patterns , supplying and fixing to walls including raking plaster backing in cement mortar 1:3 and pointed with tile grout to match the tiles. *Prime Cost of, Boarder tiles glazed colour 12 "x 3" with decorative patterns (extreme design)=N/A*	**m**	**Deleted**
	Granite flooring-Local		
T072	Granite floor tiles 300mm x 300mm x 12mm (Local) supplying and fixing to floors including raking plaster bedding with cement mortar 1:3. *Prime Cost of, Granite floor tiles 12" x 12"x ¾" (Local, Range 1)=3119*	**m2**	**Deleted**
T073	Granite floor tiles 600mm x 300mm x 20mm (Local) supplying and fixing to floors including raking plaster bedding with cement mortar 1:3. *Prime Cost of, Granite floor tiles 24" x 12"x¾" (Local, Range 2)=6237*	**m2**	**37,298**
T074	Labour cost for fixing 300mm x 100mm x 20mm Granite skirting to bottom line of walls including cutting ,rounding & Forming edges polishing etc.	**m**	**1,552**
	Glass block		
T075	Glass block 200mm x 200mm with all specials supplying and fixing to walls including raking plaster and bedding in cement mortar 1:3.	**m2**	**20,619**
	Vinyl Sheet Flooring		
T076	Supplying and laying 2mm thick Vinyl Flooring with necessary adhesive etc. (Mipolam 150 or equivalent) (Upto 14 m2 only)	**m2**	**6,674**

Construction BSR 2024

for

Department of Buildings ***(Metric Version)***

Item Code	Item Description	Unit	Basic Rate 2024
	Vinyl Tile		
T077	Supplying and laying 2mm thick Vinyl tile with necessary adhesive etc. (Mactile - Gerflor or equivalent) (Upto 14m2 only)	**m2**	**4,951**
	Loop pile carpeting		
T078	Supplying and laying Loop pile carpeting with 5mm thick with Mcfoam under layer , firmly bonded to the existing floor. Carpet having primary & Secondary backings, namely polypropylene & Classic back respectively. And having the minimum pile weight of 20 Oz-USA per sq. yard. & loop density of 6,100 Oz/Cu.yard. (Neyland II or equivalent) (Upto 14m2 only)	**m2**	**3,229**
	Cut pile carpeting		
T079	Supplying and laying 1/8 gauged, Wide Open Cut pile carpeting (USA or equivalent) with 5mm thick with Mac Form under layer , firmly bonded to the existing floor. Carpet having primary & Secondary backings, namely woven polypropylene & Classic back polypropylene, respectively. And having the minimum pile weight of 30 Oz per sq. yard. & loop density of 5320 Oz/Cu.yard. (Upto 14m2 only)	**m2**	**6,674**
	Interlocking paving		
T080	Supplying and Laying 80mm thick "Uni" type Coloured interlocking paving blocks having Compressive Strength of 40N/mm2, layed on plain improved sub surface. Rate inclusive for Quarry dust bedding (Upto 14m2 only)	**m2**	**7,491**
T081	Supplying and Laying 80mm thick "Uni" type Natural cement colour interlocking paving blocks having Compressive Strength of 40N/mm2, layed on plain improved sub surface. Rate inclusive for Quarry dust bedding. (Upto 14m2 only)	**m2**	**6,399**
	Paving tile Slabs		
T082	Supplying and Laying 300 x300 x50mm thick Non Reinforced, Natural cement colour, Concrete paving Slab, layed on plain improved sub surface. Rate inclusive for Quarry dust bedding. (Upto 14m2 only)	**m2**	**5,090**
T083	Supplying and Laying 300 x300 x50mm thick Reinforced, Natural cement colour, Concrete paving Slab, layed on plain improved sub surface. Rate inclusive for Quarry dust bedding. (Upto 14m2 only)	**m2**	**6,851**

Construction BSR 2024

for

Department of Buildings ***(Metric Version)***

Item Code	Item Description	Unit	Basic Rate 2024
	U-GLAZER		
U001	Glass panes fixing with (Group 6 category A) timber beadings (Glass available)	**m2**	**3,390**
U002	Glass panes 3 mm clear supplying and fixing with (Group 6 category A) timber beadings.	**m2**	**5,133**
U003	Glass panes 5 mm clear, supplying and fixing with Teak Beadings.	**m2**	**6,116**
U004	Glass panes 5 mm pinhead or obscure supplying and fixing with (Group 6 category A) timber beadings.	**m2**	**8,376**
U005	Glass panes 3 mm pinhead or obscure supplying and fixing with (Group 6 category A) timber beadings.	**m2**	**6,574**
U006	Paint removing from painted glass panes with Caustic Soda Solution or other paint remover.	**m2**	**1,095**

Construction BSR 2024

for

Department of Buildings ***(Metric Version)***

Item Code	Item Description	Unit	Basic Rate 2024
	V-PAINTING & DECORATING		
V001	Walls, scraped to original plaster, sand papering and lime putting cracks and defects, preparing surface for Distemper, snowcem, paint or similar application.	m2	214
V002	Walls, scraping and removing soot and levelling internally in Kitchen (extra over colour washing)	m2	61
	Total coat / Skim coat		
V003	Applying Total coat joint compound and wall filler two coats, finished smooth with sand papering, and prepare for colour washing.	m2	1,790
V004	Applying Skim Coat compound on walls or sofit two coats, finished smooth with sand papering, and prepare for colour washing.	m2	447
	Cement washing to walls		
V005	Cement washing to walls of single storeyed buildings, 1 coat, patching and preparing surface.	m2	65
V006	Cement washing to walls of single storeyed buildings, 2 coat, patching and preparing surface.	m2	110
V007	Cement washing externally to walls of building with upper floors, 1 coat.	m2	83
	White or colour washing walls		
V008	White or colour washing walls of single storeyed buildings 1 coat, including patching up and preparing surface.	m2	65
V009	White or colour washing walls of single storeyed buildings 2 coats, including patching up and preparing surface.	m2	114
V010	White or Colour washing external walls of two storeyed buildings, 1 coat.	m2	76
V011	White or Colour washing external walls in buildings, of more than 2 storeys, 1 coat.	m2	88
V012	White or Colour washing external walls in Two storeyed buildings, 2 coats.	m2	135
V013	White or Colour washing external walls in building with more than 2 storeys, 2 coats.	m2	146
	Snowcem paint		
V014	Painting walls with snowcem or equivalent cement paint, 2 coats to new work.	m2	582
	Alkali resisting primer		
V015	Painting walls with alkali resisting primer where necessary.	m2	426
	Elastometic filler Primer		
V016	Painting walls with one coat of Elastometic filler Primer where necessary.	m2	442
	Alkali resisting water Proofing sealer		
V017	Painting walls with one coat of Alkali resisting water Proofing sealer where necessary.	m2	355
	Anti-fungus paint		
V018	Applying Anti-fungus paint to all exposed surfaces on walls already prepared.	m2	1,113

Construction BSR 2024

for

Department of Buildings ***(Metric Version)***

Item Code	Item Description	Unit	Basic Rate 2024
	Silicone masonry water repellent paint		
V019	Painting Walls with one coat of Silicone masonry water repellent paint.	m2	267
	Bathroom paint		
V020	Painting Walls with one coat of Bathroom paint.	m2	345
	Emulsion paint		
V021	Painting Walls with one coat of emulsion paint. (new work or after preparation of old wall)	m2	283
V022	Painting walls with two coats of emulsion paint. (new work or after preparation of old wall)	m2	515
	Painting weather shield (External walls) on New work		
V023	Painting external walls with One coat of weather shield paint. (On New work or prepared old work).	m2	386
V024	Painting external walls with Two coats of weather shield paint. (On New work or prepared old work).	m2	717
	Acrylic Emulsion (Exterior paint)		
V025	Painting external walls with two coats of Acrylic Emulsion paint resist against algae, fungus and scrubs.	m2	742
	Painting asbestos sheet roof		
V026	Painting over the asbestos sheet roof with coats of roof shield paint.	m2	540
V027	Painting under side of asbestos roofing sheet with one coats of emulsion paint	m2	381
V028	Painting under side of asbestos roofing sheet with two coats of emulsion paint	m2	581
V029	Painting under side of asbestos roofing sheet with one coat of primer after preparing surface	m2	786
	Floor Painting		
V030	Painting floors with One coat of quick drying Floor paint including washing, cleaning and smoothing down the surface.	m2	461
V031	Painting floors with Two coats of quick drying Floor paint including washing, cleaning and smoothing down the surface.	m2	903
	Anticorrosive paint		
V032	Painting steelwork, 1 coat with anticorrosive paint including removing scale and wire brushing.	m2	357
V033	Painting steelwork, 2 coats, with anticorrosive paint including removing scale and wire brushing.	m2	646
	Painting on GI Surface		
V034	Painting new galvanized iron GI Adhesion Promoter one coat and one coat of Dulux metal primer zink chromate or duco oil primer or equivalent including washing surface with water after manufactures specification.	m2	953
	Aluminium paint		
V035	Painting, aluminium paint, 1 coat on metal surfaces.	m2	342
V036	Aluminium paint, one coat, along 50mm thick band.	m	68

Construction BSR 2024

for

Department of Buildings ***(Metric Version)***

Item Code	Item Description	Unit	Basic Rate 2024
V037	Aluminium paint, two coat, along 50mm thick band.	m	125
	Enamel paint		
V038	Painting one coat of Enamel paint, including washing and cleaning the surface.	m2	505
V039	Painting two coat of Enamel paint, including washing and cleaning the surface.	m2	949
	Removal of Paint from timber.		
V040	Paint removed entirely with blow lamp to bare timber.	m2	408
V041	Painting G.I pipes 12mm to 20mm with approved paint, 2 coats.	m	141
	Wood preservative		
V042	Wood preservative, (clear) applied to woodwork one coat (old work)	m2	295
V043	Wood preservative, (clear) applied to woodwork two coats (New work)	m2	545
	Enamel paint with Wood primer Under coat		
V044	Painting new woodwork, with primer, undercoat and 2 coats of enamel paint.	m2	1,481
V045	Painting new woodwork with approved primer, one coat.	m2	477
	Polishing wood work with Wax		
V046	Wax polishing wood work including thoroughly sand papering surface in new work only of permanent fixtures.	m2	976
	Painting with Wood sheen		
V047	Painting with Wood sheen paint including washing cleaning and smoothing down surface, One coat.	m2	434
V048	Painting with wood sheen paint including washing cleaning and smoothing down surface, Two coats.	m2	751
	Polyurethane Varnishing		
V049	Varnishing with polyurethane varnish after washing down and sand papering, 1 coat.	m2	508
V050	Varnishing with polyurethane varnish after washing down and sand papering, 2 coats.	m2	822
	polyurethane varnish-Matt		
V051	Varnishing with polyurethane varnish after washing down and sand papering, 2 coats.	m2	849
	Removing Varnish		
V052	Varnishing, removing entirely to bare timber and preparing surface.	m2	569
	Painting with Sanding sealer / Woof finish		
V053	Applying new woodwork with two coats of Sanding sealer and two coats of wood finish	m2	908
V054	Applying wood finish, one coat, including washing, cleaning and smoothing down surface.	m2	406
V055	Applying wood finish, one coat, including two coats of sanding sealer after washing, cleaning and smoothing down surface.	m2	1,064

Construction BSR 2024

for

Department of Buildings ***(Metric Version)***

Item Code	Item Description	Unit	Basic Rate 2024
	Painting with Perque varnish		
V056	Cutting, levelling ,polishing and applying two coats of Perque varnish for an existing timber base floor.	**m2**	**2,505**
V057	Applying masonry sealer for walls one coat.	**m2**	**466**
	Painting Letters on (Board / Wall)		
V058	Lettering 25mm to 37.5mm painted in Sinhalese, English or Tamil, including painting background.	**Nos**	**113**
V059	Lettering 50mm to 75mm painted in Sinhalese, English or Tamil, including painting background.	**Nos**	**522**
V060	Lettering 100mm to 125mm painted in Sinhalese, English or Tamil, including painting background.	**Nos**	**287**
	Water base Painting		
V061	Preparing and application two coats of normal range (JAT-Sayerlack brand or equivalent) water based stain and two coats of water based top coat (JAT-Sayerlack brand or equivalent) to new wood work. Rate shall include for preparing the surface and sanding with sander machine (Prime cost of water base stain -JAT - Master brand- 4L is Rs. 7,604.00 and water base top coat 4L is Rs. 15,532.00 with five year product warranty)	**m2**	**2,473**

Construction BSR 2024

for

Department of Buildings ***(Metric Version)***

Item Code	Item Description	Unit	Basic Rate 2024
	W-DRAINAGE SYSTEMS		
	Wire dome (Steel)		
W001	Wire domes for 63mm pipes supplying and fixing.	**Nos**	**596**
W002	Wire domes for 110mm pipes supplying and fixing.	**Nos**	**840**
	Wire dome (PVC)		
W003	Supplying & fixing PVC wire dome for 2"(50mm) dia. P.V.C drainage pipes.	**Nos**	**405**
W004	Supplying & fixing PVC wire dome for 4" (100mm)dia. P.V.C drainage pipes.	**Nos**	**517**
	Drainage Fittings 4" (110mm) dia-(Local make)		
W005	Supplying & fixing 110mm dia. P.V.C plain socket (Local make)	**Nos**	**1,549**
W006	Supplying & fixing 110mm dia. P.V.C drainage elbow with single Door, approved quality with rubber ring joint.(Locally made)	**Nos**	**2,040**
W007	Supplying & fixing 110mm dia. P.V.C drainage bend 45 degree. (S-Lon or Equivalent.)	**Nos**	**1,578**
W008	Supplying & fixing 110mm dia. P.V.C drainage bend 45 degree ,with single Door (S-Lon or Equivalent.)	**Nos**	**2,054**
W009	Supplying & fixing 110mm dia. P.V.C drainage bend 89 degree. (S-Lon or Equivalent.)	**Nos**	**1,543**
W010	Supplying & fixing 110mm dia. P.V.C drainage bend 89 degree. With single Door (S-Lon or Equivalent.)	**Nos**	**2,032**
W011	Supplying & fixing 110mm dia. P.V.C drainage Tee. (S-Lon or Equivalent.)	**Nos**	**2,072**
W012	Supplying & fixing 110mm dia. P.V.C drainage Swept Tee. (S-Lon or Equivalent.)	**Nos**	**2,277**
W013	Supplying & fixing 110mm dia. P.V.C drainage Tee. with single Door (S-Lon or Equivalent.)	**Nos**	**2,441**
W014	Supplying & fixing 110mm dia. P.V.C drainage Swept Tee. with single Door (S-Lon or Equivalent.)	**Nos**	**2,668**
W015	Supplying & fixing 110mm dia. P.V.C drainage "Y" junction (S-Lon or Equivalent.)	**Nos**	**2,370**
W016	Supplying & fixing 110mm dia. P.V.C drainage "Y" junction with single Door (S-Lon or Equivalent.)	**Nos**	**2,152**
	Drainage Fittings 2" (63mm) dia.		
W017	Supplying & fixing 63mm dia. P.V.C drainage bend 45 degree. (S-Lon or Equivalent.)	**Nos**	**925**
W018	Supplying & fixing 63mm dia. P.V.C drainage bend 45 degree, with single Door (S-Lon or Equivalent.)	**Nos**	**1,077**
W019	Supplying & fixing 63mm dia. P.V.C drainage bend 89 degree. (S-Lon or Equivalent.)	**Nos**	**1,195**
W020	Supplying & fixing 63mm dia. P.V.C drainage bend 89 degree, with single Door (S-Lon or Equivalent.)	**Nos**	**1,712**

Construction BSR 2024

for

Department of Buildings ***(Metric Version)***

Item Code	Item Description	Unit	Basic Rate 2024
W021	Supplying & fixing 63mm dia. P.V.C drainage Tee. (S-Lon or Equivalent.)	**Nos**	**1,195**
W022	Supplying & fixing 63mm dia. P.V.C drainage Tee. with single Door (S-Lon or Equivalent.)	**Nos**	**1,493**
W023	Supplying & fixing 63mm dia. P.V.C drainage "Y" junction (S-Lon or Equivalent.)	**Nos**	**1,226**
W024	Supplying & fixing 63mm dia. P.V.C drainage "Y" junction with single Door (S-Lon or Equivalent.)	**Nos**	**1,550**
	Drainage Fittings 1½"or (50mm) dia		
W025	Supplying & fixing 50mm dia. P.V.C drainage bend 45 degree. (S-Lon or Equivalent.)	**Nos**	**849**
W026	Supplying & fixing 50mm dia. P.V.C drainage bend 45 degree with single Door (S-Lon or Equivalent.)	**Nos**	**955**
W027	Supplying & fixing 50mm dia. P.V.C drainage bend 89 degree. (S-Lon or Equivalent.)	**Nos**	**858**
W028	Supplying & fixing 50mm dia. P.V.C drainage bend 89 degree, with single Door (S-Lon or Equivalent.)	**Nos**	**987**
W029	Supplying & fixing 50mm dia. P.V.C drainage Tee. (S-Lon or Equivalent.)	**Nos**	**1,071**
W030	Supplying & fixing 50mm dia. P.V.C drainage Swept Tee. (S-Lon or Equivalent.)	**Nos**	**1,360**
W031	Supplying & fixing 50mm dia. P.V.C drainage Tee. with single Door (S-Lon or Equivalent.)	**Nos**	**1,267**
W032	Supplying & fixing 50mm dia. P.V.C drainage Swept Tee. with single Door (S-Lon or Equivalent.)	**Nos**	**1,400**
W033	Supplying & fixing 50mm dia. P.V.C drainage "Y" junction (S-Lon or Equivalent.)	**Nos**	**1,133**
W034	Supplying & fixing 50mm dia. P.V.C drainage "Y" junction with single Door (S-Lon or Equivalent.)	**Nos**	**1,276**
	Drain Pipes P.V.C, 4" or (110mm)dia, (PNT9)- lay in Trenches		
W035	Drains, P.V.C, 110mm dia: (PNT9) laying on cement concrete 150mm thick bedding up to 600mm depth of invert including excavation, back filling and cement concrete hunching 1:3:6(25mm).	**m**	**4,919**
W036	Drains P.V.C, 110mm dia. (PNT9) laying on cement concrete 150mm thick bedding over 600mm. up to 1200mm. depth of invert including excavation back filling and cement concrete hunching 1:3:6(25mm).	**m**	**5,321**
W037	Drains P.V.C, 110mm dia. (PNT9) laying on cement concrete 150mm thick bedding over 1200mm. up to 1800mm. depth of invert including excavation back filling and cement concrete hunching 1:3:6(25mm).	**m**	**6,476**

Construction BSR 2024

for

Department of Buildings ***(Metric Version)***

Item Code	Item Description	Unit	Basic Rate 2024
	Drain Pipes P.V.C, 6" or (160mm)dia, (PNT9)- lay in Trenches		
W038	Drains PVC, 160mm dia. (PNT9) laying on cement concrete 150mm thick bedding up to 600mm. depth of invert including excavation , backfilling and cement concrete hunching 1:3:6 (25mm).	**m**	**7,216**
W039	Drains PVC, 160mm dia.(PNT9) laying on cement concrete 150mm thick bedding over 600mm up to 1200mm depth of invert including excavation backfilling and cement concrete hunching 1:3:6 (25mm).	**m**	**7,622**
W040	Drains PVC, 160mm dia.(PNT9) laying on cement concrete 150mm thick bedding 1200mm up to 1800mm depth of invert including excavation backfilling and cement concrete hunching 1:3:6 (25mm) .	**m**	**8,772**
	Drain Pipes P.V.C, 12" or (315mm)dia, (PNT9)		
W041	Drains PVC, 315mm dia.(PNT9) laying on cement concrete 150mm thick bedding over 600mm up to 1200mm depth of invert including excavation backfilling and cement concrete hunching 1:3:6 (25mm).	**m**	**20,572**

Construction BSR 2024

for

Department of Buildings ***(Metric Version)***

Item Code	Item Description	Unit	Basic Rate 2024
	X-EXTERNAL WORKS		
	Fencing		
X001	Fence barbed wire, 12 1/2 gauge, 4 points, 75mm apart, supplying & fixing on existing timber posts with G.I staples.	**m**	**107**
X002	Fence, Barbed wire 12 1/2 gauge, 4 points, 75mm apart, supplying & fixing on existing concrete posts with available hook bolts.	**m**	**68**
X003	Fence posts or struts, Milla, Na, Palu or Satin 100mm to 150mm average dia. supplying and fixing in ground complete, inclusive of sharpening and tarring.	**m**	**1,060**
X004	Intermediate fence posts or struts, cement concrete 1: 1½ :3 (20mm) reinforced with 4 Nos. 6mm (1/4")dia. M.S rods, 1700mm high square section 100mm to 150mm supplying and fixing complete as per drawing No. 68 of 22.07.1936.	**Nos**	**2,926**
X005	Intermediate fence posts or struts, cement concrete 1: 1½ :3 (20mm) reinforced with 4 Nos. 6mm (1/4") dia. M.S rods, 1700mm high square section 100mm to 150mm supplying and fixing complete as per drawing No. 68 of 22.07.1936.	**Nos**	**3,427**
X006	End post and strut for Type barbed wire fence supplying and fixing complete in cement concrete as per drawing No. 68 of 22.07.1936.	**Nos**	**17,060**
X007	Fence, bared wire, 5 strands, 12 1/2 B.W.G with 4 points at 75mm centers and R.C. posts (1:2:4) 20mm metal, reinforced with 4 Nos. 6mm rods with No. 14 B.W.G stirrups at 200mm centers. Post to be fixed at 2400mm centers including excavation, cement concrete foundation 1:3:6 (40mm) metal to corner posts and struts, and straining bolts. Struts to be reinforced with 4 Nos. 10mm roads and corner posts with 4 Nos. 12mm roads.	**m**	**2,284**
X008	Straining Bolts, 450mm long 12mm dia. making and fixing (approx.).	**Nos**	**1,492**
X009	Stoneware pipes, 100mm dia, over fume cupboards, supplying and fixing along wall with iron brackets and plugs.	**m**	**3,173**
	Chain link fencing		
X010	Supplying and fixing 50mm dia. heavy duty GI pipe uprights for receiving chain link fence. Rate to include for painting one coat of anticorrosive and two coats of enamel paint and welding 150mmx150mmx6mm thick MS plate to bottom of pipe and fixing fiberglass pipe cap 50mm dia.(Rate exclude cement concrete base & Excavation.)	**m**	**5,880**
X011	Supplying and fixing 50mmx50mm gauge 10 , 1.5m high (gauge 10), galvanized and PVC coated chain link fence . Fixed to existing GI post and including horizontal bracing with 16mmx 6mm MS flat iron with GI J bolts and washers , PVC coated tieing wires etc.,	**m2**	**2,498**

Construction BSR 2024

for

Department of Buildings ***(Metric Version)***

Item Code	Item Description	Unit	Basic Rate 2024
X012	Supplying and welding 37.5mmx37.5mmx6mm MS angle iron horizontal bracing to existing GI pipe posts. Rate to include for painting one coat of anticorrosive paint and two coats of enamel paint.	m	1,635
X013	Fabricating and fixing of MS grills with 25mmx 6mm flat iron frame and 6mm dia.MS. rods welded to diamond shape 75mm centers both ways.	m2	9,455
	LANDSCAPING		
	Laying turf sods		
X014	Supplying & laying turf sods of approved type including bedding material, pegging and watering.	m2	1,316
	Road Construction		
X015	Supplying and pilling approved 100mm aggregate for road construction, at site excluding hire charges.	m3	2,768
X016	Supplying and pilling approved 38mm aggregate for road construction, at site excluding hire charges.	m3	2,981
X017	Supplying and pilling approved 20mm aggregate for road construction, at site excluding hire charges.	m3	3,102
X018	Supplying and pilling approved 12mm aggregate for road construction, at site excluding hire charges.	m3	2,581
X019	Spreading ,watering & rolling 12mm aggregate including hire charges of roller.(Materials Paid Separately)	m3	3,246
X020	Spreading ,watering & rolling 50mm-20mm aggregate including hire charges of roller.(Materials Paid Separately)	m3	3,942
X021	Bitumen(80/100) surfacing first coat using 2Ltr/Sq.m including blinding with sand at the rate of 125 Sq.m/Cu.m.	m2	510
X022	Bitumen(80/100) surfacing 2 nd subsequent coat using 1 Ltr/Sq.m including blinding at the rate of 125 Sq.m/Cu.m	m2	319
X023	Emulsion /Cold bitumen (CRS-1) surface treatment 1st coat with 3.5 ltr/Sq.m including blinding with sand,@125 Sq.m/Cu.m(Manual)	m2	662
X024	Emulsion /Cold bitumen (CRS-1) surface treatment subsequent coat using 0.075 ltr/Sq.m including blinding with sand,@125 Sq.m/Cu.m(Manual)	m2	206