# Building Schedule of Rates

## For

# CONSTRUCTION WORKS

## OF

# Government Buildings

# B.S.R -2020

## Department of Buildings

---

**B.S.R. Workgroup Committee,**
**Dept. of Buildings,**
**" Serhsiripaya",**
**Battaramulla.**

# Contents

Page Nos.


| | | | |
|---|---|---|---|
| **A.** | *INTRODUCTORY NOTES & ADDITIONS TO SPECIFICATIONS* | | |
| | *A.1* | *INTRODUCTORY NOTES* | *A01-A03* |
| | *A.2* | *ADDITIONS TO SPECIFICATIONS* | *A04-A07* |
| **B.** | *PRICING PREAMBLES* | | *B01-B16* |
| **C.** | *DEMOLITIONS* | | *C01-C01* |
| **D.** | *EXCAVATION & EARTHWORK* | | *D01-D02* |
| **F.** | *CONCRETE WORK* | | *F01-F04* |
| **G.** | *MASONRY WORK* | | *G01-G02* |
| **H.** | *WATER PROFING* | | *H01-H01* |
| **J.** | *STRUCTURAL METAL WORK* | | *J01-J01* |
| **K.** | *METAL WORK* | | *K01-K05* |
| **L.** | *WOOD WORK* | | *L01-L09* |
| | *L1* | *CARPENTRY-STRUCTURAL TIMBER WORK-(ROOF)* | *L01-L01* |
| | *L2* | *JOINERY (WALLS)* | *L01-L05* |
| | *L3* | *IRON MONGERY* | *L05-L09* |
| **M.** | *CLADDING* | | *M01-M01* |
| **N.** | *PARTITION LINING / SUSPENDED CEILING* | | *N01-N06* |
| **P.** | *ROOF COVERING* | | *P01-P03* |
| **Q.** | *PLUMBING / SANITORY INSTALLATION* | | *Q01-Q16* |
| **R.** | *MECHANICAL INSTALLATIONS* | | *R01-R06* |
| **S.** | *ELECTRICAL INSTALLATION* | | *S01-S09* |
| **T.** | *FINISHING & FLOORING* | | *T01-T05* |
| | *T1* | *PLASTERER* | *T01-T02* |
| | *T2* | *PAVIOR* | *T02-T05* |
| **U.** | *GLAZING* | | *U01-U01* |
| **V.** | *PAINTING & DECORATING* | | *V01-V03* |
| **W.** | *DRAINAGE SYSTEMS* | | *W01-W03* |
| **X.** | *EXTERNAL WORK* | | *X01-X02* |


DOB Build Future ..... Restore Past

# A. INTRODUCTORY NOTES & ADDITIONS TO SPECIFICATIONS

## A.1 INTRODUCTORY NOTES

### A.1.1 Trade Names ;

Where trade names , brands and / or catalogue numbers are referred to sole preference to any material or equipment is not intended . Any other material or equipment may be used, provided that the characteristics of type, quality,appearance, finish, method of construction and / or performance is not less than what is specified and provided, and prior approval is obtained.

### A.1.2 Based Standard

This BSR has been prepared generally in accordance with the principles of "Method of Measurement of Building Works(First Revision) , Sri Lanka Standard 573:1999"

### A.1.3 Analysis for Basic Rates

The Material and Labour component required for the various items of work including the minimal plant required for same is detailed in the analysis of the Basic Rates which consist of the following

**(a) Materials**

The quantities of material required for the items are computed from known data and experience. Their total value is calculated on the basis of current prices at source of supply. Unless otherwise stated wastage is allowed in the norms.

**(b) Transport**

This component provides for the cost of transport of material from sources of supply to the sites of work. This component is usually added to the material cost.

**(C) Labour**

The labour wages are as approved by the Government from time to time and on the basis of an 8 hour working day.

Rates used in this B.S.R. are as follows.

| Category | Rate/ Per day |
|---|---|
| Unskilled Labour | 1500 |
| Semi Skilled Labour | 1700 |
| Skilled Labour | 1900 |
| Special Skilled Labour | 2100 |

**(d) Plant**

This component provides for the minimum plant required for the item of work. The cost of tools is provided for in the Overheads component.

**(e) Basic Cost**

The basic cost is the sum of the costs of items **(a),(b),(c)**and **(d)** above.



This BSR is for Construction works only

## A.1.4 Preliminaries

Preliminaries for building works should be claimed under guide lines of ICTAD Publication No. ICTAD/ID/04 Second Edition - June 2009

## A.1.5 Overheads and Profit factors

These rates dose not include any overhead and profit factors and taxes such as VAT etc. Hence it should be included whenever necessry according to the nature of the contract considering the usage of priliminaries as mentioned in the clause A1.4 above.

## A.1.6 Allowances for lifting work

Allowances to be made in the rates for lifting respect of work on upper floors.

In the analysis of the various items of work (other than specified) in the following pages, the rates refer to work on the ground floor.

### (a). Ground and 3 upper floors

To these rates the percentage (of the ground floor rates) indicated in table below should be added to obtain the rates applicable to the 1st, 2nd and 3rd floors. This B.S.R is limited to work on the ground and 3 upper floors only.

| Serial No. | Item | Ground to 1st floor % | Ground to 2nd floor % | Ground to 3rd floor % |
|---|---|---|---|---|
| 1 | Concrete | 3 | 5 | 7 |
| 2 | 9" Brickwork (Area wise) | 5 | 7 | 9 |
| 3 | 9" Brickwork (Volume wise) | 5 | 7 | 10 |
| 4 | 4 1/2" Brickwork | 5 | 7 | 10 |
| 5 | Steel reinforcement | 2.5 | 5 | 4.5 |
| 6 | Plastering | 5 | 10 | 15 |
| 7 | Floor Tiling | 2 | 4 | 6 |
| 8 | Wall Tilling | 2 | 4 | 6 |
| 9 | Roof Calicut tile | 3 | 6 | 9 |
| 10 | Roof asbestos | 3 | 5 | 7 |
| 11 | Ceiling work | 3 | 5 | 7 |
| 12 | Painting | 3 | 6 | 9 |

### (b).Fourth floor and above

If a building has more than four floors or when the contract period is compressed to a few months, then it will be necessary to allow for the use of heavy machinery such as tower crane, mobile cranes, dumpers loaders, batching plant for mixing of concrete ,bins for the storage of concrete material etc.and also for the employment of contract managers and additional staff.

The cost of such items of work will not be accommodated within the general ' Mark-Up' and will have to be provided for in separate items such as preliminaries to the contract.

## A.1.7 Earth work and landscaping

Soils met within excavation have been classified as follows.

1. Soft /Loose soil
2. Ordinary soil
3. Hard /Dense soil
4. Mud/ wet clay
5. Soft disintegrated rock(i.e. rock not requiring blasting)
6. Hard rock - a) Where blasting is approved
   b) Where blasting is prohibited

The classification of soil in note 1 above and the analysis provide for the different type of soil will help the estimator in arriving at the actual of excavation, for which he will have to allow in his estimate.

Under note 1(6) b Hard rock ,an analysis is provided for removing Hard Rock met with in foundation excavations where blasting is prohibited or cannot be done, like in built up areas where blasting can cause damage to adjoining buildings

For excavation beyond the depth of 5' 0" an additional unskilled laborer should be added for every additional depth of 5' 0" or part thereof for each cube of excavation beyond the original 5' 0" depth

DOB Build Future ..... Restore Past



This BSR is for Construction works only

## A.2 ADDITIONS TO SPECIFICATIONS

### A.2.1 Timber :

Unless otherwise specified in the respective Trades / Sections , the timber for all trades shall be as specified in Carpentry and Joinery.

All timbers under exceptional Circumstances, any equivalent timber to the given Species may be used with the approval of the Engineer.

**(Group-1): Door, Window and Fanlight Frames**

| | | | | | |
|---|---|---|---|---|---|
| Category A | Satin | Palu | Milla | Ketakala | Tulang |
| | Halmilla | Mee | Hulanhik | Wewarana | Valdel. |
| | Kohomba | | | | |
| Category B | Grandis | | | | |

**(Group-2): Door , Window and Fanlight Sashes , Cupboards, Counters and Shelving**

| | | | | |
|---|---|---|---|---|
| Category A | Satin | Tulan | Halmilla | Mahogany |
| | Kohomba | Wewarana | Hulanhik | Sooriya mara |
| Category B | Ginisapu | | | |

**(Group-3): Roof Framework**

| | | | | | |
|---|---|---|---|---|---|
| Category A | Madan | Milla | Palu | Wewarana | Tulang |
| | Mee | Valdel. | Micro | Kolon | Etathimbiri |
| Category B | Domba | Grandis | | | |

**(Group-4): Ceiling Framework and Partitions**

| | | | | | |
|---|---|---|---|---|---|
| Category A | Satin | Palu | Milla | Ketakala | Tulang |
| | Halmilla | Mee | Hulanhik | Wewarana | Valdel. |
| | Kohomba | Etathimbiri | | | |
| Category B | Domba | Grandis | | | |

**(Group-5): Valance Board and Valley Boarding**

| | | | | | |
|---|---|---|---|---|---|
| Category A | Kolon | Tulang | Val Del | Kohomba | Sooriya mara |
| | Mahogany | Satin | Hulanhik | Wewarana | |
| Category B | Ginisapu | | | | |

**(Group-6): Beadings :**

| | | |
|---|---|---|
| Alstonia | Mahogany | Lunumidella |

**(Group-7): Special Timber**

| | |
|---|---|
| Jak | Teak |

**Source: Selection of timber species- State Timber Coorporation.**

## A.2.2 Aluminium Panels

All Aluminium sections shall be fully treated extruded Aluminium alloy sections in accordance with BS 1470,1471, 1473, 1474 or latest relevant EN standed

All Aluminium sections to be locally extruded

All Aluminium sections shall present clear, straight and sharply defined lines. They shall be free from defects, impairing strength, appearance and durability.

### *Finish*

All members shall be finished either by

( i ) Anodizing or

( ii ) Powder coating ( What ever specified in Aluminium Items )

Anodizing -Exposed surface of all members shall be anodized using two steps. Anodizing process to an anodic thickness of not less than 10-15 microns and shall be free of any defects.

### *Powder coating*

Powder coating shall be carried out using polyester coating with proper and appropriate pre- treatment to a thickness of not less than 60-80 microns, measured on all significant surfaces.

### *Screws and Hardware Items*

Concealed screws, nuts, bolts, rivets and other fastening devices shall be of Aluminium, non-magnetic stainless steel or other approved corrosive resistant materials. If visible, they shall blend with the finish of the framing Aluminium sections.

### *Glass*

Glazing shall be minimum of 5mm thick clear float glass. Glass shall be secured at all edges with compression gaskets and glazing beads. When fixing glass, all glazing sealant shall be carefully applied and cleaned off properly.

### *Workmanship*

The fabrication and installation of all Aluminium work must be carried out by specialist tradesmen.

All dimensions shown on the drawings and the shop drawings must be verified by actual site measurement before fabrication and installation. Any cutting to enlarge the size of openings and approved practical method to fill the excess void behind frames required after installation shall be executed by the Contractor at his own expense.

All Aluminium members shall be factory fabricated to the best standard of workmanship under experienced factory supervision and control.

Materials, method of fabrication, assembly, installation, fastenings, supports, braces, operating parts and the like shall be in accordance with the approved shop drawings.



This BSR is for Construction works only

All joints in frames at corners, junctions and intersections shall be mechanically jointed and be such that when assembled they are as strong and rigid as adjoining sections. Due care must be taken to ensure that all joints are water tight and leak-proof. Joint lines should not be visible.

Provisions must be made for expansion and contraction in horizontal and vertical members which are exposed to the weather or environments. Any distortion of members or any glass cracked or broken as a result of inadequate provisions must be rectified by the Contractor at his own expenses.

All works shall be securely installed and anchored in position, set plumb, square and level in accurate alignment with other work, all in accordance with the approved shop drawings to the Engineer's satisfaction.( The allowable tolerance in terms of specified dimensions shall be plus/minus 1.5mm.)

***Submissions***

The Contractor shall submit shop drawings showing the following information where appropriate to the item ;

layout (Sectional plan and elevation) of complete assembly

- full size sections of members
- methods of assembly
- methods of glazing
- methods of installation, including fixings caulking, flashing
- provisions for vertical and horizontal expansion
- junctions and trim to adjoining surfaces
- fittings and accessories

The Contractor shall submit certificates from the Aluminium manufacture and/or an approved testing laboratory which attest that the coating thickness offered is as specified.

***Doors & Windows***

Frame and /or sash sections shall be of extruded EN-AW 6063-T5 Aluminium Alloy

***Aluminium Louvers***

Fixed louvers shall be of the weather proof type, suitable for overcoming water carried- over by wind and the fixed louvers shall have free areas of not less than 50%

The Contractor shall provide a guarantee in respect of the weatherproof properties of the fixed louvers.

All powder coatings shall match the windows. Panels shall be so constructed as to be completely weather proof at junctions with adjoin structures .



This BSR is for Construction works only

***Partitions***

The frames shall be properly machined to permit easy assembly and to form weather-tight joints when caulked.

Partition members shall be 76mm in depth and the thickness of 1.2mm.

Following dimensions are applied for the frame members of each assembly units

| Assembly Unit | Minimum Member Depth (mm) | Minimum Member Thickness (mm) |
|---|---|---|
| Casement Window,Fanlight | 70 | 1.5 |
| Sliding door/Window | 80 | 1.5 |
| Door | 100 | 1.5 |
| Fixed glass Window | 100 | 1.5 |

Rates shall include for all necessary hinges, screws, rubber beadings, Skelton bolts, Aluminium louvers, pinhead stickers, etc.(Door Locks ,Door Handles,Door closers paid separately )

Locks- (Union or equivalent )

Hinges-(Union or equivalent )

Handle-Grade 304 stainless steel

***Reffer notes 7.(d), Under pricing preambles*

Build Future ..... Restore Past

# B. PRICING PREAMBLES

## 1. GENERAL

a. The Bidder shall read and be conversant with the full description of workmanship and materials as described in this document under section (A) ,Pricing preambles, notes on trades in BSR and ICTAD Specification for the respective items of work/ trades prior to the preparation of the Bid.

b. The Bidder shall refer to the relevant Clauses of Pricing Preamble when pricing composite item of works.

c. The rate for each item must be comprehensive and must include for complying in all respects with the requirements of the aforesaid specifications, these Pricing Preambles, cover all the obligations under the Contract, and all matters and things necessary for the proper construction, completion and maintenance of the Works. No claim for additional payment shall be allowed for any error or misunderstanding by the Contractor of the work involved.

d. The rate for each item shall also include for all the following -

i. Labour and all connected costs ;

ii. Materials and goods including all connected costs;

iii. Preparatory works and setting out of particular item ;

iv. Complying with regulations of the Municipal Council and/or any other relevant authority under which particular item of work is to be executed unless otherwise included in the Preliminaries ;

v. Fitting and fixing materials and goods in position, including hoisting to any height or lowering to any depth and all temporary works, equipment and small tools ;

vi. Plant and equipment unless otherwise included in Preliminaries ;

vii. Handling of materials and working in situation where there is very restricted working space or no working space ;

viii. Square cutting and Waste of materials ;

ix. Forming of ends, angles, miters and junctions between straight and raking or curved work ;

x. Protecting and cleaning ;

xi. All other incidental works and necessary works which are not described in the B.O.Q. but described in the aforesaid specifications and or shown in the drawings for the proper completion of the relevant item of work ;

xii. Establishment charges and overheads( not included in preliminaries or anywhere in the Bill Of Quantities), and profits.

e. In addition to above, the rates for items of work in Substructure shall include for the works at depths extending below ground water table where applicable including excavation under water,removal and disposal of mud and sand and preparation of place to a condition suitable for proper execution of the works.

## 2. EXCAVATION AND EARTHWORK

a. All works under this section are measured net and no working space is allowed.

b. The Contractor shall be responsible for the design and execution of the excavation method which is subject to scrutiny by the Engineer. However, scrutiny by the Engineer shall not in any way relieve the contractor of his responsibilities and duty of care.

c. Existing ground levels shown in the Drawings have been taken at the surface of the ground, with no particular differentiation to indicate buried foundations, pavings etc.

d. The Contractor shall note that the rate for compacted earth fill and granular fill, stone, gravel and sand beds shall include for imported materials or materials from borrow areas.

e. Rates for Excavation & Earthwork shall include for -

i. Accepting site as found and preparing to condition suitable for proper execution of the Works

ii. Excavating by whatever means are necessary including excavation done manually or by machine in any type of ground including ground with boulders (except rock) and excavation around existing RCC. bored piles and jet grout piles ;

iii. Trimming sides, keeping clean and consolidating bottom of basement, sumps, pits and trenches ;

iv. Backfilling and disposal of surplus excavated materials as specified and directed ;

v. Any necessary additional works required due to

a. Working space required by the Contractor ;
b. Earthworks supports ;
c. Formwork ;

vi. Any additional trimming or appropriate back- filling to provide specified or approved formations and profiles necessitated by the uneven excavation of the earth, unless otherwise measured separately ;

f. Rates for compacted earth fill, granular fill and gravel and sand beds shall include for finishing sub-grade to slopes and falls, depositing in layers, leveling, blinding, and machine or hand-packing to form vertical or battered or level faces, and for forming sinking where required under floor slabs or sub-floor layers.



This BSR is for Construction works only

g. Rates for approved damp-proof membrane shall include for laps, and straight, raking and circular cutting, and for notching around all obstructions.

## 3. CONCRETE WORK

a. Rates for concrete work shall include for -

i. Mixing as per specification, depositing, handling, hoisting and placing at any height or depth ;

ii. In case of readymix concrete, transporting, admixtures, handling, pumping/hoisting and placing at any height or depth ;

iii. Packing and tamping around reinforcement, including vibrating ;

iv. Contractor's designed kickers, construction joints and sealents ;

v. Finishing to slopes and falls, and preparing surface ready for screeds or paving, where necessary, including cutting to sizes and temporary supports to form necessary grooves ;

vi. Curing ;

vii. Preparation of ground surface, grading to slope and falls, if any, and machine or hand packing to form vertical or battered or level surface and all necessary formwork to edges of blinding concrete in case of pile caps ground slab/ramps/beams.

***FORMWORK:***

a. Formwork for similar concrete members are measured together irrespective of the height or depth and the shape or form.

b. Extra-over rate for a particular type of high quality formwork should be applied only for the areas of formwork which requires such high quality type formwork as specified.

c. Formwork shall be properly designed and strictly as described in the specifications for the particular type of concrete surface finish and it should be sufficiently strong and grout tight.

d. Faces of Jet grouting piles, masonry and concrete work which will be formed or used as formwork shall not be measured as formwork and no payment shall be made for same.

e. <u>Rate for formwork shall include for -</u>

i. Fabricating setting up and erection at any height or depth ;

ii. Strutting, supporting through lower floors and supporting at any level, including additional propping, strutting and supporting decks ;



This BSR is for Construction works only

iii. Coating with shuttering oil and or lining ;

iv. Easing, striking and removing ;

v. Cleaning, preparing for reuse ;

vi. Removal when no longer required ;

vii. Props, stays, struts, wedges, bolts, incidental items and materials such as nails, screws anchors hooks etc ;

viii. All overlaps and passing at angles ;

ix. Labour at intersections and narrow widths ;

x. Rubbing down and making concrete surface good after removal of formwork ;

xi. All fillets, to form grooves, rebates and throats, splays or chamfers, raking and circular cutting, and cutting around all pipes, sleeves, conduits, ducting, metal sections and fittings ;

xii. Providing samples as required by the Engineer of the different formed finishes specified.

***REINFORCEMENT:***

a. i. Standard length of reinforcing bar for the purpose of measurement shall be 6.0 m. or 12.0 m

ii. Payment for bar reinforcement shall be to be nearest Kilogram.

b. Rates for reinforcement shall include for -

i. Rolling margin ;

ii. Preparation of bar bending schedules ;

iii. Straightening as required and cleaning of bars ;

iv. Cutting, bending and binding ;

v. Hoisting and placing in position at any height or depth ;

vi. Binding wires, and cover blocks.

vii. Necessary spacers. (inevitable laps & chairs paid separately)

viii. Aligning and supporting in position during concreting.



This BSR is for Construction works only

**PRECAST CONCRETE WORKS:**

a. Rates for precast concrete works shall include for -

i. Moulds and for formwork with the required finish to all exposed surfaces in accordance with the specifications, hacking surfaces to form key for rendering etc, and hoisting to any height or depth including providing any lifting holes or other devices to the approval of the Engineer,building in, including bedding and jointing in mortar as required, and any necessary strutting and supporting.

ii. The requirements of the Pricing Preamble clauses which refer to Concrete Work,Reinforcement and Formwork.

iii. Loading, transporting to Site, unloading, handling and stacking.

iv. Hoisting and fixing in position at any height or depth.

## 4. MASONRY WORK

a. In the calculation of the volumes of brick wall which are not multiples of the size of standard bricks, the thickness of such walls shall be taken as the thickness of full bricks from which they can be cut. The same principle of calculation of volume shall be used for all brickwork of which the cross-sectional dimensions are not multiple of brick sizes.

b. Rates for brickwork/Block work shall include for -

i. Plumbing, angles,straight cutting,forming rebates,reveals and raking out joints for plastering;

ii. Splay cutting, rough cutting, fair cutting, forming chases or grooves for slabs, partitions,staircases, roofs and the like, bonding ends of walls, building in or cutting and pinning in and making goods on lintels, timber and steel works ;

iii. Building at any level or height of slabs or beams, additional labour in kerbs, isolated and attached piers, all cutting, bonding at angles and intersections, building into or against adjacent work, wedging and pinning up to soffits;

iv. Supplying and fixing metal clamps, Galvanized, steel boundary ties, and brick reinforcement etc;

v. Necessary cutting required in walls which are not multiples of brick size ;

vi. Preparing existing walls for raising and pinning new brickwork ;

vii. Bonding new walls to concrete faces and old walls where necessary, and materials to be used for such bonding.

**Damp Proof Course**



This BSR is for Construction works only

a. Rates for Damp Proof Course shall include for -

i. Necessary leveling screed and trimming top of rubble/block/brick plinth wall ;

ii. Fair edges, rounded edges, drips and arises, angle fillets ;

iii. Turning nibs of asphalt into grooves ;

iv. Cutting to line and jointing new to old asphalt.

## STONE WORK

### a Generally

Stones are defined as consolidated aggregates of one or more minerals and includes all types of rock used in the construction industry.

### b Rubble work

Rubble Stone masonry built of stones either irregular in shape as quarried or shaved and only hammer dressed and having comparatively thick joints.

Rates for Rubble Masonry shall include for -

i. All joggles, cramps, dowels, ties, templates ;

ii. Plumbing, angles, fair returns, setting, jointing, eaves filling, pointing and fixing in position, hoisting to any given height or depth ;

iii. Bonding ends of walls, rough cutting and fair cutting ;

iv. Leveling up in walling for Damp Proof Courses, sills, thresholds, string courses, copings and the like ;

v. Forming straight vertical joints next to dressings, panels, brickwork etc ;

vi. Forming openings and dressed margins ;

vii. Forming chases, throats, rebates, margin flutes, sinking, chamfered and rounded edges, and all labour connected therewith.

### c Ashlar Stone masonry using dressed stone blocks of given dimensions having faces perpendicular to each other and laid in courses.

Rates for stone work shall include for:-

i. Extra material for curved work
ii. All rough and fair cutting
iii. Dressing

iv. Forming rough and fair grooves, throats, mortices, chases, rebates, holes, stops and mitres.



This BSR is for Construction works only

v. Raking out joints for key
vi. Labours in eaves filling
vii. Dressed margins to rubble work
iix. Leveling uncoursed work
ix. Rough and fair square cutting
x. Centering
xi. Wedging up and pinning to concrete soffits and steel work
xii. Building in frames, flashing, damp proof courses including filling hollows of corner blocks with mortar
xiii. Building in ties, lugs, plates, lintels, pipe sleeves, inserts, switch boxes and the like. As the work proceeds.

d **Stone Veneering work (Face rubble work)**

i. Stone lining upto 80mm along planes parallel to natural bed. The natural bed may be masonry of brickwork or rubbel work, concrete surface.
ii. Stones cut into slabs of required thickness.
iii. Dressed to very close tolerances.

## 5. WATER PROOFING

a. Rates for Water Proofing shall include for ;

i. For necessary leveling and trimming top of rubble/block/brick plinth wall ;

ii. Fair edges, rounded edges, drips and arises, angle fillets ;

iii. Forming internal and external angles, bonding bricks/blocks and the like ;

iv. Turning nibs of asphalt into grooves and asphalting around brackets ;

v. Cutting to line and jointing new to old asphalt ;

vi. Temporary screeds, ground and rules.

## 6. STRUCTURAL STEELWORK

a. Rate shall include for :

All shop fabrication work, including cutting, drilling, bolting, riveting, welding, grinding, delivering, unloading, hoisting, erecting and fixing.

## 7. METAL WORKS

a. All Aluminium sections shall be fully treated extruded Aluminium alloy sections in accordance with BS 1470,1471, 1473, 1474 or latest relevant EN Standed

b. Contractor to prepare shop drawings for approval of the Engineer.


This BSR is for Construction works only

c. Rates for Metal Work shall include for anchors, screws, dissimilar metals and providing thermal movement and the preamble clauses for Structural Steel Work where relevant and they shall apply equally to relevant items of this section.

**Aluminum components**

d. Fabrication & fixing of Aluminum components shall be carried out by experienced tradesman.The Contractor shall furnish particulars of Aluminum fabricator through the engineer for his approval.

The Contractor will be required to furnish a guarantee on material and workmanship for a period of 8 years from the date of handing over of Works in the form required by the employer, binding the Aluminum manufacturer and the Contractor jointly and severally

Material: As described under section A (Additions to specifications)

## 8. ROOF COVERING AND ROOF PLUMBING

a. Rates for roof covering and roof plumbing shall include for :

i. Hoisting, placing and fixing in position ;

ii. Straight cutting, raking cutting, circular cutting, notching, and working around obstructions and waste ;

iii. Nails, screws and the like ;

iv. Drilling and making holes or opening and the like;

b. Rates for flashings shall include for the following in addition to the requirement of "a" above -

i. Bending and cutting to required shape and forming roll edges ;

ii. Angles, edges and ends ;

iii. Notching over roofing ribs or dressing into roof cover/concrete as the case may be ;

iv. Forming and dressing into or around walls at obstructions and the like ;

v. Stepping up ;

vi. Sealing with sealant materials.

## 9. CARPENTRY(Roof and ceiling frame)

a. Sizes of all timber given are finished sizes.



This BSR is for Construction works only

b. All timber shall be well seasoned and treated against insect and termite attack before fixing in position

c. Rates for carpentry shall include for -

i. Any type of cutting required, sawing, notching, drilling, trimming, framing, jointing, splayed edges and the like, hoisting and fixing in position with nails, spikes, plugs, screws, and gluing and priming to joints and ends ;

ii. Forming splayed edge, grooves, chamfers, scribed and rounded edge, beveling,molding and the like ;

iii. Plugging, wedging, nuts and washers with bolts,sprockets and pins and the like ;

iv. Nogging or solid bridging, cut between studs or joints for structural timber.

v. Rebating, singings, grooving, mortising ;

vi. Additional timber lengths required for carpentry jointing ;

vii. Protection and keeping clean for staining, polishing or painting where applicable ;

d. Rates for roof decking shall include for machine sanding, protecting and preparing in addition to the requirements c above.

e. Rates for walls and ceiling lining shall include for jointing and fixing to walls/ ceiling/ eaves etc. all cover and joint strips, in addition to the requirements c above.

f. Rates for timber paneling/wall lining shall include for cover moldings, sills, stiles and head moldings to openings as relevant.

## 10. JOINERY

a. Sizes of all timber given are finished sizes.

b. All timber shall be well seasoned and treated against insect and termite attack before fixing.

c. Timber used for joinery works shall be well seasoned well treated and in one species of special class timber recommended for the particular class of Joinery works as specified in the Specification.

d. Rates for Joinery shall include for -

i. Any type of cutting required, sawing, notching, drilling, trimming, planing, forming and jointing and the like, fixing in position complete with nails, spikes, plugs, screws and gluing and priming to joints and ends ;

ii. Forming splayed and tongued edges, rebates mortises, grooves, chamfers, scribed and rounded edges, beveling, moulding, margin and the like and rounded corners, sinkings ;

iii. Working to stated sizes, for all short lengths making mitres, joints and ends ;



This BSR is for Construction works only

iv. Necessary bolts, dowels metal clips, anchors, grips and fixing joinery ;

v. Glueing, dowelling, plugging, wedging pining and the like ;

vi. Punching heads and filling with approved filler if nails or pins are used for fixing ;

vii. Countersinking and filling heads with approved filler, if brass screws are used for fixing ;

viii. Painting rebates of frames before fixing glass ;

ix. Bedding in cement mortar filling and hanging to frame lining ;

x. Keeping clean for staining, polishing or painting;

xi. Painting, Laquering or Varnishing as specified.

e. Preambles for Glazing section and a, b and c under Painting and Decorating section shall equally apply to Joinery works.

f. Ironmongary

i. All cutting, fitting, sinking, boring, mortising ;

ii. Matching screws for ironmongery

iii. Removing during decoration, refixing after decoration, leaving oil and in proper working order on completion and supplying and labeling all keys and handing over to Employer.

## 11. WALL,FLOOR AND CEILING FINISHES

a. i. All works under this trade shall be measured after deduction for voids,openings, doors and windows

ii. All other small quantities/panels/narrow widths/ arises/ reveals/ angles/ ends/short lengths including those of tiling work on door and window jambs and reveals are measured together with the respective tiling item and labour in such work shall be included in the rate for the main finishing item and they shall not be measured/paid separately.

b. <u>Rates for wall, floor, ceiling finishings and wall floor screed and bedding shall include for -</u>

i. All temporary rules, screeds, templates and supports, curing and cleaning off on completion and exact thickness required to finish ;

ii. Caulked joints and making good and cutting around bolts, pipes conduits,sleeves, ducting, fittings, sections, obstructions and the like ;

iii. Tamping and compacting ;

iv. Raking out joints of new brickwork/Block work or hacking concrete to form key, including brushing, cleaning off and dampening ;



This BSR is for Construction works only

v. Forming internal and external angles and arises ;

vi. Any extra thickness required to finish to true levels ;

vii. Any additional dubbing out required to plastered surfaces of brickwork and to the finished surface of concrete to obtain the requisite standard of finish ;

viii. Samples to be submitted for the approval of the Engineer.

c. Rates for tile slab or block finishing to floor and wall shall also include for the following in addition to the above -

i. Straight raking and circular cutting ;

ii. Dubbing out or packing to concrete surface to correct deviations within specified tolerance ;

iii. Laying or finishing to falls or cross falls ;

iv. Expansion joints at perimeter and between bays where required in case of floor tile paving ;

v. Sand blasting, cleaning, waxing and appropriate floor finishings.

d. Rates for ceiling lining shall include for the following

i. Working to sides and soffits of attached or isolated beams and soffit of staircases where relevant;

ii. Additional forming required for lighting and air-conditioning grills ;

iii. Straight, raking and circular cutting ;

iv. Neoprene sealing for air tightness around hatches if any ;

v. Matching edges where cutting occurs and for filling the heads of fixings with approved filler where relevant ;

vi. Painted mild steel hanging rods.



This BSR is for Construction works only

## 12. GLAZING

a. i. Type of Glazing shall be as specified.

ii. Thickness of glazing shall be as per the design of the approved specialist contractor who will be engaged by the Contractor. However, the minimum thickness shall be 6mm.

b. Rates for Glazing shall include for -

i. Glazing, fixing, bedding priming and panel pins and other materials and labour for same and cutting to size ;

ii. Templates, straight cutting, circular cutting, grinding edges or special type of edges required and sand blasting ;

iii. Glazing beads, washlether or neoprene strip, glazing sealant, weather stripping, caulking joint silicone joint ;

iv. Replacing cracked or broken glass ;

v. Making holes where necessary ;

vi. Samples to be submitted for the approval of the Engineer.

## 13. PAINTING AND DECORATING

**Note**
Colour and the quality of all paint and other painting materials shall be approved by the Engineer prior to use.

a. Rates for painting shall include for -

i. Preparation of surfaces, cleaning down, smoothing, etc ;

ii. Submission of samples for the approval of the Engineer ;

iii. Protection of floors, walls and fittings etc ;

iv. Working to returns, painting in any colour, multi- colour works, cutting into line at junctions of different colours at angles or plain surfaces, painting in small quantities ;

v. Cleaning down upon completion

b. Rates for work to isolated general surfaces shall include for working on door frames, linings,window subframes (where of a differing material to the window), skirting, rails, architrave's, bars,posts, balusters and the like.

c. Rates for work to glazed general surfaces, glazed windows and the like (measured both sides,flat over glass, irrespective of size and panes) shall include for work to edges and glazing rebates, returns and moldings of frames, mullions, transoms, architaves and the like.


This BSR is for Construction works only

d. Rates for work to pipes and conduits (which shall include trunking, ducting and the like) shall include for all work on hangers, supports, brackets and the like.

## 14. PLUMBING

a. <u>The rates for Plumbing shall include for :</u>

i. Refer specifications for full description of materials and workmanship.

ii. Screws, nails, sockets, connectors, backnuts, nipples, and standard pipe fixing or supporting clips, saddles, brackets straps, screws, nails, solder rivets connectors, flanges pipe sleeves, brackets, made bend holder bats and the like.

iii. Short lengths, joints connections and couplers in running length.

iv. Sealing, fixing and support with holder bats or pipe clips cut and pinned built in wall or slabs.

v. Plugging screwing to walls or ceiling

vi. All laps, straight cutting and waste

vii. The fittings including bends, tees, collars, reducers elbows, valve sockets, junctions, caps and the like for pipe less than or equal 50mm dia pipe.

viii. Jointing compound, solvent cement and incidental materials and labour.

ix. Connecting pipes to sanitary fixtures and appliances.

x. Standard and special pipe fixing arrangement where necessary fittings, supporting clips,saddles,brackets, holder bats straps etc.

xi. All builders works such as chasing and forming holes through brick work/ blockwork/ foundations and concrete slabs beams columns floor slabs manholes and like and making good all damages.

xii. Testing and disaffection after completion.

b. <u>Rates for sanitary fittings shall include for</u>

i. Fittings such as taps, waste water outlet, flushing cistern, internal overflows and the like and supporting brackets, incidental materials for fixing.

ii. Assembling, jointing together, fixing components parts and jointing to pipes including necessary coupling and for leaving perfectly clean undamaged and in perfect working order as on completion.

c. Jointing and or connecting pipes to sanitary fittings.



This BSR is for Construction works only

Any special water supply and drainage fittings such as bends, tees, reducers etc. unless otherwise specified separately in the Bill of Quantities, shall be deemed to have been included in the relevant items and such items should accordingly be rated to include for such specials etc. and for any extra work involved and the satisfactory completion of such items.

Where pipes pass through walls or slabs these shall be wrapped with a layer of inert materials. For pipes exceeding 50 mm dia sleeve pipes shall be used for the full thickness of slabs, walls or beams through which the pipes pass.

**DRAINAGE WORK**

a. The provisions and the clauses of precedence trades shall equally apply to relevant item of this trade.

b. The rates for trench excavation for pipes shall include for depending and widening the trench as necessary to enable the barrels of pipes of rest on firm and to facilitate jointing.

c. The rates for rock excavation in trench excavations shall include for importing selected materials to replace any excavated rock which is unsuitable for back filling and for all additional rock excavation and appropriate filling beyond the maximum measurable in accordance with the specification.

d. The rates for concrete beds and surrounds to pipes shall include for flexible joints and any necessary formwork where required by the specification.

**15. ELECTRICAL INSTALLATIONS**

a. The execution of Electrical Installation shall every respect comply with the current Regulations of the Institute of Electrical Engineers, London, requirements of Ceylon Electricity Board and the area Authority.

b. The rates for equipment and control area, distribution boards, meters, switches, fuses, etc. shall include for connecting up, fixings and supports for the complete installation and for suitable mounting boards, frames, supports, housings and cabinets where required.

c. The rates for cables, tape, bus-bar trunking etc. (except where included in sub circuits or electrical points) and the like shall include for joints in the running length, all allowances for sagging snaking, for drawings through conduits,laying in trunking of surface fixing where retired with cable supports, clears, hangers, channels, insulators and the like.

d. i. The rates for cables and the like laid in benches shall include for drawing through conduits or ducts where required.

ii. The rates for cable terminations shall include for all connections point boxes, insulating and jointing materials, cable terminations glands, lock nuts, bushes and the like.



This BSR is for Construction works only

e. i. The rates for conduits trunking cable tray etc. (except where included in sub circuits of electrical points) and the like shall include for all short lengths, joints and couplers in the running length, and for all fixings and supports with approved saddles, crumpets, clips and the like cut and pinned, built-in or plugged and screwed to walls or ceilings including chasing brick work, block work, concrete slab beams walls columns and the like and make good.

ii. The rates for conduits and the like shall include for all bends, tees, socket and the like,cutting, screwing, threading, jointing and providing all conduit boxes, junction boxes and the like.

f. The rates for the installation of sub main circuits, lighting points switched points, socket outlets, fused spur outlets, isolators, etc. (other than those applicable to the distribution switch gear) shall include where applicable, for all conduit, trunking, cable tray, cabling, terminations, fixings and connections from the distribution
switched gear to and including the point (accessories measured separately) and shall be deemed to include for any item mentioned in the Electrical installation Specification but not shown on the drawings and vice-versa.

g. The rates for lighting fittings, fittings such as ceiling fans and extract fans, and for appliances such as air- conditioning units shall include for assembly, fixing and connection from the spur outlet or isolator to the fitting or appliance with all necessary additional wiring earthing and outlet roses and leaving perfectly clean and undamaged on completion.

h. The rates for fixing only fittings and appliances provided by the employer should include in addition to the foregoing for accepting delivery, storing and handling the fittings and providing any additional materials and internal wiring.

j. The rates for connections only to fittings and appliances such as pumps, water heaters, air conditioning units and extract fans shall include for connection from the isolator or spur outlet to the fitting or appliance (these being measured separately) , with all necessary additional wiring, earthing and outlet roses.

k. The rates for power outlets shall include for mounting boxes and frames.

l. The rates for power switched with remote outlets shall include for the additional outlet plates and boxes.

m. The rates for switched socket outlets shall include for 1 No fused plug top and 4 No fuse links.

n. The preceding preambles shall apply equally to auxiliary installations such as TV installations, telephone installations, and bell signal systems.

o. Painting of timber work and metal work.

p. If the items of electrical installation are measured as sub circuit point wiring or in electrical points, the rates for such items shall include for :

i. The preceding clauses of this trade where relevant.

ii. Preparation of asbuilt drawings to be submitted to Employer at the handing


This BSR is for Construction works only

over/ practical completion.

iii. All items and accessories required for proper installation as per specification and regulation up to load point and labour connected therewith.

iv. All wiring, conduiting and cables and labour connected therewith if not measured separately.

v. Items specified in the specification but not shown in the drawings.

vi. Disconnecting and refixing of electrical fitting and appliances as required for the convenience of other trades.

vii. Painting of timber work metal work executed under this trade.

q. Rate to include submission of Megar Test report of the building Elactrical Installation from Charted Elactrical Engineer

DOB Build Future ..... Restore Past



This BSR is for Construction works only

**Construction BSR 2020**

*for*

**Department of Buildings** ***(Metric Version)***

| Item Code | Item Description | Unit | Basic Rate 2020 |
|---|---|---|---|
| | **C - DEMOLISHER** | | |
| **C001** | Demolishing brickwork in cement stacking brick and clearing debris away | **$m^3$** | **802** |
| **C002** | Demolishing brickwork in lime stacking brick and clearing debris away | **$m^3$** | **1,068** |
| **C003** | Removing existing Ceiling, stacking materials and clearing debris away. | **$m^2$** | **104** |
| **C004** | Demolishing Cement mass concrete in floors of 150mm thick, and clearing debris away. | **$m^3$** | **4,767** |
| **C005** | Demolishing reinforced cement concrete in suspended floors of 100mm thick, removing reinforcement and clearing debris away. | **$m^2$** | **1,049** |
| **C006** | Removing and stacking corrugated sheets, G.I., asbestos or Zn/Al from roof , or walls and clearing debris away. | **$m^2$** | **113** |
| **C007** | Removing and stacking Door or Window, size upto 3.75 m2 from existing walls | **Nos** | **1,350** |
| **C008** | Removing and stacking Door or Window, size over 3.75 m2 from existing walls | **Nos** | **1,130** |
| **C009** | Removing and stacking Door or Window, sash only up to 3.75 m2 from existing walls | **Nos** | **196** |
| **C010** | Demolishing floors brick paved, 100mm thick and clearing debris away. | **$m^2$** | **121** |
| **C011** | Demolishing rubble masonry in cement, stacking rubble and clearing debris away. | **$m^3$** | **1,470** |
| **C012** | Removing and stacking tiles Calicut or half round, from roof of single storeyed buildings and clearing debris away. | **$m^2$** | **81** |
| | **Transporting debris** | | |
| **C013** | Transporting debris cleared away from site by tractor (app 16Km away). Rate to include loading & unloading. | **Load** | **4,515** |

| Item Code | Item Description | Unit | Basic Rate 2020 |
|---|---|---|---|
| | **D - EARTH WORK** | | |
| | **Site Clearing** | | |
| **D001** | Clearing site vegetation including removal of bushes, shrub under growth hedges and tree stumps upto 300mm girth measured at height upto 1.0 m above ground level ,removing rubbish upto a distance of 50m beyond the outer walls of the proposed building. | **$m^2$** | **24** |
| | **Removing Trees** | | |
| **D002** | Removing trees and stumps size of girth varies from 300mm and upto 600mm and girths are measured at 1.0 m height above ground level including cutting of trunks and branches, grubbing up roots, staking of serviceable materials and disposal of unserviceable materials.( aveg. 150mm dia. and aveg. ht 3.0m) | **Nos** | **1,522** |
| **D003** | Removing trees and stumps size of girth varies beyond 600mm and upto 1200mm and girths are measured at 1.0 m height above ground level including cutting of trunks and branches, grubbing up roots, staking of serviceable materials and disposal of unserviceable materials.(aveg. 300mm dia. and aveg. ht 4.5m) | **Nos** | **4,600** |
| **D004** | Removing trees and stumps size of girth varies beyond 1.2m and upto 2.4m and girths are measured at 1.0 m height above ground level including cutting of trunks and branches, grubbing up roots, staking of serviceable materials and disposal of unserviceable materials.( aveg. 600mm dia. and aveg. ht.7.0m) | **Nos** | **15,450** |
| **D005** | Removing trees and stumps size of girth varies beyond 2.4m and girths are measured at 1.0 m height above ground level including cutting of trunks and branches, grubbing up roots, staking of serviceable materials and disposal of unserviceable materials.( aveg. 1.0m dia. and aveg. ht.10.0m) | **Nos** | **30,900** |
| | **Removing Top Soil** | | |
| **D006** | Removing top soil to a depth not exceeding 150mm & depositing as directed within site | **$m^2$** | **162** |
| | **Excavation** | | |
| **D007** | Excavation over site to reduce level in any material except rock requiring blasting including depositing and levelling as directed upto a distance not exceeding 10.0m | **$m^3$** | **861** |
| **D008** | Excavation in trenches for walls/column pits in soft/loose soil from 0 to 1.5 m deep and depositing excavated material to a distance not exceeding 10.0m . (Earth work support to be paid separately). | **$m^3$** | **530** |
| **D009** | Excavation in trenches for walls/column pits in ordinary soil from 0 to 1.5 m deep and depositing excavated material to a distance not exceeding 10.0m . (Earth work support to be paid separately). | **$m^3$** | **1,192** |
| **D010** | Excavation in trenches for walls/column pits in hard dense soil from 0 to 1.5 m deep and depositing excavated material to a distance not exceeding 10.0m . (Earth work support to be paid separately). | **$m^3$** | **1,854** |

| Item Code | Item Description | Unit | Basic Rate 2020 |
|---|---|---|---|
| D011 | Excavation in trenches for walls/column pits in mud/wet soil from 0 to 1.5 m deep and depositing excavated material to a distance not exceeding 10.0m . (earth work support to be paid separately). | $m^3$ | 1,589 |
| D012 | Excavation in trenches for walls/column pits in soft disintegrated rock (not requiring blasting) up to a depth of 1.5 m and depositing excavated material to a distance not exceeding 10.0m . (earth work support to be paid separately). | $m^3$ | 1,324 |
| D013 | Excavation in trenches for walls/column pits in hard rock requiring blasting up to a depth of 1.5 m and depositing excavated material to a distance not exceeding 10.0m . (earth work support to be paid separately). | $m^3$ | 1,895 |
| D014 | Benching rock in foundation in 1.0m steps.(Blasting prohibited) | $m^2$ | 4,642 |
| | **Earthwork-backfilling** | | |
| D015 | Backfilling in 150mm layers & compacting pits and trenches with available earth | $m^3$ | 530 |
| D016 | Backfilling in 150mm layers & compacting pits and trenches with imported earth. | $m^3$ | 2,235 |
| D017 | Filling under floors including levelling watering and compacting in *150mm* layers with selected earth available at site | $m^3$ | 1,059 |
| D018 | Filling under floors including levelling watering and compacting in 150mm layers with imported earth. | $m^3$ | 2,765 |
| D019 | Sand filling in Column footing, wall under foundations, watered and well rammed. | $m^3$ | 6,939 |
| D020 | Supplying, spreading, levelling, watering, Graded Quarry dust (4.5mm downward) in 225mm thick layers and compaction using machine Rammer.(loose volume). Rate include hire charges of the machine rammer. | $m^3$ | 3,825 |
| | **Earth work support** | | |
| D021 | Earth work support (open planking ) in trenches upto a depth of *1.5m.* | $m^2$ | 1,104 |
| D022 | Earth work support (close planking ) in trenches upto a depth of *1.5m.* | $m^2$ | 1,662 |
| D023 | Earth work support (close planking ) in deep excavation in trenches upto *5m* depth. | $m^2$ | 1,854 |
| | **Anti-termite Treatment** | | |
| D024 | Anti-termite treatment for the new construction with applying Biflex 10Tc or approved equivalent as per manufacturer's specification including horizontal & vertical barriers with 10 years warranty on application. | $m^2$ | 291 |

| Item Code | Item Description | Unit | Basic Rate 2020 |
|---|---|---|---|
| | **F - CONCRETE** | | |
| | **(Reinforcement and shuttering paid for separately)** | | |
| | **Mixing Concrete *(Excluding Placing)(In-Situ Concrete)*** | | |
| **F001** | Mixing concrete 1:3:6 (40mm) using mixer | **$m^3$** | **11,622** |
| **F002** | Mixing concrete 1:2½:5 (25mm) using mixer | **$m^3$** | **12,561** |
| **F003** | Mixing concrete 1:2:4 (20mm) using mixer | **$m^3$** | **13,579** |
| **F004** | Mixing concrete 1: 1½ :3 (20mm) using mixer | **$m^3$** | **14,760** |
| **F005** | Mixing concrete 1: 1: 2 (20mm) using mixer | **$m^3$** | **18,056** |
| | **Mass Concrete ( Including Placing)** | | |
| | **Site Mixed Concrete 1:3:6 (40mm) -(Gr.15 Mix)** | | |
| | ***In Foundation*** | | |
| **F006** | 50mm thick cement concrete 1:3:6(40mm) screed in foundation at depths Not exceeding 1.5 m. | **$m^2$** | **697** |
| **F007** | 50mm thick cement concrete 1:3:6(40mm) screed in foundation at depths Exceeding 1.5 m & upto 3.0m | **$m^2$** | **724** |
| **F008** | 75mm thick cement concrete 1:3:6(40mm) screed in foundation at depths Not exceeding 1.5 m. | **$m^2$** | **1,032** |
| **F009** | 75mm thick cement concrete 1:3:6(40mm) screed in foundation at depths Exceeding 1.5 m & upto 3.0m | **$m^2$** | **1,073** |
| | **Site Mixed Concrete 1:2:4 (20mm)-(Gr.20 Mix)** | | |
| | ***In Foundations*** | | |
| **F010** | 75mm thick cement concrete 1:2:4 (20mm) in foundation at depths Not exceeding 1.5 m. | **$m^2$** | **1,181** |
| **F011** | 75mm thick cement concrete 1:2:4 (20mm) in foundation at depths Exceeding 1.5 m & upto 3.0m | **$m^2$** | **1,222** |
| **F012** | 150mm thick cement concrete 1:2:4 (20mm) floor (mass concrete) | **$m^2$** | **2,503** |
| | **Reinforced Concrete ( Including Placing)** | | |
| | **Site Mixed Concrete 1:2:4(20mm)-Grade 'C - 20'** | | |
| | ***In Column shafts/Walls- upto 1st floor level*** | | |
| **F013** | Cement concrete with 1:2:4 (20mm), in 113mmx150mm column in ground floor. | **m** | **420** |
| **F014** | Cement concrete with 1:2:4 (20mm), & 150mmx150mm Columns in ground floor | **m** | **545** |
| **F015** | Cement concrete with 1:2:4 (20mm) ,& 225mmx225mm Columns in ground floor | **m** | **1,195** |
| **F016** | Cement concrete 1:2:4(20mm) & 300mmx300mm Column shafts in ground floor, using mixer and vibrator. | **m** | **2,043** |
| **F017** | Cement concrete with 1:2:4(20mm), in 350mmx350mm column in ground floor | **m** | **2,553** |
| **F018** | Cement concrete with 1:2:4 (20mm),225mmx150mm beam upto 1st floor level | **m** | **819** |
| **F019** | Cement concrete with 1:2:4 (20mm),225mmx225mm beam upto 1st floor level | **m** | **1,261** |

| Item Code | Item Description | Unit | Basic Rate 2020 |
|---|---|---|---|
| F020 | Cement concrete with 1:2:4 (20mm),225mmx300mm beam upto 1st floor level | m | 1,785 |
| | ***In Floor Slabs*** | | |
| F021 | 125mm thick R.C.C. floor slab with 1:2:4 (20mm), in 1st floor, rate inclusive of placing vibrating and curing. | $m^2$ | 2,413 |
| F022 | 150mm thick R.C.C. floor slab with 1:2:4 (20mm) ,in 1st floor, rate inclusive of placing vibrating and curing. | $m^2$ | 2,881 |
| | ***In Lintols*** | | |
| F023 | Cement concrete with 1:2:4 (20mm), in 113mmx150mm lintols in ground floor | m | 434 |
| F024 | Cement concrete with 1:2:4 (20mm), in 225mmx225mm lintols in ground floor | m | 1,254 |
| F025 | Cement concrete with 1:2:4 (20mm), in 225mmx300mm lintols in ground floor | m | 1,664 |
| F026 | Cement concrete with 1:2:4 (20mm), in 300mmx375mm, lintols in ground floor | m | 2,738 |
| | **Site Mixed Concrete 1:1½:3(20mm)-Grade 'C - 25'** | | |
| | ***In Floors*** | | |
| F027 | 150 mm thick cement concrete 1: 1½ :3 (20mm)Ground floor (mass concrete), rate inclusive of placing. | $m^2$ | 2,683 |
| F028 | 125mm thick R.C.C. floor slab with 1:1½ :3 (20mm) ,in 1st floor, rate inclusive of placing and curing. | $m^2$ | 2,563 |
| F029 | 150mm thick R.C.C. floor slab with 1:1½:3 (20mm), in 1st floor, rate inclusive of placing and curing. | $m^2$ | 3,061 |
| | ***In Column shafts*** | | |
| F030 | Cement concrete with 1: 1½ :3 (20mm),in 150mmx150mm columns in ground floor. | m | 574 |
| F031 | Cement concrete with 1: 1½ :3 (20mm), in 225mmx225mm column in ground floor 1: 1½ :3 (20mm) | m | 1,256 |
| F032 | Cement concrete with 1: 1½ :3 (20mm), in 300mmx300mm column in ground floor | m | 2,153 |
| F033 | Cement concrete with 1: 1½ :3 (20mm), in 350mmx350mm column in ground floor | m | 2,693 |
| | ***In Beams*** | | |
| F034 | Cement concrete with 1: 1½ :3 (20mm) ,150mmx150mm beam upto 1st floor level. | m | 568 |
| F035 | Cement concrete with 1:1½:3 (20mm),225mmx150mm beam upto 1st floor level. | m | 861 |
| F036 | Cement concrete with 1:1½:3 (20mm),225mmx225mm beam upto 1st floor level | m | 1,323 |
| F037 | Cement concrete with 1:1½:3 (20mm),225mmx300mm beam upto 1st floor level | m | 1,867 |
| | ***In Lintols*** | | |
| F038 | Cement concrete with 1:1½:3 (20mm), in 113mmx150mm lintols in ground floor | m | 454 |
| F039 | Cement concrete with 1:1½:3 (20mm) , & 225mmx225mm lintols in ground floor | m | 1,315 |

| Item Code | Item Description | Unit | Basic Rate 2020 |
|---|---|---|---|
| F040 | Cement concrete with 1:1½:3 (20mm) , & 225mmx300mm lintols in ground floor | m | 1,747 |
| F041 | Cement concrete with 1:1½:3 (20mm) ,in 300mmx 375mm lintols in ground floor | m | 2,875 |
| | **Ready mixed Concrete** | | |
| F042 | Supplying and laying Ready Mixed concrete Grade 20 (First floor slab).. | $m^3$ | 18,965 |
| F043 | Supplying and laying Ready Mixed concrete Grade 25 (First floor slab). | $m^3$ | 19,280 |
| F044 | Hiring charges for concrete pump Truck ( Up to 30m3) | Item | 25,093 |
| F045 | Hiring charges for concrete pump Truck ( For every 1m3 above 30m3) | $m^3$ | 756 |
| | **Timber Formwork** | | |
| | **Form work (For Column in ground floor)** | | |
| F046 | Sawn timber formwork to 225mmx225mm cement concrete column in ground floor including making mould, assembling ,dismantling ,cleaning and repairing after use. | $m^2$ | 2,073 |
| | **Form work (Untreated Non-structural Category A)** | | |
| F047 | Shuttering for floor slab concrete including 100mmx50mm (untreated non-structural category A) timber joists and necessary props. upto 3.6m height. (Rate to include for dismantling same when required). | $m^2$ | 1,825 |
| F048 | Shuttering for column shaft 225mm x 225mm including (untreated non-structural category A) timber joists and necessary props etc. (Rate to include for dismantling same when required) | $m^2$ | 2,257 |
| F049 | Shuttering for beam sides & soffit in (untreated non-structural category A) timber, joists and necessary props etc. (Rate to include for dismantling same when required) | $m^2$ | 1,502 |
| | **20mm thick plywood form work** | | |
| F050 | 20mm thick plywood form work for concrete beams in ground floor consider 225 mmx 300 mm beam to 6 m, long contact area 5 m2. | $m^2$ | 2,681 |
| F051 | Supplying and fixing 20mm thick plywood form work in column ground floor consider area 1.4 m2. ( 1.5 m high 225 mmx 225 mm column. ) | $m^2$ | 2,180 |
| F052 | Supplying and fixing 20mm thick plywood timber formwork for underside of fist floor slab. consider 6m x 3m area - 18 m2. | $m^2$ | 2,392 |
| | **Sawn timber formwork** | | |
| F053 | Sawn timber formwork for concrete beam in ground floor including timber joist and necessary props (Rate to include for dismanteling same when required). | $m^2$ | 1,414 |
| F054 | Sawn timber formwork for underside of first floor slab including timber joist and necessary props (Rate to include for dismanteling same when required). | $m^2$ | 1,625 |

| Item Code | Item Description | Unit | Basic Rate 2020 |
|---|---|---|---|
| | **Reinforcement** | | |
| **F055** | Tor steel reinforcement to slabs, beams, columns or lintols bent to shape laid in position and tied with G I wire as directed | **Mt** | **249,988** |
| **F056** | Tor steel rods in foundation bending to shape, laying in position and tying with G.I wire as directed. | **Mt** | **220,511** |
| **F057** | Mild steel reinforcement to slabs, beams, columns or lintols bent to shape laid in position and tied with G I wire as directed | **Mt** | **260,638** |

| Item Code | Item Description | Unit | Basic Rate 2020 |
|---|---|---|---|
| | **G-MASONRY WORK** | | |
| | **Brick Work *and* Block Work** | | |
| | **Brick Work** | | |
| **G001** | Brick work in cement sand 1:5 in foundation upto D P C | **$m^3$** | **15,814** |
| **G002** | Brick work in cement sand 1:8 in foundation upto D P C | **$m^3$** | **15,672** |
| **G003** | Brick work in cement sand 1:5 in *112.5mm* (4½") thick walls in ground floor | **$m^2$** | **1,979** |
| **G004** | 225mm (9") thick brick wall cement sand 1:5 in superstructure/ walls in ground floor | **$m^2$** | **3,700** |
| **G005** | Brick work 350mm (13½") thick in cement sand 1:5 in superstructure in ground floor | **$m^2$** | **5,542** |
| **G006** | 225mm (9") thick brick wall cement sand 1:8 in superstructure/walls in in ground floor | **$m^2$** | **3,628** |
| **G007** | 112.5mm (4½") thick brick wall (wire cut) in cement sand 1:5 in ground floor | **$m^2$** | **2,790** |
| **G008** | 225mm (9") thick in cement and sand 1:5 with wire cut brick | **$m^2$** | **5,244** |
| **G009** | Extra over for facing including raised pointing 3mm thick in cement sand 1:1 mixture in ground floor | **$m^2$** | **1,665** |
| **G010** | 75mm thick floor paved in lime mortar 2:5 in ground floor | **$m^2$** | **1,666** |
| **G011** | 75mm thick floor paved in cement mortar 1:8 in ground floor | **$m^2$** | **1,602** |
| **G012** | Steps 338mm x150mm in brick in cement and sand 1:5 with 16mm thick cement and sand 1:2 rendering including necessary excavation | **m** | **1,653** |
| | **Hollow block masonry** | | |
| **G013** | 100mm thick Hollow block masonry in cement and sand mortar 1:5 with cavities unfilled in ground floor.3.0mx3.0m area ( size of each block 400mmx200mmx100mm) (Min com/st 3.0 N/mm2 ) | **$m^2$** | **1,462** |
| **G014** | 150mm thick hollow block work in cement and sand mortar 1:5 with cavities unfilled in ground floor.3.0mx3.0m area ( size of each block 400mmx200mmx150mm) (Min com/st 3.0 N/mm2 ) | **$m^2$** | **1,854** |
| **G015** | 200mm thick Hollow block masonry in cement and sand mortar 1:5 with cavities unfilled in ground floor. 3.0mx3.0m area ( size of each block 400mmx200mmx200mm) (Min com/st 3.0 N/mm2 ) | **$m^2$** | **2,437** |
| | **Solid block masonry** | | |
| **G016** | 100mm thick solid block masonry in cement and sand mortar 1:5 in ground floor. 3.0mx3.0m area ( size of each block 400mmx200mmx100mm) (Min com/st 3.0 N/mm2 ) | **$m^2$** | **1,679** |
| **G017** | 150mm thick solid block masonry in cement and sand mortar 1:5 in ground floor.3.0mx3.0m area ( size of each block 400mmx200mmx150mm) (Min com/st 3.0 N/mm2 ) | **$m^2$** | **2,262** |
| **G018** | 200mm thick solid block masonry in cement and sand mortar 1:5 in ground floor. 3.0mx3.0m area ( size of each block 400mmx200mmx200mm) (Min com/st 3.0 N/mm2 ) | **$m^2$** | **2,870** |

| Item Code | Item Description | Unit | Basic Rate 2020 |
|---|---|---|---|
| | **Stone Work** | | |
| **G019** | Random rubble (150mm-250mm) masonry in cement mortar 1:5 in foundation | **$m^3$** | **11,652** |
| **G020** | Random rubble (150mm-250mm) masonry in cement mortar 1:5 in superstructure | **$m^3$** | **12,535** |
| | **Paste rubble** | | |
| **G021** | Supplying & Laying pointed (50mm-75mm thick ) or Paste rubble masonry in cement and sand 1:2 in ground Floor.(Including hire chargers of Grinder) | **$m^2$** | **7,651** |

| Item Code | Item Description | Unit | Basic Rate 2020 |
|---|---|---|---|
| | **H-WATER PROOFING** | | |
| **H001** | *20mm* thick DPC in cement sand 1:2 finished with 2 coats hot tar and blinded with sand | **$m^2$** | **1,177** |
| **H002** | Concrete waterproofing treatment by using Crystallization technology according to Manufacturers specification's. (***"Xypex"*** or equivalent approved product including preparation of surface) | **$m^2$** | **2,156** |
| **H003** | Waterproofing treatment using cement based, micro-porous (breathing), coating according to Manufacturers Specifications. (***"Thoroseal"*** or equivalent approved product including preparation of surface), | **$m^2$** | **1,616** |
| **H004** | Waterproofing treatment by using flexible polymer cement slurry according to Manufacturers specification's. (***"Masterseal 540"(Barralastic)*** or equivalent approved product including preparation of surface) | **$m^2$** | **1,023** |
| **H005** | Waterproofing and crack isolation membrane type treatment to slab (area less than $300m^{2)}$ according to Manufacturers specification's. (***"Mapelastic"*** or equivalent approved product including preparation of surface) | **$m^2$** | **1,776** |
| **H006** | Waterproofing treatment to external walls by using acrylic elastomeric high flexible bituminous coating according to Manufacturers specification's. (***"Synroof"*** or equivalent approved product including preparation of surface) | **$m^2$** | **1,001** |
| **H007** | Supply & Laying Gauge 750 Polythene damp proof membrane with 150mm laps laid under floors. | **$m^2$** | **132** |

| Item Code | Item Description | Unit | Basic Rate 2020 |
|---|---|---|---|
| | **J-STRUCTURAL METAL WORKS** | | |
| | **"C" channel** | | |
| **J001** | Supplying & Fixing of a structural steel channel purlin 127mm x 64mm (14.9 Kg/m) fixed as a purlin on roof trusses / roof beams with necessary bolts/cleat connecting arrangement (Cleats and Bolts Paid separately). Rate shall include for applying two coats of enamel paint ( C.I.C. or equivalent ) after treating with a coat of anticorrosive paint to all exposed faces of purlin. | **m** | **1,143** |
| | **Wire mesh** | | |
| **J002** | Wire netting, hexagonal mesh 12mm supplying and fixing (beading to be paid for separately) | **$m^2$** | **666** |
| | **Weld mesh** | | |
| **J003** | 50mmx50mm Weld mesh No.12, supplying and fixing to existing frames with staples (fillets and beadings to be paid for separately) | **$m^2$** | **1,380** |
| **J004** | 50mm x 50mm Weld mesh No.10 supplying and fixing to window frames with 50mm x 12mm (Group 2) timber beadings, and painting weld mesh with 2 coats anti-corrosive paint, and beadings with primer, undercoat and 2 coats enamel paint to approved. Rate to include for making openings for bolts, casement stays etc. | **$m^2$** | **4,341** |
| **J005** | 50mmx50mm Weld mesh No.12 supplying and fixing to window frames with 50mm x 12mm (Group 2) timber beading, and painting weld mesh with 2 coats anti-corrosive paint, and beadings with primer, undercoat and 2 coats enamel paint to approved tint Rate to include for making openings for bolts, casement stays etc. | **$m^2$** | **3,886** |
| | **Web Truss - (Angle between $15^0$ - $45^0$)** | | |
| **J006** | Fabricating & Fixing Steel web Truss , Span less than 8m consist of 38mmx38mmx6mm top chord and bottom chord with 16mm mild steel bracings. Including all , gusset plates , cleats , rivets , nuts, washers, rag bolts, separators etc.. (Rate shall include for painting of two coats of anticorrosive paint & one coat of enamel paint.) (Hoisting charges paid separately) | **Kg** | **360** |



This BSR is for construction works only

| Item Code | Item Description | Unit | Basic Rate 2020 |
|---|---|---|---|
| | **K-METAL WORK** | | |
| | **Aluminium** | | |
| | **** Aluminium window **** | | |
| | **70mm (1.2mm thick) Aluminium Casement Double Sash Window** | | |
| | Supplying, Fabricating & Installing of 1.2mm thick 70mm deep double sashed Aluminium Casement window frame and 1.2mm thick 40mm X 35mm (depth) window sashes . Rate to include for 5mm thick glass pans, EPDM rubber beadings, weather strips, casement locks, Hinges, rawl plugs, fasteners & etc. (Alumex extrusion Nos. CA-2005, CA 1011 & CA 1012 or equivalent) | | |
| **K001** | -DO- Matt Finished Aluminium | **$m^2$** | **15,142** |
| **K002** | -DO- Natural Anodized Aluminium | **$m^2$** | **16,046** |
| **K003** | -DO- Bronzed Anodized Aluminium | **$m^2$** | **16,179** |
| **K004** | -DO-Powder Coated Aluminium | **$m^2$** | **17,316** |
| **K005** | -DO-Wood Finished Aluminium | **$m^2$** | **21,295** |
| | **70mm (1.2mm thick) Aluminium Casement Double Sash Window with Top Fixed Panel** | | |
| | Supplying, Fabricating & Installing of 1.2mm thick 70mm deep double sashed Aluminium Casement window frame and 1.2mm thick 40mm X 35mm (depth) window sashes with fixed glass panels on top. Rate to include for 5mm thick glass pans, EPDM rubber beadings, weather strips, casement locks, Hinges, rawl plugs, fasteners & etc. (Alumex extrusion Nos. CA-2005, CA 1011 & CA 1012 or equivalent) | | |
| **K006** | -DO- Matt Finished Aluminium | **$m^2$** | **13,801** |
| **K007** | -DO- Natural Anodized Aluminium | **$m^2$** | **14,626** |
| **K008** | -DO- Bronzed Anodized Aluminium | **$m^2$** | **17,290** |
| **K009** | -DO-Powder Coated Aluminium | **$m^2$** | **15,777** |
| **K010** | -DO-Wood Finished Aluminium | **$m^2$** | **19,655** |
| | **1.3mm thick 70mm Double Sashed Aluminium Sliding window** | | |
| | Supplying, Fabricating & Fixing Aluminium window with 1.3mm thick ,70mm depth Aluminium framed (max. width 32.0mm) Double sash(max. width 36.2mm)Sliding Window including 5mm clear glass pans, necessary/ EPDM rubber beadings, sliding lock etc. (Alumex extrusion No. 70S-1001, 70S-1201-1, 70S-1101-1, 70S-1401, 70S-1501, 70S-1601, 70S-1701 & etc. or equivalent) | | |
| **K011** | -DO- Matt Finished Aluminium | **$m^2$** | **7,807** |
| **K012** | -DO- Natural Anodized Aluminium | **$m^2$** | **8,167** |
| **K013** | -DO- Bronzed Anodized Aluminium | **$m^2$** | **8,262** |
| **K014** | -DO-Powder Coated Aluminium | **$m^2$** | **8,684** |
| **K015** | -DO-Wood Finished Aluminium | **$m^2$** | **10,243** |

| Item Code | Item Description | Unit | Basic Rate 2020 |
|---|---|---|---|
| | **1.3mm thick 70mm Double Sashed Aluminium Sliding window with 2 Fixed Panels at Top or Bottom** | | |
| | Supplying, Fabricating & Fixing Aluminium Window with 1.3mm thick ,70mm depth Aluminium Framed (max. width 61.0mm) Double sash (max. width 56.2mm) Sliding Window with Two fixed panels on top or bottom including 5mm clear glass pans, necessary/EPDM beadings, sliding lock etc.(Alumex extrusion No. 70S-1012, 70S-1201-1, 70S-1101-1, 70S-1401, 70S-1501, 70S-1601, 70S-1701 & etc. or equivalent) | | |
| **K016** | -DO- Matt Finished Aluminium | **$m^2$** | **8,435** |
| **K017** | -DO- Natural Anodized Aluminium | **$m^2$** | **8,818** |
| **K018** | -DO- Bronzed Anodized Aluminium | **$m^2$** | **8,917** |
| **K019** | -DO-Powder Coated Aluminium | **$m^2$** | **9,807** |
| **K020** | -DO-Wood Finished Aluminium | **$m^2$** | **10,968** |
| | **1.3mm thick 70mm 4 Sashed Aluminium Sliding window with 4 Sliding Panels at Top or Bottom** | | |
| | Supplying, Fabricating & Fixing Aluminium Window with 1.3mm thick ,70mm depth Aluminium Framed (max. width 60.0mm) Four Sliding Sashes(max. width 30.0mm) with Four Sliding panels on Top or Bottom including 5mm thick clear glass pans, necessary/EPDM beadings, sliding locks etc.(Alumex extrusion No. 70S-1201-1, 70S-1001-1, 70S-1006, 70S-1914, 70S-1401, 70S-1501, 70S-1601, 70S-1701 & etc. or equivalent) | | |
| **K021** | -DO- Matt Finished Aluminium | **$m^2$** | **8,295** |
| **K022** | -DO- Natural Anodized Aluminium | **$m^2$** | **8,690** |
| **K023** | -DO- Bronzed Anodized Aluminium | **$m^2$** | **8,790** |
| **K024** | -DO-Powder Coated Aluminium | **$m^2$** | **9,257** |
| **K025** | -DO-Wood Finished Aluminium | **$m^2$** | **10,769** |
| | **1.5mm thick 80mm 6 Sashed Aluminium Sliding window** | | |
| | Supplying, Fabricating & Fixing Aluminium Window with 1.5mm thick ,80mm depth Aluminium Framed (max. width 37.6mm) Six Sashes Sliding Window(max. width 63.0mm) including 5mm clear glass pans, necessary/EPDM beadings, sliding lock etc. (Alumex extrusion No. 80S-2001, 80SFL-1001, 80S-2201, 80S-2301, 80S-2101, 80S-2501, 80S-2601, 80S-2701, 80S-2101 & etc. or equivalent) | | |
| **K026** | -DO- Matt Finished Aluminium | **$m^2$** | **10,737** |
| **K027** | -DO- Natural Anodized Aluminium | **$m^2$** | **11,422** |
| **K028** | -DO- Bronzed Anodized Aluminium | **$m^2$** | **11,550** |
| **K029** | -DO-Powder Coated Aluminium | **$m^2$** | **12,395** |
| **K030** | -DO-Wood Finished Aluminium | **$m^2$** | **14,763** |



This BSR is for construction works only

| Item Code | Item Description | Unit | Basic Rate 2020 |
|---|---|---|---|
| | **Fixed glass Windows** | | |
| | **70mm (1.2mm thick) Aluminium Fixed Glass Window** | | |
| | Supplying, Fabricating & Installing of 1.2mm thick 70mm deep Aluminium fixed glass window with 5mm thick clear glass pan. Rate to include for rubber/EPDM beadings, rawl plugs, fasteners etc. (Alumex extrusion Nos. CA 1011 & CA 1012 or equivalent) | | |
| **K031** | -DO- Matt Finished Aluminium | **$m^2$** | **7,865** |
| **K032** | -DO- Natural Anodized Aluminium | **$m^2$** | **8,199** |
| **K033** | -DO- Bronzed Anodized Aluminium | **$m^2$** | **8,242** |
| **K034** | -DO-Powder Coated Aluminium | **$m^2$** | **8,942** |
| **K035** | -DO-Wood Finished Aluminium | **$m^2$** | **11,792** |
| | **Aluminium doors** | | |
| | **1.6mm thick Aluminium 100mm double door** | | |
| | Supplying, Fabricating and Installing of Aluminium Double sashed 100mm door with 5mm thick glass pans. Rate inclusive of necessary fasteners suitable wool felt and hinges (Union or equivalent 102x76x2 mm) etc.(Door closers, door locks and door handles paid separately) | | |
| **K036** | -DO- Matt Finished Aluminium | **$m^2$** | **14,580** |
| **K037** | -DO- Natural Anodized Aluminium | **$m^2$** | **15,457** |
| **K038** | -DO- Bronzed Anodized Aluminium | **$m^2$** | **15,649** |
| **K039** | -DO-Powder Coated Aluminium | **$m^2$** | **16,855** |
| **K040** | -DO-Wood Finished Aluminium | **$m^2$** | **20,743** |
| | **1.6mm thick Aluminium 100mm single door** | | |
| | Supplying, Fabricating and Installing of Aluminium Single sashed 100mm door with 5mm thick glass pans. Rate inclusive of necessary fasteners, wool felt and hinges (Union or equivalent 102x76x2 mm) etc.(Door closers, door locks and door handles paid separately) | | |
| **K041** | -DO- Matt Finished Aluminium | **$m^2$** | **17,757** |
| **K042** | -DO- Natural Anodized Aluminium | **$m^2$** | **19,074** |
| **K043** | -DO- Bronzed Anodized Aluminium | **$m^2$** | **19,323** |
| **K044** | -DO-Powder Coated Aluminium | **$m^2$** | **20,952** |
| **K045** | -DO-Wood Finished Aluminium | **$m^2$** | **26,098** |
| | **Aluminium Sliding Door** | | |
| | **80mm (1.5 mm thick) Aluminium Sliding Door** | | |
| | Supplying, Fabricating and Installing 1.5mm thick 33.7mmX80mm (depth) Aluminium framed two sliding door sashes with 5mm thick glass pans, suitable/EPDM rubber beadings, necessary fastners, rollers & etc.(door locks and door handles paid separately) (Alumex extrusion Nos. 80S-2001, 80S-2002, 80S2101 and etc. or equivalent) | | |
| **K046** | -DO- Matt Finished Aluminium | **$m^2$** | **10,800** |
| **K047** | -DO- Natural Anodized Aluminium | **$m^2$** | **11,495** |
| **K048** | -DO- Bronzed Anodized Aluminium | **$m^2$** | **11,627** |

| Item Code | Item Description | Unit | Basic Rate 2020 |
|---|---|---|---|
| K049 | -DO-Powder Coated Aluminium | $m^2$ | 12,484 |
| K050 | -DO-Wood Finished Aluminium | $m^2$ | 15,356 |
| | **100mm (1.5 mm thick) Aluminium Sliding Door** | | |
| | Supplying, Fabricating and Installing 1.5mm thick 30mmX98mm (depth) Aluminium framed one half fixed & Single Sliding Door sash with 5mm thick glass, suitable/EPDM rubber beadings, necessary fastners, rollers & etc. (Door closers, door locks and door handles paid separately) (Alumex extrusion Nos. SD-1001, DS-1101, SD1501 and etc. or equivalent) | | |
| K051 | -DO- Matt Finished Aluminium | $m^2$ | 11,037 |
| K052 | -DO- Natural Anodized Aluminium | $m^2$ | 11,763 |
| K053 | -DO- Bronzed Anodized Aluminium | $m^2$ | 11,911 |
| K054 | -DO-Powder Coated Aluminium | $m^2$ | 13,974 |
| K055 | -DO-Wood Finished Aluminium | $m^2$ | 15,359 |
| | **100mm (1.5 mm thick) Aluminium Sliding Door with top fixed panel** | | |
| | Supplying, Fabricating and Installing 1.5mm thick 30mmX98mm (depth) Aluminium framed one half fixed & Single Sliding Door sash with top fixed panels. Rate to include for 5mm glass pans, suitable/EPDM rubber beadings, necessary fastners, rollers & etc.(Door closers, door locks and door handles paid separately) (Alumex extrusion Nos. SD-1001, DS-1101, SD1501 and etc. or equivalent) | | |
| K056 | -DO- Matt Finished Aluminium | $m^2$ | 12,325 |
| K057 | -DO- Natural Anodized Aluminium | $m^2$ | 12,538 |
| K058 | -DO- Bronzed Anodized Aluminium | $m^2$ | 12,570 |
| K059 | -DO-Powder Coated Aluminium | $m^2$ | 13,701 |
| K060 | -DO-Wood Finished Aluminium | $m^2$ | 16,714 |
| | **100mm (1.6 mm thick) Aluminium 3 track Sliding Door** | | |
| | Supplying, Fabricating and Installing 1.5mm thick 30mmX98mm (depth) Aluminium framed one half fixed & Single Sliding Door sash with top fixed panels. Rate to include for 5mm glass pans, suitable rubber beadings, necessary fastners, rollers & etc.(Door closers, door locks and door handles paid separately) (Alumex extrusion Nos. SD-1001, DS-1101, SD1501 and etc. or equivalent) | | |
| K061 | -DO- Matt Finished Aluminium | $m^2$ | 11,108 |
| K062 | -DO- Natural Anodized Aluminium | $m^2$ | 11,400 |
| K063 | -DO- Bronzed Anodized Aluminium | $m^2$ | 11,735 |
| K064 | -DO-Powder Coated Aluminium | $m^2$ | 12,698 |
| K065 | -DO-Wood Finished Aluminium | $m^2$ | 14,541 |

| Item Code | Item Description | Unit | Basic Rate 2020 |
|---|---|---|---|
| | **Zn/Alu Roller door** | | |
| **K066** | Supplying and fixing of a Zn/Alu Roller door, having a maximum clear width of 6.0m and consisting of 0.6mm thick Zn/Al covering sheet, center bar pulleys, side plates with necessary racers, fabricating mechanical winding box with m.s square tube and covering the box with metallic sheets, fixing on site with bottom bars and G.I, u-channels for vertical guides at two vertical edges, which are painted with two coats of anticorrosive paint and two coats of enamel paint to match the colour of door sheeting, and sound reduction rubber beading embedded in the guide bars. Pulling rod and chain to be provided for manual rolling operation. (Additional length of 225mm to two sides horizontally and 450mm to upper end inside the mechanical box as initial winding vertically to be added to the clear opening area). | **$m^2$** | **6,910** |
| | **Roller door motor** | | |
| **K067** | Suppling roller shutter door moter, 0.5Hp, 300w, 2.5A sing-phase, 1780 rpm and 54:1 gear ratio, with two remote controllers for auto operation. | **Nos** | **32,025** |



This BSR is for construction works only

| Item Code | Item Description | Unit | Basic Rate 2020 |
|---|---|---|---|
| | **L-WOOD WORK** | | |
| | ***L1-Carpentry*** | | |
| **L001** | Prepare and apply two coat of Wood preservative (clear type) to structural timber including touching up out ends etc. after fixing | **$m^2$** | **210** |
| | **Timber treatment** | | |
| **L002** | Structural Timber treated by Vacuum Pressure Impregnation Technique with approved wood preservatives such as CCB that are registered by register of pesticides, for protection against wood destroying agents such as wood bores, fungi and termites. (Execution according to the Manufacturers specifications) (By "Finlay Celurised treated " or equivalent system) | **m3** | **16,209** |
| **L003** | Reepers 50mm x25mm in (Group3, Category A) timber supplying and fixing with iron nails, upto 30m (Shifting of tiles to be paid for separately) | **m** | **196** |
| **L004** | Supply and fixing 50mm x50mm (Group3,Category A) timber Battons in roof work, with nails over 30m. | **m** | **413** |
| **L005** | Supply and fixing 100mm x50mm (Group3,Category A) timber rafters for roof work. | **m** | **879** |
| **L006** | Supply and fixing 175mm x50mm (Group3,Category A) timber ridge plate in roof work. | **m** | **1,756** |
| **L007** | Supply and fixing 100mm x75mm (Group3,Category A) timber wall plate in roof work. | **m** | **1,425** |
| **L008** | Supply and fixing 125mm x75mm (Group3,Category A) timber perlin in roof work. | **m** | **1,783** |
| **L009** | Supply and fixing 100mm x75mm (Group3,Category A) timber Struts, upto 1800mm height in roof structure, including forming necessary Timber joints at both ends.600mm Timber bearer provided at Bottom. | **m** | **2,073** |
| **L010** | Class 1 timber frame work for Calicut pattern tile hip roof in single storey building consisting of wall plate beam ridge plate rafters etc.. (Preservative treatment to be measured separately) | **$m^2$** | **3,790** |
| **L011** | Cclass 1 timber frame work for corrugated asbestos sheet roof in single storeyed building | **$m^2$** | **2,246** |
| | ***L2-Joinary*** | | |
| | **Boards, barge, valance, fascia** | | |
| **L012** | Boards, barge, valance, fascia, 200mm wide and 25mm thick in (Group 5,Category A), timber fixing complete with necessary screws new or renewing, above .028 m3 | **m** | **1,025** |
| **L013** | Boards, barge, valance, fascia, 200mm wide and 25mm thick in (Group 5,Category A), timber supplying and fixing complete with necessary screws new or renewing, upto .028 m3 | **m** | **1,066** |
| **L014** | Boards, barge, valance, fascia, 200mm wide and 25mm thick in (Group 5,Category B), timber supplying and fixing complete with necessary screws new or renewing, above .028 m3 | **m** | **586** |

| Item Code | Item Description | Unit | Basic Rate 2020 |
|---|---|---|---|
| **L015** | Boards, barge, valance, fascia, 200mm wide and 25mm thick in (Group 5,Category B), timber supplying and fixing complete with necessary screws new or renewing, upto .028 m3 | **m** | **582** |
| **L016** | 20mmx225mm high Valance board in (Group 5,Category A), timber fixed with brass screws to ends of rafters (For tile roofing) | **m** | **1,299** |
| **L017** | 20mmx225mm high barge board in (Group 5,Category A), timber fixed with brass screws at 600mm centers to sides of rafters | **m** | **1,294** |
| | **Ceiling / Partition** | | |
| **L018** | Ceiling, asbestos, flat fixing with clout headed nails to 100mm x 50mm joists and 50mm bearers of (Group 4,Category A) timber including 37.5mm x 12mm cover fillets and 62.5mm x 37.5mm coves of Halmilla timber. Rate to include 2 coats of wood preservatives to joists and bearers. Primer undercoating and two coats of emulsion paint to Asbestos sheets. | **m2** | **4,579** |
| **L019** | Flat asbestos horizontal eaves ceiling comprising 50mm x 50mm bearers in(Group 4,Category A) timber asbestos sheet supplied and fixed with beadings & cove moulding, rate to include for applying wood preservative to timber frame, two coats enamel paint for beadings, and two coats emulsion paint for asbestos ceiling. | **$m^2$** | **3,636** |
| **L020** | Ceiling or partition, Lunumidella, 12mm planning, lapping and nailing to existing frames or underside of rafters, above 9.3m2 (Fillets and beadings paid for separately) | **$m^2$** | **1,355** |
| **L021** | Ceiling or partition, Lunumidella, 12mm planning, lapping and nailing to existing frames or underside of rafters, upto 9.3 m2 (Fillets and beadings paid for separately) | **$m^2$** | **1,452** |
| **L022** | Ceiling or partition, Lunumidella, 12mm beading and rebating, nailing to underside of existing joists, rafters or frames, above one square (Fillets and beadings, paid for separately) | **$m^2$** | **1,209** |
| **L023** | Ceiling or partition, Lunumidella, 16mm beading and rebating, nailing to underside of existing joists, rafters or frames, upto one square (Fillets and beadings, paid for separately) | **$m^2$** | **1,495** |
| **L024** | Ceiling openings 600mm x 450mm approx., forming complete with 50mm x 50mm bearers. (Glass tiles or sheets paid for separately) | **Nos** | **2,536** |
| **L025** | Ceiling Lunumidella 12mm planks lapping and nailing to framework consisting of 100mm x 50mm joists and 50mm x 50mm bearers in (Group 4,Category A) timber, Rate to include for 2 coats of tar nap to joists and bearers. | **$m^2$** | **4,297** |
| **L026** | Ceiling Lunumidella 20mm thick planks lapping and nailing to framework consisting of 100mm x 50mm joists and 50mm x 50mm bearers in (Group 4,Category A) timber, Rate to include for 2 coats of tar nap to joists and bearers. | **$m^2$** | **4,521** |
| | **Beading** | | |
| **L027** | Beading, Burma Teak, 37.5mm to 50mm x 12mm plain chamfering, supplying and fixing complete with brass screws. | **m** | **451** |
| **L028** | Beading, Burma Teak, 25mm x 20mm plain chamfering, supplying and fixing complete with brass screws. | **m** | **375** |

| Item Code | Item Description | Unit | Basic Rate 2020 |
|---|---|---|---|
| **L029** | Beading, Alstonia or local timber 37.5mm to 50mm x 12mm plain chamfering, supplying and fixing complete with brass screws. | **m** | **137** |
| **L030** | Beading, Halmilla, 37.5mm to 50mm x 12mm, plain chamfering, supplying and fixing complete with brass screws. | **m** | **274** |
| **L031** | Beading or filleting in Ginisapu or local timber for glass panes supplying and fixing complete with brass springs or brass panel pins. | **m** | **137** |
| | **Cove, mouldings** | | |
| **L032** | Cove, mouldings, Alstonia or equivalent 62.5mm x 37.5mm fixing with brass screws and plugs new or renewing. | **m** | **442** |
| | **Fillets, quadrant** | | |
| **L033** | Fillets, quadrant 20mm x 20mm supplying and fixing with springs or nails, in (Group 6, Category A) timber. | **m** | **140** |
| **L034** | Fillets, quadrant 25mm x 25mm in (Group 6, Category A) timber supplying and fixing with springs or nails. | **m** | **151** |
| | **Doors or Windows** | | |
| **L035** | Doors or windows, ledging, bracing and battening with groove and tongue joints, 100mm x 75mm frames and 20mm to 22mm thick sashes in (Group 2,Category A) local timber complete with brass furniture (Rim lock, Hinges). | **$m^2$** | **17,453** |
| **L036** | Doors or windows, ledging, bracing and battening with groove and tongue joints, 100mm x 75mm frames and 20mm to 22mm thick sashes in (Group 2,Category B) local timber complete with brass furniture. | **$m^2$** | **12,050** |
| **L037** | Doors or windows, framing and battening, with 100mm x 75mm frames and 25mm to 28mm sashes in (Group 2,Category A) local timber complete with brass furniture. | **$m^2$** | **19,386** |
| **L038** | Doors or windows, framing and battening, with 100mm x 75mm frames and 25mm to 28mm sashes in (Group 2,Category B) local timber complete with brass furniture. | **$m^2$** | **14,013** |
| **L039** | Doors or windows, framing and battening, with 100mm x 75mm frames and 32mm to 37.5mm sashes in (Group 2,Category A) local timber complete with brass furniture. | **$m^2$** | **18,507** |
| **L040** | Doors or windows, framing and battening, with 100mm x 75mm frames and 32mm to 37.5 mm sashes in (Group 2,CategoryB) local timber complete with brass furniture. | **$m^2$** | **14,463** |
| **L041** | Doors or Windows, framing and battening, sash only 25mm to 28mm thick in (Group 2,Category A) timber supplying and fixing complete with available furniture. | **$m^2$** | **12,580** |
| **L042** | Doors for garages, framing and battening in (Group 2,Category A) timber with 125mm x 100mm frames and 37.5mm thick sashes supplying and fixing complete with iron pintoles and strap hinges. | **$m^2$** | **13,051** |
| **L043** | Doors or Windows, glazing and/or paneling with 100mm x 75mm frames and 28mm to 32mmsashes in (Group 2,Category A) local timber supplying and fixing complete with brass furniture. | **$m^2$** | **17,923** |

| Item Code | Item Description | Unit | Basic Rate 2020 |
|---|---|---|---|
| **L044** | Doors or Windows, glazing and/or paneling with 100mm x 75mm frames and 28mm to 32mm sashes in (Group 2,Category B) local timber supplying and fixing complete with brass furniture. | **$m^2$** | **13,270** |
| | **Door frame** | | |
| **L045** | Door frame 100mm x 75mm in (Group 2,Category A) timber supplying & fixing in position. | **m** | **2,008** |
| **L046** | Door frame 100mm x 50mm in (Group 2,Category B) timber supplying and fixing in position. | **m** | **1,026** |
| | **Plywood Door** *** Note:(Brand - MACKPY or equivalent)* | | |
| **L047** | Door,32mm thick plywood ordinary (Moisture Resistant) single sash, size 825mmx 2025mm, hung on finished size 100mmx 75mm frame in (Group 2,Category A) timber and complete with brass furnitures. .(Door Lock paid Separately) | **$m^2$** | **11,011** |
| **L048** | Door,32mm thick plywood ordinary (Moisture Resistant) single sash, size 825mmx 2025mm, hung on finished size 100mmx 75mm frame in (Group 2,Category B) timber and complete with brass furnitures. .(Door Lock paid Separately) | **$m^2$** | **9,574** |
| **L049** | Supplying and fixing plywood door 32mm thick (Moisture Resistant) single sash, size 825mmx 2025mm,hung to the existing frame including necessary brass fittings.(Door Lock paid Separately) | **$m^2$** | **5,356** |
| **L050** | Supplying & fixing 32mm thick Ply wood door, Both Side Luxury finish (Moisture Resistant) ,size 825mmx 2025mm, single sash, hung to existing frame including necessary brass fittings.(Door Lock paid Separately) | **$m^2$** | **7,313** |
| | **Door PVC** | | |
| **L051** | Door PVC supply and fixing to existing opening, (with out frame), Lock, complete with altered size with out preparing reveals. (Size 750mmx1025mm) | **$m^2$** | **5,127** |
| **L052** | Door PVC supply and fixing to existing opening, with frame, Lock, complete with altered size with out preparing reveals. (Size 750mmx1025mm) | **$m^2$** | **8,043** |
| **L053** | Supplying and fixing **PVC step nosing** to stairway step edges using approved adhesive. | **m** | **533** |
| | **Louver blades** | | |
| **L054** | Louvre blades 10mm minimum thickness in (Group 1, Category A) timber up to 100mm width supplying and fixing. | **m** | **601** |
| **L055** | Louvre blades 10mm minimum thickness in (Group 1, Category A) timber over 100mm and up to150mm. | **m** | **660** |
| **L056** | Louvre blades 10mm minimum thickness in (Group 1, Category A) timber over 150mm and up to 225mm. | **m** | **893** |

| Item Code | Item Description | Unit | Basic Rate 2020 |
|---|---|---|---|
| | **Wooden Posts** | | |
| **L057** | Posts, verandah, 125mm x 125mm tapering to 100mm x 100mm in (Group3, Category A) local timber, supplying and fixing on spur stones (spur stones paid for separately) | **m** | **3,436** |
| **L058** | Posts, verandah 150mm x 150mm tapering to 125mm x 125mm in (Group3, Category A) local timber supplying and fixing on spur stones (spur stones paid for separately) | **m** | **4,768** |
| **L059** | Posts, Wooden, round jungle timber 125mm minimum and average 150mm dia. supplying and fixing. | **m** | **309** |
| | **Skirting** | | |
| **L060** | Skirting in Teak ( 225mm x 25mm moulding and beading supplying and fixing complete to wooden frame. | **m** | **2,282** |
| **L061** | Supplying and fixing Skirting in Lunumedella board 150mm x 20mm on walls. | **m** | **1,052** |
| | **Pantry cupboards units** | | |
| **L062** | Supplying and fixing pantry cupboards top unit with (Group 2,Category A) timber 25mm thick apx.2700mmx800mmx300mm (high) outer frame and shashes.Applying two coats of woodsheen to exposed outer surface complete with handles,conceal hinges,anchor bolts etc and painting 2 coats of varnish to internal surface. | **m** | **39,808** |
| **L063** | Supplying and fixing pantry cupboards bottom unit with (Group 2,Category A) timber 25mm thick apx.2700mmx825mmx600mm (high) including Perstop laminated worktop and drawers with runners, conceal hinges and handles fixed. Applying two coats of woodsheen to exposed outer surface complete with handles,conceal hinges,anchor bolts etc and painting 2 coats of varnish to internal surface. ( Rate excluding sink, taps and other accessories) | **m** | **49,612** |
| | ***Iron Mongary - L3*** | | |
| | **Cabin Hooks (Iron)** | | |
| **L064** | Cabin Hooks and eyes, 50mm Iron, supplying and fixing. | **set** | **78** |
| **L065** | Cabin Hooks and eyes, 75mm Iron, supplying and fixing. | **set** | **79** |
| **L066** | Cabin Hooks and eyes, 150mm Iron, supplying and fixing. | **set** | **126** |
| **L067** | Cabin Hooks and eyes, 200mm Iron, supplying and fixing. | **set** | **170** |
| **L068** | Cabin Hooks and eyes, 225mm Iron, supplying and fixing. | **set** | **176** |
| | **Cabin Hooks (Brass)** | | |
| **L069** | Cabin Hooks 50mm polished, brass, heavy quality supplying and fixing with brass screws. | **Nos** | **317** |
| **L070** | Cabin Hooks 75mm polished, brass, heavy quality supplying and fixing with brass screws. | **Nos** | **338** |
| **L071** | Cabin Hooks150mm polished, brass, heavy quality supplying and fixing with brass screws. | **Nos** | **370** |
| **L072** | Cabin Hooks 200mm, polished, brass heavy Quality supplying & fixing with brass screws. | **Nos** | **406** |
| **L073** | Cabin Hooks, 225mm, polished, brass heavy quality supplying & fixing with brass screws. | **Nos** | **469** |

| Item Code | Item Description | Unit | Basic Rate 2020 |
|---|---|---|---|
| L074 | Cabin Hooks, 250mm, polished, brass heavy quality supplying & fixing with brass screws. | Nos | 590 |
| L075 | Cabin Hooks, 300mm, polished, brass heavy quality supplying & fixing with brass screws. | Nos | 606 |
| | **Casement fasteners, brass** | | |
| L076 | Casement Stays, Iron 250mm heavy quality, supplying and fixing. | Nos | 269 |
| L077 | Casement Stays, Iron 300mm heavy quality, supplying and fixing. | Nos | 290 |
| | **Casement fasteners, brass** | | |
| L078 | Casement fasteners, brass with mortice plate, polished heavy quality supplying and fixing with brass screws. | Nos | 522 |
| L079 | Casement stays, polished 250mm heavy quality supplying and fixing. | Nos | 466 |
| L080 | Casement stays, polished 300mm heavy quality supplying and fixing. | Nos | 508 |
| L081 | Fanlight Catches, brass heavy quality, supplying and fixing with brass screws complete. | Nos | 601 |
| L082 | Handles, door, brass, polished heavy quality supplying and fixing with brass screws complete. | Nos | 470 |
| | **Hasp and staple, brass** | | |
| L083 | Hasp and staple 10mm iron, safety type of approved heavy quality, supplying and fixing with iron screws. | Nos | 244 |
| L084 | Hasp and staple 150mm iron, safety type of approved heavy quality, supplying and fixing with iron screws complete. | Nos | 255 |
| L085 | Hasp and staple 300mm x 50mm iron, specially made out of 6mm iron plate and fixing with 6mm x 50mm bolts and nuts complete. | Nos | 3,019 |
| | **Hasp and staple, brass** | | |
| L086 | Hasp and staple, Safety type, 150mm brass, polished heavy quality supplying and fixing with brass screws, complete. | Nos | 527 |
| L087 | Hasp and staple, Safety type, 100mm brass, polished heavy quality supplying and fixing with brass screws, complete. | Nos | 475 |
| L088 | Hat Hooks, brass, supplying and fixing with brass screws. | Nos | 277 |
| | **Hinges (Iron)** | | |
| L089 | Hinges, butt, 50mm iron of approved heavy quality supplying and fixing with iron screws. | pairs | 542 |
| L090 | Hinges, butt, 75mm iron of approved quality supplying and fixing with iron screws. | pairs | 606 |
| L091 | Hinges, butt, 100mm iron of approved quality supplying and fixing with iron screws. | pairs | 692 |
| L092 | Hinges, butt, 125mm iron of approved quality supplying and fixing with iron screws. | pairs | 927 |
| L093 | Hinges supplied by Dept. fixing complete with screws. | pairs | 297 |
| L094 | Hinges, strap iron 37mm x 6mm, 300mm long supplying & fixing with necessary bolts and nuts (excluding pintols) | Nos | 1,442 |
| L095 | Hinges, strap iron 50mm x 6mm, 900mm long supplying and fixing with necessary bolts and nuts (excluding pintols) | Nos | 2,362 |
| L096 | Hinges, spring, Japanese Helical, door supplying and fixing with iron screws complete. | Nos | 1,256 |

| Item Code | Item Description | Unit | Basic Rate 2020 |
|---|---|---|---|
| | **Hinges, brass** | | |
| **L097** | Hinges, butt, 50mm brass, polished heavy quality supplying and fixing with brass screws complete. | **pairs** | **581** |
| **L098** | Hinges, butt, 75mm brass polished heavy quality supplying and fixing with brass screws complete. | **pairs** | **719** |
| **L099** | Hinges, butt, 87.5mm brass polished heavy quality supplying and fixing with brass screws complete. | **pairs** | **1,121** |
| **L100** | Hinges, butt, 100mm brass polished heavy quality supplying and fixing with brass screws complete. | **pairs** | **1,205** |
| **L101** | Hinges, butt, 125mm brass polished heavy quality supplying and fixing with brass screws complete. | **pairs** | **1,305** |
| **L102** | Hinges center pivoted (consisting of 2 pieces) brass, polished heavy quality supplying and fixing with brass screws complete. | **pairs** | **846** |
| **L103** | Hinges, gravity, brass supplying and fixing with brass screws complete. | **pairs** | **963** |
| **L104** | Hinges, Parliamentary, 100mm brass, polished heavy quality supplying and fixing with brass screws complete. | **pairs** | **1,603** |
| **L105** | Hinges, Parliamentary, 125mm brass, polished heavy quality supplying and fixing with brass screws complete. | **Nos** | **836** |
| **L106** | Hinges, Parliamentary, 150mm brass, polished heavy quality supplying and fixing with brass screws complete. | **Nos** | **928** |
| **L107** | Hinges, spring, double acting, brass 100mm supplying and fixing. | **Nos** | **1,919** |
| | **Hinges (Stainless Steel) for Timber Doors** | | |
| **L108** | Supplying and fixing UNION- Butt Hinges, 100mmx75mmx 3mm (thick) stainless steel, for wooden doors with brass screws. | **pairs** | **3,665** |
| | **Hinges (Stainless Steel) for Aluminium Doors** | | |
| **L109** | Supplying and fixing UNION- Butt Hinges,100mmx75mmx 2mm (thick) stainless steel, for Aluminium doors with pop rivets.<br>*Prime Cost of, UNION Butt Hinges, , 4"x3"x 2mm (thick) stainless steel, for Aluminium doorsPrime Cost of, =2100* | **pairs** | **2,398** |
| | **Holdfast** | | |
| **L110** | Holdfast 3.2mm x 50mm x 225mm flat iron supplying and fixing complete. per no<br>*Prime Cost of, Flat iron 2"x⅛"Prime Cost of, =95* | **Nos** | **493** |
| **L111** | Locks, rim, 100mm iron, superior quality, heavy type supplying and fixing with iron screws complete. | **Nos** | **1,525** |
| **L112** | Locks, rim, 150mm iron, superior quality, heavy type supplying and fixing with iron screws complete. | **Nos** | **1,283** |
| **L113** | Locks, mortice, 100mm iron, superior quality, heavy type supplying and fixing with iron screws complete. | **Nos** | **1,382** |
| **L114** | Locks, mortice, 150mm iron, superior quality, heavy type supplying and fixing with iron screws complete. | **Nos** | **1,677** |
| **L115** | Locks, Bird type supplying and fixing with iron screws complete. | **Nos** | **949** |
| | **Locks (Brass)** | | |
| **L116** | Locks, cupboards, 62.5mm brass, 4 levers with brass screws supplying and fixing complete. | **Nos** | **598** |

| Item Code | Item Description | Unit | Basic Rate 2020 |
|---|---|---|---|
| **L117** | Locks, rim 150mm polished brass, 2 levers, superior quality and English make, supplying and fixing. | **Nos** | **4,165** |
| **L118** | Locks, rim 125mm single lever of best quality local manufacture, supplying and fixing. | **Nos** | **2,905** |
| **L119** | Supplying and fixing ,night latch/Rim Lock (Duplicate/Local), with duplicate keys. | **Nos** | **1,776** |
| **L120** | Supplying and fixing , Yale or Union, night latch Lock (Rim Lock), with duplicate keys. (Nos: 1022C,1027 or 1028),(Imported, British or south African make) | **Nos** | **8,518** |
| **L121** | Door rings, brass 37.5mm to 44mm supplying and fixing to doors and windows with brass screws. | **Nos** | **298** |
| **L122** | Lock Mortice (local) single supplying & fixing. | **Nos** | **4,095** |
| **L123** | Lock Mortice (local) double, supplying and fixing. | **Nos** | **6,221** |
| **L124** | Supplying and fixing two Lever single door UNION Motice Lock (No2295),(Imported, British or south African make). | **Nos** | **3,788** |
| **L125** | Supplying and fixing two Lever double door UNION Motice Lock (No2242), (Imported, British or south African make). | **Nos** | **7,437** |
| **L126** | Supplying and fixing UNION Cylindrical Motice Lock (No:X985) including Door handle pair,(Imported, British or south African make). | **Nos** | **12,455** |
| **L127** | Supplying and fixing UNION Nob set Lock (No:X96300) (Imported, British or south African make). | **Nos** | **6,132** |
| **L128** | Supplying and fixing UNION Nob set Lock for Toilets (No:X96350) (Imported, British or south African make). | **Nos** | **5,481** |
| | **Door lock for Aluminium Doors** | | |
| **L129** | Supplying and Fixing UNION Door lock (No-X 920,X925 or X930) for Aluminium Door with necessary accessories to working order.<br>*Prime Cost of, UNION Door lock (No-X 920,X925 or X930) for Aluminium DoorPrime Cost of, =4533* | **Nos** | **5,587** |
| **L130** | Supplying and Fixing Door lock(No-VR50101B) for Aluminium Door with necessary accessories to working order.<br>*Prime Cost of, Door lock-VR50101BPrime Cost of, =5618* | **Nos** | **6,101** |
| **L131** | Supplying and Fixing Door lock(No-VR50101C) for Aluminium Door with necessary accessories to working order.<br>*Prime Cost of, Door lock-VR50101cPrime Cost of, =6038* | **Nos** | **6,521** |
| | **Stainless Steel Door Handle for Aluminium Doors** | | |
| **L132** | Supplying and Fixing lock for Aluminium Sliding door with necessary accessories .<br>*Prime Cost of, Sliding door LockPrime Cost of, =772* | **Nos** | **1,087** |
| | **Stainless Steel Door Handle for Aluminium Doors** | | |
| **L133** | Supplying and Fixing Stainless Steel Door Handle for Aluminium door with necessary accessories .<br>*Prime Cost of, Stainless Steel Door handlePrime Cost of, =1628* | **Nos** | **1,943** |

| Item Code | Item Description | Unit | Basic Rate 2020 |
|---|---|---|---|
| | **Floor hinge** | | |
| **L134** | Supplying and Fixing of UNION floor hinge (No: 8300) with necessary accessories .(Imported, British or south African make)<br>*Prime Cost of, UNION floor hing (No: 8300)Prime Cost of, =26250* | **Nos** | **29,668** |
| **L135** | Supplying and fixing imported floor hinges (new star) of approved quality including chipping of existing floors and making good after completion.<br>*Prime Cost of, Floor hingePrime Cost of, =18323* | **Nos** | **20,713** |
| | **Door Closer** | | |
| **L136** | Supplying and fixing door closer Japanese make of approved heavy quality<br>*Prime Cost of, Door closer (new star)Prime Cost of, =5355* | **Nos** | **5,898** |

| Item Code | Item Description | Unit | Basic Rate 2020 |
|---|---|---|---|
| | **M-CLADDING** | | |
| **M001** | Supplying, fabricating and installing of 4.0mm thick Aluminium composite cladding panel (Alucobond or equivalent European make) with open joint tray panel system using non corrosive 50x81x3mm tk. Aluminium "T" channel section (al 217), non corrosive 50x50x3mm pressed aluminium "U" wall bracket sub frame and AL 201 & AL 202 profiles on tray panel, Rate to include for ss nut and bolts, ss screws, blind rivets, U channels, Nylon resistant, Anchor bolts, and other necessary accessories. Bird mesh to be provided in side of vent areas, all complete as per manufacture's specifications. | **$m^2$** | **12,950** |



This BSR is for construction works only

| Item Code | Item Description | Unit | Basic Rate 2020 |
|---|---|---|---|
| | **N-PARTITIONS & SUSPENDED CEILING** | | |
| | **Aluminium Partitions** | | |
| | **Aluminium Partition Frame Work (max. height 3600mm) - with Fully Fabric Board, 1.2mm thick, 76mm depth (max. width 23.0mm) extrusions** | | |
| | Supplying, Fabricating and Installing FULLY Fabric board ( both sides) ALUMINIUM PARTITION consist of 1.2mm thick, 76mm depth (max. width 23.0mm) Aluminium extrusions and GI channel stiffener frame work enclosed in Aluminium frame work with an appropriate grid pattern, span not exceeding 1200mm in both vertical & horizontal directions suited to the available space and additional GI channel bracings placed in 600mm centers at vertical direction. Rate inclusive of Aluminium beadings (including necessary rubber beadings) necessary fasteners etc. | | |
| **N001** | -DO- Matt Finished Aluminium | **$m^2$** | **6,974** |
| **N002** | -DO- Natural Anodized Aluminium | **$m^2$** | **7,066** |
| **N003** | -DO- Bronzed Anodized Aluminium | **$m^2$** | **7,092** |
| **N004** | -DO-Powder Coated Aluminium | **$m^2$** | **7,250** |
| **N005** | -DO-Wood Finished Aluminium | **$m^2$** | **7,785** |
| | **Aluminium Partition Frame Work - top & bottom with Fabric Boards & middle panel with Glass Pans (max. height 3600mm), 1.2mm thick, 76mm depth (max. width 23.0mm) extrusions** | | |
| | Supplying, Fabricating and Installing Glass & Fabric Board ALUMINIUM PARTITION frame work with 1.2mm thick, 76mm depth (max. width 23.0mm) Aluminium extrusions. And top & Bottom panels consist of 3mm thick Fabric Board (both sides) with GI channel stiffener frame work enclosed in appropriate grid pattern, span not exceeding 1200mm in both vertical & horizontal directions, suited to the available space and additional GI channel bracings placed in 600mm centers at vertical direction. Middle panel consists of 5mm thick glass pans, span not exceeding 1200mm in both directions. Rate inclusive of Aluminium beadings (including necessary rubber beadings) necessary fasteners etc. | | |
| **N006** | -DO- Matt Finished Aluminium | **$m^2$** | **6,799** |
| **N007** | -DO- Natural Anodized Aluminium | **$m^2$** | **6,924** |
| **N008** | -DO- Bronzed Anodized Aluminium | **$m^2$** | **6,958** |
| **N009** | -DO-Powder Coated Aluminium | **$m^2$** | **7,146** |
| **N010** | -DO-Wood Finished Aluminium | **$m^2$** | **7,909** |

| Item Code | Item Description | Unit | Basic Rate 2020 |
|---|---|---|---|
| | **Aluminium Partition Frame Work - top & bottom with PVC Boards & middle panel with Glass Pans (max. height 3600mm), 1.2mm thick, 76mm depth (max. width 23.0mm) extrusions** | | |
| | Supplying, Fabricating and Installing Glass & PVC Board ALUMINIUM PARTITION frame work with 1.2mm thick, 76mm depth (max. width 23.0mm) Aluminium extrusions. Top & Bottom panels consist of 3mm thick PVC Board (both sides) with GI channel stiffener frame work enclosed in appropriate grid pattern, span not exceeding 1200mm in both vertical & horizontal directions, suited to the available space and additional GI channel bracings placed in 600mm centers at vertical direction. Middle panel consists of 5mm thick glass pans, span not exceeding 1200mm in both directions. Rate inclusive of Aluminium beadings (including necessary rubber beadings) necessary fasteners etc. | | |
| **N011** | -DO- Matt Finished Aluminium | **$m^2$** | **5,498** |
| **N012** | -DO- Natural Anodized Aluminium | **$m^2$** | **5,841** |
| **N013** | -DO- Bronzed Anodized Aluminium | **$m^2$** | **5,874** |
| **N014** | -DO-Powder Coated Aluminium | **$m^2$** | **6,063** |
| **N015** | -DO-Wood Finished Aluminium | **$m^2$** | **6,825** |
| | **Aluminium Partition Frame Work (max. height 3600mm) - with Fully PVC Board, 1.2mm thick, 76mm depth (max. width 23.0mm) extrusions** | | |
| | Supplying, Fabricating and Installing 3mm thick Fully PVC board ( both sides) ALUMINIUM PARTITION consist of 1.2mm thick, 76mm depth (max. width 23.0mm) Aluminium extrusions and GI channel stiffener frame work enclosed in Aluminium frame work with an appropriate grid pattern, span not exceeding 1200mm in both vertical & horizontal directions suited to the available space and additional GI channel bracings placed in 600mm centers at vertical direction. Rate inclusive of Aluminium beadings (including necessary rubber beadings) necessary fasteners etc. | | |
| **N016** | -DO- Matt Finished Aluminium | **$m^2$** | **5,284** |
| **N017** | -DO- Natural Anodized Aluminium | **$m^2$** | **5,736** |
| **N018** | -DO- Bronzed Anodized Aluminium | **$m^2$** | **5,770** |
| **N019** | -DO-Powder Coated Aluminium | **$m^2$** | **5,958** |
| **N020** | -DO-Wood Finished Aluminium | **$m^2$** | **6,721** |



This BSR is for construction works only

| Item Code | Item Description | Unit | Basic Rate 2020 |
|---|---|---|---|
| | **Aluminium Partition Frame Work - 5 mm thick fully Glass (max. height 3600mm), 1.2mm thick, 76mm depth (max. width 23.0mm) extrusions** | | |
| | Supplying, Fabricating and Installing 5mm thick Fully Glass, ALUMINIUM PARTITION consist of 1.2mm thick, 76mm depth (max. width 23.0mm) Aluminium extrusions and GI channel stiffener frame work enclosed in Aluminium frame work with an appropriate grid pattern, span not exceeding 1200mm in both vertical & horizontal directions suited to the available space . Rate inclusive of Aluminium beadings (including necessary rubber beadings) necessary fasteners etc. | | |
| **N021** | -DO- Matt Finished Aluminium | **$m^2$** | **6,065** |
| **N022** | -DO- Natural Anodized Aluminium | **$m^2$** | **6,191** |
| **N023** | -DO- Bronzed Anodized Aluminium | **$m^2$** | **6,224** |
| **N024** | -DO-Powder Coated Aluminium | **$m^2$** | **6,413** |
| **N025** | -DO-Wood Finished Aluminium | **$m^2$** | **7,175** |
| | **Aluminium Partition Frame Work - (max. height 3600mm) Fully Louvered. 1.2mm thick, 76mm depth (max. width 23.0mm) Aluminium extrusions** | | |
| | Supplying, Fabricating and Fixing FULLY ALUMINIUM LOUVERED PARTITION with 1.2mm thick, 76mm depth (max. width 23.0mm) Aluminium extrusions to form an appropriate grid pattern, span not exceeding 1200mm in both vertical & horizontal directions, suited to the available space and all panels consist of Louvers enclosed with Aluminium louver frame. Rate inclusive of Aluminium beadings (including necessary rubber beadings) necessary fasteners etc. (Rate for DG-01 & DG-101 louver extrusions) | | |
| **N026** | -DO- Matt Finished Aluminium | **$m^2$** | **14,655** |
| **N027** | -DO- Natural Anodized Aluminium | **$m^2$** | **15,550** |
| **N028** | -DO- Bronzed Anodized Aluminium | **$m^2$** | **16,032** |
| **N029** | -DO-Powder Coated Aluminium | **$m^2$** | **17,425** |
| **N030** | -DO-Wood Finished Aluminium | **$m^2$** | **24,526** |
| | **Aluminium 76mm Shopfront** | | |
| | Supplying, Fabricating and Installing fully glass 1.2 mm thick,76mm Aluminium Shopfront, frame work fixed as an appropriate grid pattern not exceeding 1200mm in both vertical & horizontal directions, suit to the available space including 5mm thick glass pans necessary rubber beadings, fasteners etc. | | |
| **N031** | -DO- Matt Finished Aluminium | **$m^2$** | **7,062** |
| **N032** | -DO- Natural Anodized Aluminium | **$m^2$** | **7,252** |
| **N033** | -DO- Bronzed Anodized Aluminium | **$m^2$** | **7,311** |
| **N034** | -DO-Powder Coated Aluminium | **$m^2$** | **7,640** |
| **N035** | -DO-Wood Finished Aluminium | **$m^2$** | **9,004** |

| Item Code | Item Description | Unit | Basic Rate 2020 |
|---|---|---|---|
| | **Aluminium Curtain Wall (1.5mm thick)** | | |
| | Supplying, Fabricating and Fixing Aluminium Curtain Wall with 1.5mm thick,85mm depth extrusions, frame work fixed as an appropriate grid pattern, span not exceeding 1200mm in both vertical & horizontal directions, suit to the available space including 5mm thick glass pans, necessary rubber beadings, fasteners etc. | | |
| **N036** | -DO- Matt Finished Aluminium | **$m^2$** | **9,989** |
| **N037** | -DO- Natural Anodized Aluminium | **$m^2$** | **10,580** |
| **N038** | -DO- Bronzed Anodized Aluminium | **$m^2$** | **10,767** |
| **N039** | -DO-Powder Coated Aluminium | **$m^2$** | **11,345** |
| **N040** | -DO-Wood Finished Aluminium | **$m^2$** | **13,414** |
| | **Partitioning (Gypsum board)** | | |
| **N041** | Supplying and fixing gypsum board partitioning with GI channel member frame work fixed onto walls and floors , 12mm. thick gypsum board fixed to both sides of frame work complete with making joints using joint tape and gypsum compound to get wall finish . | **$m^2$** | **8,188** |
| | **Hot dip GI interlocking ceiling frame work only** | | |
| **N042** | The frame members for suspended ceiling are in a standard kit (CKM or equivalent). Main runners ( 38mmx24mmx3660mm) are fixed at 1220 centers securely suspended using 4mm dia. GI hanging rod to the structural soffit or timber roof, using an appropriate suspension at 1220mm centers, Cross Tees (27mmx24mmx1220mm) of 1220mm length to be fixed between the main runners at 610mm centers and another cross tees (27mmx24mmx610mm) fixed at mid span between 610mm to form a grid structure of 610mmx 610mm in size. wall angles (24mmx24mmx3050mm) are fixed at wall edges. ( Edge molding and painting paid separately) | **$m^2$** | **2,790** |
| | **(Mineral fiber / Stone wool) acoustic ceiling suspended ceiling** | | |
| **N043** | Supplying & fixing of 600mm x600mm & 15mm thick (Mineral fiber / Stone wool) Acoustic ceiling boards (Rockfon or equivalent-Provides sound insulation from top and sound absorption within room level) lay on hot dip GI pre engineered interlocking ceiling frame work. The frame members for suspended ceiling are in a standard kit (CKM or equivalent). Main runners ( 38mmx24mmx3660mm) are fixed at 1220 centers securely suspended using 4mm dia adjustable GI hanging rod with spring clips to the structural soffit or existing roof structure, using an appropriate suspension at 1220mm intervals along each Main runners. Cross Tees (27mmx24mmx1220mm) of 1220mm length to be fixed between the main runners at 610mm centers and another cross tees (27mmx24mmx610mm) fixed at mid span between 610mm to form a grid structure of 610mmx 610mm in size. wall angles (24mmx24mmx3050mm) are fixed at wall edges. | **$m^2$** | **3,928** |

| Item Code | Item Description | Unit | Basic Rate 2020 |
|---|---|---|---|
| **N044** | Supplying & fixing 1200mm x 600mm x 15mm thick Mineral fiber acoustic ceiling boards lay on Existing interlock type ceiling frame work , forming a panel side of 600mm X 600mm, and at the average elevation of 3600mm from the working floor, (for 12 nos or 9m2) | **$m^2$** | **1,340** |
| **N045** | Supplying and installing mineral fiber Japanese make suspended exposed ceiling system, using 1200mm x 600mm X 15 mm thick ceiling boards, lay on white colour interlock type, hot dip GI grid system , forming a panel side of 1200mm x 600mm, and suspended on 4mm rods with spring clip to soffit of concrete or timber roofs. ( Edge molding paid separately) | **$m^2$** | **4,081** |
| **N046** | Supplying and installing mineral fiber Japanese make suspended exposed ceiling (Reaveal edge) system, using 605 mm X 605 mm X 15 mm white colour ceiling boards lay on white colour interlock type hot dip GI grid system , forming a panel side of 610mmx610mm,and suspended on 4mm rods with spring clip to soffit of concrete or timber roofs. . ( Edge molding & Painting paid separately) | **$m^2$** | **4,264** |
| | **Super Flex Suspended ceiling** | | |
| **N047** | Supplying and installing Super Flex (Plain) suspended ceiling system, using 1200mm X 1200mm X 3.2 mm ceiling boards lay on white colour interlock type hot dip GI grid system , forming a panel side of 600mm X 600mm , and suspended on 4mm rods with spring clip to soffit of concrete or timber roofs. ( Edge molding & Painting paid separately) | **$m^2$** | **2,019** |
| **N048** | Supplying and installing Super Flex (with design) suspended ceiling system, using 1200mm X 1200mm X 3.2 mm ceiling boards in white colour interlock type hot dip GI grid system , forming a panel side of 600mm X 600mm, and suspended suspended on 4mm rods with spring clip to soffit of concrete or timber roofs ( Edge molding & Painting paid separately) | **$m^2$** | **2,093** |
| | **Gypsum board suspended ceiling** | | |
| **N049** | Supplying and fixing gypsum board suspended ceiling . using 600mm x 600mm X 9 mm. thick ceiling boards in white colour interlock type hot dip GI grid system , forming a panel side of 600mmx600mm, and suspended suspended on 4mm GI hanging rods with spring clip to soffit of concrete or timber roofs ( Edge molding & Painting paid separately) | **$m^2$** | **3,742** |
| | **Metal ceiling** | | |
| **N050** | Supply and installation of concealed type metal false ceiling, Including revel edge of 600mm x 600mm size 0.5mm minimum thickness, epoxy powder painted steel Tiles (paint film thickness of average 80microns ) suspended to the roof frame work with, 0.3 mm thick pre painted hot dip galvanized, 15mm x 38mm plain TEE-grid bars and 20mm x 24mm wall angles, suspended with adjustable burrerfly clip, 4mm dia. surface treated galvanized steel hanger rods, complete with necessary anchor bolts and any other accessories. (All in accordance with the approved shop drawings, to the Engineers' satisfaction. ) | **$m^2$** | **5,813** |

| Item Code | Item Description | Unit | Basic Rate 2020 |
|---|---|---|---|
| **N051** | Supply and installation of lay in type "E-Metallic Aluminum ceiling, Including revel edge of 600mmx600mm size 0.7mm average thickness, 80 microns high quality powder coated Aluminum perforated or plain ceiling panels,. Suspended to the roof frame work with hot dip galvanized "T" bars of 14mm x 38mm and wall angles of 19mm x 24mm suspended with, adjustable burrerfly clip, 04mm GI hanging roads, anchor bolts and all other accessories. (All in accordance with the approved shop drawings, to the Engineers' satisfaction. ) | **$m^2$** | **6,807** |
| | **Ceiling panels (Pinholes)** | | |
| **N052** | Supplying, fixing aluminium 600mmx600mm ceiling panels (Pinholes) with aluminium frame work and adjustable. | **$m^2$** | **4,986** |

| Item Code | Item Description | Unit | Basic Rate 2020 |
|---|---|---|---|
| | **P-ROOF COVERING AND ROOF PLUMBING** | | |
| | **Tiles, Calicut pattern, flat** | | |
| **P001** | Tiles Calicut pattern, supplying and laying in any building on existing roof frame. | **$m^2$** | **1,144** |
| | **Tiles half round** | | |
| **P002** | Tiles half round, supplied and laid in any building on existing roof frame. | **$m^2$** | **6,943** |
| **P003** | Supplying and laying half round tiles on the existing asbestos roof. | **$m^2$** | **3,681** |
| | **Zinc Aluminium Colour bonded Steel Roofing** | | |
| **P004** | Supplying and fixing Zinc Aluminium colour bonded steel roofing sheets ( 0.47 gauge )on existing frame work using nut & bolt / self tapping screws or fasteners. | **$m^2$** | **2,198** |
| **P005** | 12mm thick heat and sound installation sheet (double side luminary aluminium foil) laying on 75mm x 75mm GI mesh under roof covering. | **$m^2$** | **1,049** |
| | **Corrugated Asbestos sheets** | | |
| **P006** | Corrugated asbestos sheet roofing on category A timber purlins supplied and fixed complete including treating timber with wood preservative (Ridging measured separately). | **$m^2$** | **3,252** |
| **P007** | Corrugated asbestos sheets supplied and fixed to roof or wall on existing framework with necessary coach screws and limpet washers or hook bolts. | **$m^2$** | **1,251** |
| | **Ridging** | | |
| **P008** | Ridging, Calicut pattern, bedded in cement and lime mortar 1:1:4, coloured to match tiles. | **m** | **692** |
| **P009** | Ridging, **half round** tiles, bedded in lime, cement mortar 1:1:4 and coloured to match tiles. | **m** | **1,001** |
| **P010** | Ridging, **Galvanized iron** 24 B.W.G 18" wide overall supplied and fixed complete. | **m** | **736** |
| **P011** | Supplying and fixing Zinc Aluminium colour bonded standard steel ridge cap to existing sheet roof using new fasteners or st /screws. | **m** | **1,377** |
| **P012** | 0.47mm thick ,width 450mm Zink aluminium sheet ridging and fixing to roofing sheet with self trapping screws | **m** | **818** |
| **P013** | Ridging with **asbestos** cement close fitting ridges supplied and fixed complete with roofing screws or hook bolts. | **m** | **1,205** |
| | **G.I Flashing** | | |
| **P014** | Flashing, G.I 22 B.W.G 450mm wide, supplying and fixing with 150mm turning up along, and top edge tucking well into wall in cement and lime mortar. | **m** | **1,630** |
| **P015** | 18 BWG (1.2mm) galvanized iron flashing 450mm girth overall 3 times bent with end laps not less than 150mm lead soldered turned and tucked up to not less than 6" into chase out in wall and pointed in cement mortar 1:2 lower end dressed over roof covering. | **m** | **1,819** |
| | **Valley gutter** | | |
| **P016** | Gutters valley, 18 B.W.G 900mm wide, renewing including timber 25mm thick boarding, sheet t be tarred, joints to be soldered and cement lime filleting complete. | **m** | **8,060** |

| Item Code | Item Description | Unit | Basic Rate 2020 |
|---|---|---|---|
| P017 | Supplying and fixing Zinc Aluminium sheet valley gutter (0.47mm) thick ,width 457mm and fixing to roof with self trapping screws.(Excluding timber boarding) Hi-tensile (Grade-550) Colour | m | 1,669 |
| P018 | Supplying and fixing Zinc Aluminium sheet valley gutter (0.47mm) thick ,width 914mm and fixing to roof with self trapping screws.(Excluding timber boarding). Hi-tensile (Grade-550) Colour | m | 2,337 |
| | **G.I semicircular Gutters** | | |
| P019 | Gutters, eaves 150mm G.I semicircular 22 B.W.G making and fixing with hooks or brackets and screws, and joints to be soldered complete. | m | 1,619 |
| P020 | Gutter, eaves 150mm moulded, G.I 22 B.W.G making and fixing complete including brackets. | m | 2,087 |
| P021 | Gutters, existing, making opening to receive 100mm to 150mm down pipe, attaching spigot piece, joints to be soldered and making good. | Nos | 1,413 |
| P022 | Gutter heads, 250mm x 250mm x 600mm making of G.I Sheets 22 B.W.G and fixing. | Nos | 5,257 |
| P023 | Making and fixing Gutter heads, 225mm x 225mm x 300mm of G.I Sheets 22 B.W.G . | Nos | 4,134 |
| P024 | Gutter hooks or brackets 20mm x 3mm supplying and fixing complete with Iron screws. | Nos | 377 |
| | **Aluminium, Zn/Alu high tensile down pipes** | | |
| P025 | Supplying, fixing 0.47mm tk., Zn/Alu high tensile down pipe (914mm girth) with brackets. | m | 1,949 |
| P026 | Supplying, fixing 0.47mm tk., Zn/Alu high tensile down pipe (457mm girth) with brackets. | m | 1,147 |
| | **Zn/Alu gutters** | | |
| P027 | Supplying, fixing 0.47mm tk., Alu gutters (914mm girth) with brackets & specials. | m | 2,171 |
| P028 | Supplying, fixing 0.47mm tk., Alu gutters (457mm girth) with brackets & specials. | m | 1,243 |
| | **Zn/Alu Down pipe Bends** | | |
| P029 | Supplying, fixing 0.47mm tk., Zn/Alu high tensile. Down pipe Bend (for 914mm girth gutter) with brackets & specials. | Nos | 1,476 |
| P030 | Supplying, fixing 0.47mm tk., Zn/Alu high tensile. Down pipe Bend (for 457mm girth gutter) with brackets & specials. | Nos | 930 |
| | **Elbows for down pipe.** | | |
| P031 | Supplying & fixing 90mm P.V.C. elbows for down pipe. | Nos | 455 |
| | **Running head.** | | |
| P032 | Supplying & fixing , only a P.V.C. running head. | Nos | 621 |
| | **Gutter end.** | | |
| P033 | Supplying & fixing , only a square type P.V.C. gutter ends. | Nos | 437 |
| | **Gutter Joint.** | | |
| P034 | Supplying & fixing , only a square type P.V.C. gutter joints. | Nos | 442 |
| | **Eves gutters (PVC)** | | |

| Item Code | Item Description | Unit | Basic Rate 2020 |
|---|---|---|---|
| **P035** | Supplying and fixing eves gutters square type PVC with necessary specials, including running heads, mitre joints, gutter joints, gutter brackets, gutter ends etc. | **m** | **767** |
| **P036** | 150mm diameter half round PVC eaves gutter fixed to timber valance board including gutter joiner and brackets fixed at 450mm centers.(other specials paid separately) | **m** | **564** |
| | **Down pipes 100mm (3 ½") dia. P.V.C** | | |
| **P037** | Supplying & fixing rain water down pipes 100mm (3½") dia. P.V.C to wall, with necessary specials, including elbows, sockets, clips etc. | **m** | **631** |
| | **Skylight glass** | | |
| **P038** | Skylight glass 600mm x 600mm, 6mm thick ribbed, supplied & fixed to roof including necessary lime cement filleting. | **Nos** | **2,249** |

| Item Code | Item Description | Unit | Basic Rate 2020 |
|---|---|---|---|
| | **Q-PLUMBER** | | |
| | **Ball valve-UPVC** | | |
| **Q001** | Supplying & fixing UPVC ball valve 20mm dia. *(S-Lon or equivalent)* | **Nos** | **433** |
| **Q002** | Supplying & fixing UPVC ball valve 25mm dia. (S-Lon or equivalent) | **Nos** | **533** |
| **Q003** | Supplying & fixing UPVC ball valve 32mm dia. (S-Lon or equivalent) | **Nos** | **598** |
| **Q004** | Supplying & fixing UPVC ball valve 40mm dia. (S-Lon or equivalent) | **Nos** | **911** |
| | **Ball valve-Brass** | | |
| **Q005** | Supplying & fixing Brass Ball valve ½" or 20mm-(Peglar or equivalent.) | **Nos** | **1,604** |
| **Q006** | Supplying & fixing Ball valve Brass ¾" or 25mm-(Peglar or equivalent.) | **Nos** | **1,974** |
| **Q007** | Supplying & fixing Ball valve Brass 1" or 32mm-(Peglar or equivalent.) | **Nos** | **2,827** |
| **Q008** | Supplying & fixing Ball valve Brass 1½" or 50mm -(Peglar or equivalent.) with necessary fittings. | **Nos** | **6,028** |
| | **Concealed Taps/Valves-Chromium plated** | | |
| **Q009** | Supply and fixing concealed valve20mm dia. *Prime cost : Rs. 2300.00* | **Nos** | **2,595** |
| | **Flush valve** | | |
| **Q010** | Supplying and fixing wall Urinal Flush Valve(FM 3A903)-High Quality *Prime cost : Rs. 7350.00* | **Nos** | **7,645** |
| | **Gate valve brass for Max. 17.5 bars (Pegler 1065 or equivalent)** | | |
| **Q011** | Supplying and fixing 15mm dia: gate valve brass imported (Pegler or equivalent, approved quality). | **Nos** | **1,565** |
| **Q012** | Supplying and fixing 20mm dia: gate valve brass imported (Pegler or equivalent, approved quality). | **Nos** | **1,935** |
| **Q013** | Supplying and fixing 25mm dia: gate valve brass imported (Pegler or equivalent, approved quality). | **Nos** | **2,554** |
| **Q014** | Supplying and fixing 32mm dia: gate valve brass imported (Pegler or equivalent, approved quality). | **Nos** | **4,244** |
| **Q015** | Supplying and fixing 40mm dia: gate valve brass imported (Pegler or equivalent, approved quality). | **Nos** | **5,174** |
| **Q016** | Supplying and fixing 50mm dia: gate valve brass imported (Pegler or equivalent, approved quality). | **Nos** | **6,930** |
| **Q017** | Supplying and fixing 63mm dia: gate valve brass imported (Pegler or equivalent, approved quality). | **Nos** | **15,260** |
| | **Float valve (Pegler 855 or equivalent)** | | |
| **Q018** | Supplying & fixing 20mm dia. brass float valve with necessary fittings | **Nos** | **3,991** |
| **Q019** | Supplying & fixing 25mm dia. brass float valve with necessary fittings | **Nos** | **6,035** |
| **Q020** | Supplying & fixing 32mm dia. brass float valve with necessary fittings | **Nos** | **10,317** |
| **Q021** | Supplying & fixing 40mm dia. brass float valve with necessary fittings | **Nos** | **15,295** |



This BSR is for construction works only

| Item Code | Item Description | Unit | Basic Rate 2020 |
|---|---|---|---|
| | **Foot valve - Copper** | | |
| **Q022** | Supplying & fixing 32mm dia. Copper foot valve with necessary fittings | **Nos** | **6,920** |
| **Q023** | Supplying & fixing 50mm dia. Copper foot valve with necessary fittings | **Nos** | **11,920** |
| **Q024** | Supplying & fixing 63mm dia. Copper foot valve with necessary fittings | **Nos** | **16,520** |
| | **Foot valve PVC** | | |
| **Q025** | Supplying & fixing 32mm dia. PVC foot valve with necessary fittings (L/D or equivalent) | **Nos** | **1,245** |
| **Q026** | Supplying & fixing 40mm dia. PVC foot valve with necessary fittings (L/D or equivalent) | **Nos** | **1,708** |
| **Q027** | Supplying & fixing 50mm dia. PVC foot valve with necessary fittings (L/D or equivalent) | **Nos** | **1,834** |
| **Q028** | Supplying & fixing 63mm dia. PVC foot valve with necessary fittings (L/D or equivalent) | **Nos** | **1,840** |
| **Q029** | Supplying & fixing 75mm dia. PVC foot valve with necessary fittings (L/D or equivalent) | **Nos** | **2,233** |
| **Q030** | Supplying & fixing 90mm dia. PVC foot valve with necessary fittings (L/D or equivalent) | **Nos** | **3,020** |
| | **Close coupled water closet suite (white) -*Imported*** | | |
| **Q031** | Supplying & fixing, close coupled water closet suite, white, (4/2.6 Lit ) with water closet Pan, Cistern, Seat & Seat cover and trap etc.: complete. (BECA-American standards)<br>*Prime Cost : Rs. 56,400.00* | **Nos** | **60,500** |
| | **Close coupled water closet suite (white)-*Manufactured in Sri Lanka.*** | | |
| **Q032** | Supplying & fixing, Vitreous china floor standing close coupled, Water Closet (toilet) suite (white / Colour) with wash down 6/3 liter dual flushing. Has a horizontal outlet and cistern with water inlet from bottom. Complete with Seat, Seat cover and concealed trap etc. . (Make: Rocell , Model: URBAN-D )<br>*Prime Cost : Rs. 22,700.00* | **Nos** | **26,800** |
| **Q033** | Supplying & fixing, Vitreous china floor standing close coupled, Water Closet (toilet) suite(White/ Colour) with wash down 6/3 liter dual flushing. Has a horizontal outlet and cistern with water inlet from bottom. Complete with Seat, Seat cover and concealed trap etc. . (Make: Rocell , Model: DUNE )<br>*Prime Cost : Rs. 26490.00* | **Nos** | **30,590** |
| **Q034** | Supplying & fixing, Vitreous china floor standing close coupled, Water Closet (toilet) suite with wash down 6/3 liter dual flushing. Has horizontal outlet and two lateral holes for bottom water connection. Cistern with water inlet from bottom. Complete with Seat, Seat cover and concealed trap etc. . (Make: Rocell , Model: INTENCE )<br>*Prime Cost : Rs. 40780.00* | **Nos** | **44,880** |

| Item Code | Item Description | Unit | Basic Rate 2020 |
|---|---|---|---|
| **Q035** | Supplying & fixing, Vitreous china floor standing close coupled, Water Closet (toilet) suite with wash down 6/3 liter dual flushing. Has horizontal outlet and two lateral holes for bottom water connection. Cistern with water inlet from bottom. Complete with Seat, Seat cover and concealed trap etc. . (Make: Rocell , Model: Elements Aqua )<br>*Prime Cost : Rs. 36,050.00* | **Nos** | **40,150** |
| **Q036** | Supplying & fixing, Vitreous china floor standing close coupled, Water Closet (toilet) suite with wash down 6/3 liter dual flushing. Has horizontal outlet and two lateral holes for bottom water connection. Cistern with water inlet from bottom. Complete with Seat, Seat cover and concealed trap etc. . (Make: Rocell , Model: Aqua+ )<br>*Prime Cost : Rs. 42,830.00* | **Nos** | **46,930** |
| **Q037** | Supplying & fixing, Vitreous china floor standing close coupled, Water Closet (toilet) suite with wash down 6/3 liter dual flushing. Has horizontal outlet and two lateral holes for bottom water connection. Cistern with water inlet from bottom. Complete with Seat, Seat cover and concealed trap etc. . (Make: Rocell , Model: Summer Blue )<br>*Prime Cost : Rs. 88,260.00* | **Nos** | **92,360** |
| **Q038** | Supplying & fixing, Vitreous china floor standing close coupled, Water Closet (toilet) suite with wash down 6/3 liter dual flushing. Has horizontal outlet and two lateral holes for bottom water connection. In-Wall Tank Cistern with water inlet from bottom. Complete with Seat, Seat cover and concealed trap etc. . (Make: Rocell , Model: Eternity )<br>*Prime Cost : Rs. 72960.00* | **Nos** | **79,760** |
| **Q039** | Supplying & fixing, Vitreous china floor standing close coupled, Water Closet (toilet) suite with wash down 6/3 liter dual flushing. Has horizontal outlet and two lateral holes for bottom water connection. In-Wall Tank Cistern with water inlet from bottom. Complete with Seat, Seat cover and concealed trap etc. . (Make: Rocell , Model: Urbanity )<br>*Prime Cost : Rs. 73,830.00* | **Nos** | **80,630** |
| **Q040** | Supplying & fixing, Vitreous china floor standing close coupled, Water Closet (toilet) suite with wash down 6/3 liter dual flushing. Has horizontal outlet and two lateral holes for bottom water connection. In-Wall Tank Cistern with water inlet from bottom. Complete with Seat, Seat cover and concealed trap etc. . (Make: Rocell , Model: Escape )<br>*Prime Cost : Rs. 73,530.00* | **Nos** | **80,330** |
| **Q041** | Supplying & fixing Vitreous china floor standing bidet (white colour), Nominal size ( 560mm x 370mm) floor to Rim height 407mm, complete with overflow hole, deck mounted single hole center set bidet faucet. (Dune-Rocell) □ Faucets not included<br>*Prime Cost : Rs. 12970.00* | **Nos** | **14,609** |
| **Q042** | Supplying & fixing Vitreous china floor standing bidet (white colour), Nominal size (560mm x 394mm) floor to Rim height 420mm, complete with overflow hole, deck mounted single hole center set bidet faucet.(Urband D-Rocell) □ Faucets not included<br>*Prime Cost : Rs. 12970.00* | **Nos** | **14,609** |

| Item Code | Item Description | Unit | Basic Rate 2020 |
|---|---|---|---|
| | **Closet-squatting type** | | |
| **Q043** | Supplying & fixing closet, squatting type, with trap. *Prime Cost : Rs. 4790.00* | **Nos** | **9,197** |
| | **Squatting pan- European** | | |
| **Q044** | Supplying and fixing foot rest type squatting pan and trap colour to working order.(American standards)<br>*Prime Cost : Rs. 21183.00* | **Nos** | **25,531** |
| | **Closet squatting type ( Indian or equivalent)** | | |
| **Q045** | Supplying & fixing closet squatting type with trap complete with cistern plastic flush pipe etc.<br>*Prime Cost : Rs. 24,800.00* | **Nos** | **32,449** |
| | **Urinal Imported- Twyford** | | |
| **Q046** | Supplying and fixing (***New wash brook*** ) urinal.(American standards)<br>*Prime Cost : Rs. 38,400.00* | **Nos** | **40,541** |
| **Q047** | Supplying & fixing W**all urinal with brackets**.(American standards)<br>*Prime Cost : Rs. 14,900.00* | **Nos** | **15,429** |
| | **Urinal - *Manufactured in Sri Lanka.*** | | |
| **Q048** | Supplying & fixing W**all urinal with Flush Valve**.(Flo Point Urinal - Rocell)<br>*Prime Cost : Rs. 31,770.00* | **Nos** | **32,299** |
| **Q049** | Supplying & fixing W**all urinal with Flush Valve**.(Dew Point Urinal - Rocell)<br>*Prime Cost : Rs. 26,190* | **Nos** | **26,719** |
| **Q050** | Supplying & fixing W**all urinal with Sensor**.(Flo Point Urinal - Rocell)<br>*Prime Cost : Rs. 46,680.00* | **Nos** | **47,209** |
| **Q051** | Supplying & fixing W**all urinal with Sensor.**(Dew Point Urinal - Rocell)<br>*Prime Cost : Rs. 36,700.00* | **Nos** | **37,229** |
| | **Sink** | | |
| **Q052** | Supplying & fixing sink, glazed, earthenware 762mm x 508mm x 203mm with waste plug, brackets etc. complete. *Prime Cost : Rs. 7875.00* | **Nos** | **10,554** |
| **Q053** | Supplying & fixing sink, glazed earthenware 610mm x 458mm x 203mm with waste plug, brackets etc., complete. *Prime Cost : Rs. 5775.00* | **Nos** | **8,454** |
| | **Stainless steel kitchen sink** | | |
| **Q054** | Supplying & fixing approved quality, stainless steel kitchen sink with single bowl & draining board with necessary waste plug, brackets etc.:<br>*Prime Cost : Rs. 6720.00* | **Nos** | **7,628** |
| **Q055** | Supplying & fixing approved quality, stainless steel kitchen sink with double bowl & draining board with necessary waste plug, brackets etc.:<br>*Prime Cost : Rs. 13125.00* | **Nos** | **14,258** |

| Item Code | Item Description | Unit | Basic Rate 2020 |
|---|---|---|---|
| **Q056** | Supplying & fixing 800mm X510mm stainless steel kitchen sink with single bowl & draining board with necessary waste plug, brackets etc.: ***(Teka or Equivalent)***<br>*Prime Cost : Rs. 21,205.00* | **Nos** | **22,113** |
| **Q057** | Supplying & fixing 1600mm X 510mm stainless steel kitchen sink with double bowl & draining board with necessary waste plug, brackets etc.: ***(Teka or Equivalent)***<br>*Prime Cost : Rs. 41,213.00* | **Nos** | **42,346** |
| | **Wash Basin** | | |
| **Q058** | supplying and fixing Lavatory wash basin with pedestal (American Standard or equivalent)<br>*Prime Cost : Rs. 25,200.00* | **Nos** | **27,119** |
| | **Wash Basin (local Bath wear)** | | |
| **Q059** | Supplying & fixing Vitreous China floor standing wash basin (white colour) having nominal side of ( 584mm x 457mm ) with universal height pedestal of floor to Rim height 838mm, over flow hole and single tap hole in center, including pedestal, Wash basin fixing kit. **(Urband D-Rocell)** □ Cupling, Faucets, waste pipe, paid separately<br>*Prime Cost : Rs. 12,590.00* | **Nos** | **15,055** |
| **Q060** | Supplying & fixing Vitreous China floor standing wash basin (white colour) having nominal side of (622mm x 483mm) with universal height pedestal of floor to Rim height 825mm, over flow hole and single tap hole in center, including pedestal, Wash basin fixing kit. **(Dune-Rocell)** □ Cupling, pipe, paid separately<br>*Prime Cost : Rs. 12,890.00* | **Nos** | **15,355** |
| **Q061** | Supplying & fixing Vitreous China floor standing wash basin (white colour) having nominal side of (622mm x 483mm) with universal height pedestal of floor to Rim height 825mm, over flow hole and single tap hole in center, including pedestal, Wash basin fixing kit. **(Intense-Rocell)** □ Cupling, pipe, paid separately<br>*Prime Cost : Rs. 26,060.00* | **Nos** | **28,525** |
| **Q062** | Supplying & fixing Vitreous China floor standing wash basin (white colour) having nominal side of (622mm x 483mm) with universal height pedestal of floor to Rim height 825mm, over flow hole and single tap hole in center, including pedestal, Wash basin fixing kit. **(Elements Aqua-Rocell)** □ Cupling, pipe, paid separately<br>*Prime Cost : Rs. 20670.00* | **Nos** | **23,135** |
| **Q063** | Supplying & fixing Vitreous China floor standing wash basin (white colour) having nominal side of (622mm x 483mm) with universal height pedestal of floor to Rim height 825mm, over flow hole and single tap hole in center, including pedestal, Wash basin fixing kit. **(Aqua+ -Rocell)** □ Cupling, pipe, paid separately<br>*Prime Cost : Rs. 21,460.00* | **Nos** | **23,925** |

| Item Code | Item Description | Unit | Basic Rate 2020 |
|---|---|---|---|
| **Q064** | Supplying & fixing Vitreous China floor standing wash basin (white colour) wall mounted brackets, over flow hole and single tap hole in center, Wash basin fixing kit. **(Summer Blue-Rocell)** □ Cupling, pipe, paid separately<br>*Prime Cost : Rs. 41,010.00* | **Nos** | **43,475** |
| **Q065** | Supplying & fixing Vitreous China floor standing wash basin (white colour) wall mounted brackets, over flow hole and single tap hole in center, Wash basin fixing kit. **(Eternity-Rocell)** □ Cupling, pipe, paid separately<br>*Prime Cost : Rs. 20,060.00* | **Nos** | **22,525** |
| **Q066** | Supplying & fixing Vitreous China floor standing wash basin (white colour) wall mounted brackets, over flow hole and single tap hole in center, Wash basin fixing kit. **(Urbanity-Rocell)** □ Cupling, pipe, paid separately<br>*Prime Cost : Rs. 27,540.00* | **Nos** | **30,005** |
| | **Corner wash basin (local Bath wear)** | | |
| **Q067** | Supplying & fixing corner wash basin with one tap, waste plug, new brackets etc.(**Aqua Corner - Rocell**)<br>*Prime Cost : Rs. 8,290.00* | **Nos** | **11,054** |
| | **Vanity basin** | | |
| **Q068** | Supplying and fixing Vanity basin 35mm x 406mm white.(Refresh-Twyford or equivalent approved quality)<br>*Prime Cost : Rs. 22827.00* | **Nos** | **25,137** |
| | **Rubber plugs** | | |
| **Q069** | Supplying & fixing plugs, rubber 32mm to 40mm for wash basins and sinks. | **Nos** | **119** |
| **Q070** | Supplying & fixing plugs, rubber 50mm to 63mm for wash basins and sinks. | **Nos** | **124** |
| | **Wooden plugs** | | |
| **Q071** | Bedding in cement mortar 1:2, plugs, wooden, in (Group 6 category A) timber 100mm long, tapered 75mm to 50mm square section, including making holes in walls, floor etc. | **Nos** | **201** |
| | **Bottle traps** | | |
| **Q072** | Supplying & fixing 40mm dia: plastic bottle trap<br>*Prime Cost : Rs. 478.00* | **Nos** | **609** |
| **Q073** | Supplying & fixing 50mm dia: plastic bottle trap<br>*Prime Cost : Rs. 583.00* | **Nos** | **714** |
| **Q074** | Supplying & fixing 63mm dia: plastic bottle trap<br>*Prime Cost : Rs. 767.00* | **Nos** | **898** |
| **Q075** | Supplying & fixing 40mm dia: bottle trap stainless steel approved quality.<br>*Prime Cost : Rs. 5,200.00* | **Nos** | **5,331** |
| **Q076** | Supplying & fixing 40mm square bottle trap stainless steel approved quality.<br>*Prime Cost : Rs. 4,900.00* | **Nos** | **5,031** |
| | **Bib Taps (Metallic)** | | |
| **Q077** | Supplying & fixing brass (Chromium plated), bib taps, 20mm (Rocell or equivalent, approved quality)<br>*Prime Cost : Rs. 3,100.00* | **Nos** | **3,294** |

| Item Code | Item Description | Unit | Basic Rate 2020 |
|---|---|---|---|
| | **Bib Taps (Plastic)** | | |
| **Q078** | Supplying & fixing Plastic Bib Tap 20mm dia. (T- Handle) (S-Lon or Equivalent.)<br>*Prime Cost : Rs. 300.00* | **Nos** | **475** |
| **Q079** | Supplying & fixing Plastic Bib Tap 20mm dia. (Round- Handle)(S-Lon or Equivalent.)<br>*Prime Cost : Rs. 300.00* | **Nos** | **475** |
| **Q080** | Supplying & fixing Plastic Bib Tap 25mm dia. (T- Handle) (S-Lon or Equivalent.)<br>*Prime Cost : Rs. 380.00* | **Nos** | **555** |
| **Q081** | Supplying & fixing Plastic Bib Tap 25mm dia. (Round- Handle)(S-Lon or Equivalent.)<br>*Prime Cost : Rs. 440.00* | **Nos** | **615** |
| **Q082** | Supplying & fixing Plastic long, Neck Bib Tap 20mm dia. (T- Handle) (S-Lon or Equivalent.)<br>*Prime Cost : Rs. 245.00* | **Nos** | **420** |
| **Q083** | Supplying & fixing Plastic Bib Tap, long Neck 20mm dia. (Round- Handle)(S-Lon or Equivalent.)<br>*Prime Cost : Rs. 320.00* | **Nos** | **495** |
| | **Swan-Neck tap-(Metallic)** | | |
| **Q084** | Supplying & fixing chromium plated swan-neck tap 20mm with necessary specials.<br>*Prime Cost : Rs. 4100.00* | **Nos** | **4,481** |
| | **Swan-Neck tap-(Plastic)** | | |
| **Q085** | Supplying & fixing Plastic Swan- tap 20mm dia. (T- Handle) (S-Lon or Equivalent.)<br>*Prime Cost : Rs. 1265.00* | **Nos** | **1,646** |
| **Q086** | Supplying & fixing Plastic Swan-Neck tap 20mm dia. (Round- Handle)(S-Lon or Equivalent.)<br>*Prime Cost : Rs. 1265.00* | **Nos** | **1,646** |
| | **Chromium plated angle Valves 20mm** | | |
| **Q087** | Supplying & fixing chromium plated angle tap 20mm with necessary specials, imported, approved quality. (Rocell or equivalent).<br>*Prime Cost : Rs. 1400.00* | **Nos** | **1,781** |
| **Q088** | Supplying & fixing chromium plated angle tap 20mm with necessary specials, imported, approved quality. (Plumber or equivalent).<br>*Prime Cost : Rs. 1683.00* | **Nos** | **2,064** |
| | **Angle Valves (Plastic)** | | |
| **Q089** | Supplying & fixing Plastic Angle Tap 20mm dia. (T- Handle) (S-Lon or Equivalent.)<br>*Prime Cost : Rs. 290.00* | **Nos** | **671** |

| Item Code | Item Description | Unit | Basic Rate 2020 |
|---|---|---|---|
| **Q090** | Supplying & fixing Plastic Angle 20mm dia. (Round- Handle)(S-Lon or Equivalent.)<br>*Prime Cost : Rs. 320.0* | **Nos** | **701** |
| | **Chromium plated basin tap 20mm** | | |
| **Q091** | Supplying and fixing basin tap.<br>*Prime Cost : Rs. 5100.00* | **Nos** | **5,360** |
| | **Self Closing taps** | | |
| **Q092** | Supplying & fixingself closing tap - 20mm chromium plated.<br>*Prime Cost : Rs. 10,800.00* | **Nos** | **10,994** |
| | **Sensor taps** | | |
| **Q093** | Supplying & fixing sensor taps, 20mm .<br>*Prime cost: Rs. 15000.00* | **Nos** | **18,774** |
| | **Stop Taps (Plastic)** | | |
| **Q094** | Supplying & fixing Plastic Stop Taps **20mm** dia. (T- Handle) (S-Lon or Equivalent.)<br>*Prime cost: Rs. 285.00* | **Nos** | **591** |
| **Q095** | Supplying & fixing Plastic Stop Taps **20mm** dia. (Round- Handle)(S-Lon or Equivalent.)<br>*Prime cost: Rs. 300.00* | **Nos** | **606** |
| **Q096** | Supplying & fixing Plastic Stop Taps **25mm** dia. (T- Handle) (S-Lon or Equivalent.)<br>*Prime cost: Rs. 425.00* | **Nos** | **731** |
| **Q097** | Supplying & fixing Plastic Stop Taps **25mm** dia. (Round- Handle)(S-Lon or Equivalent.)<br>*Prime cost: Rs. 570.00* | **Nos** | **876** |
| **Q098** | Supplying & fixing Plastic Stop Taps **32mm** dia. (T- Handle) (S-Lon or Equivalent.)<br>*Prime cost: Rs. 590.00* | **Nos** | **896** |
| **Q099** | Supplying & fixing Plastic Stop Taps **32mm** dia. (Round- Handle)(S-Lon or Equivalent.)<br>*Prime cost: Rs. 750.00* | **Nos** | **1,056** |
| | **Garden Taps (brass)** | | |
| **Q100** | Supplying & fixing garden tap 20mm dia: brass, heavy quality, with necessary specials, imported, approved quality. *Prime cost: Rs. 2054.00* | **Nos** | **2,229** |
| | **Garden Taps (Plastic)** | | |
| **Q101** | Supplying & fixing Plastic Garden Tap 20mm dia. (T- Handle) (S-Lon or Equivalent.)<br>*Prime cost: Rs. 350.00* | **Nos** | **525** |
| **Q102** | Supplying & fixing Plastic Garden Tap 20mm dia. (Round- Handle)(S-Lon or Equivalent.)<br>*Prime cost: Rs. 440.00* | **Nos** | **615** |

| Item Code | Item Description | Unit | Basic Rate 2020 |
|---|---|---|---|
| | **Pillar cocks** | | |
| **Q103** | Supplying & fixing pillar cocks 20mm Chromium plated, to basins. (Plumber or equivalent) *:Prime cost Rs. 2,500.00* | **Nos** | **2,881** |
| | **Pillar taps** | | |
| **Q104** | Supplying and fixing 20mm dia: chromium plated Pillar tap. (T- handle)<br>*Prime cost: Rs. 4700.00* | **Nos** | **4,875** |
| **Q105** | Supplying and fixing 20mm dia: chromium plated Pillar tap. (Round- handle)<br>*Prime cost: Rs. 2650.00* | **Nos** | **3,031** |
| | **Basin Piller Taps (Plastic)** | | |
| **Q106** | Supplying & fixing Plastic Basin Piller tap 20mm dia. (Round- Handle)(S-Lon or Equivalent.)<br>*Prime cost: Rs. 760.00* | **Nos** | **1,141** |
| | **Stop cock** | | |
| **Q107** | Supplying & fixing stop cock, brass 20mm dia. | **Nos** | **1,669** |
| **Q108** | Supplying & fixing stop cock, brass 25mm dia. | **Nos** | **1,919** |
| **Q109** | Supplying & fixing stop cock, brass 32mm dia. | **Nos** | **3,044** |
| **Q110** | Supplying & fixing stop cock, brass 40mm dia. | **Nos** | **6,769** |
| **Q111** | Supplying & fixing stop cock, brass 50mm dia. | **Nos** | **10,008** |
| **Q112** | Supplying & fixing stop cock, brass 63mmdia. | **Nos** | **16,264** |
| **Q113** | Supplying & fixing stop cock, chromium plated 20mm dia . | **Nos** | **1,669** |
| | **Hooks for pipes** | | |
| **Q114** | Hooks for 20mm pipes, supplying and fixing. | **Nos** | **41** |
| **Q115** | Hooks for 25mm pipes, supplying and fixing. | **Nos** | **41** |
| **Q116** | Hooks for 32mm pipes, supplying and fixing. | **Nos** | **44** |
| **Q117** | Hooks for 40mm pipes, supplying and fixing. | **Nos** | **50** |
| **Q118** | Hooks for 50mm pipes, supplying and fixing. | **Nos** | **51** |
| **Q119** | Hooks for pipes, available, fixing. | **Nos** | **26** |
| | **Jam Nuts** | | |
| **Q120** | Jam Nuts, G.I 1/2"(12.5mm) supplying and fixing. | **Nos** | **102** |
| **Q121** | Jam Nuts, G.I 3/4"(20mm) supplying and fixing. | **Nos** | **113** |
| **Q122** | Jam Nuts, G.I 1"(25mm) supplying and fixing. | **Nos** | **138** |
| **Q123** | Jam Nuts, G.I 1 1/4"(31.25mm) supplying and fixing. | **Nos** | **148** |
| **Q124** | Jam Nuts, G.I 1 1/2"(37.5mm) supplying and fixing. | **Nos** | **166** |
| **Q125** | Jam Nuts, G.I 2"(50mm) supplying and fixing. | **Nos** | **253** |
| | **Nipples, G.I** | | |
| **Q126** | Nipples, G.I 1/2"(12.5mm) Supplying & fixing. | **Nos** | **138** |
| **Q127** | Nipples, G.I 3/4"(20mm) Supplying & fixing | **Nos** | **158** |
| **Q128** | Nipples, G.I 1"(25mm) Supplying & fixing. | **Nos** | **198** |
| **Q129** | Nipples, G.I 1 1/4"(31.25mm) Supplying & fixing. | **Nos** | **248** |
| **Q130** | Nipples, G.I 1 1/2"(37.5mm) Supplying & fixing. | **Nos** | **318** |
| **Q131** | Nipples, G.I 2"(50mm) Supplying & fixing. | **Nos** | **378** |

| Item Code | Item Description | Unit | Basic Rate 2020 |
|---|---|---|---|
| | **Pipes G.I** | | |
| **Q132** | Pipes G.I 1/2"(12.5mm) heavy quality supplying and fixing (fittings to be paid for separately) including any necessary trenching, backfilling and making good, or fixing to walls (pipe hooks to be paid for separately) | **m** | **872** |
| **Q133** | Pipes G.I 3/4"(20mm) heavy quality supplying and fixing (fittings to be paid for separately) including any necessary trenching, backfilling and making good, or fixing to walls (pipe hooks to be paid for separately). | **m** | **977** |
| **Q134** | Pipes, G.I 1"(25mm) heavy quality supplying and fixing (fittings to be paid for separately) including any necessary trenching, backfilling and making good, or fixing to walls. (Pipe hooks to be paid for separately) | **m** | **1,122** |
| **Q135** | Pipes, G.I 1 1/4"(31.25mm) heavy quality supplying and fixing (fittings to be paid for separately) including any necessary trenching, backfilling and making good, or fixing to walls. (Pipe hooks to be paid for separately) | **m** | **1,440** |
| **Q136** | Pipes, G.I 1 1/2"(37.5mm) heavy quality supplying and fixing (fittings to be paid for separately) including any necessary trenching, backfilling and making good, or fixing to walls. (Pipe hooks to be paid for separately) | **m** | **1,843** |
| **Q137** | Pipes, G.I 2"(50mm) heavy quality supplying and fixing (fittings paid for separately) including any necessary trenching, backfilling and making good, or fixing to walls. (Pipe hooks to be paid for separately) | **m** | **2,207** |
| **Q138** | Pipes, G.I 2 1/2" (60mm) heavy quality supplying and fixing (fittings paid for separately) including any necessary trenching, backfilling and making good, or fixing to walls. (Pipe hooks to be paid for separately) | **m** | **2,421** |
| **Q139** | Pipes, G.I 3"(75mm) heavy quality supplying and fixing (fittings to be paid for separately) including any necessary trenching, backfilling and making good, or fixing to walls. (Pipe hooks to be paid for separately) | **m** | **3,359** |
| | **GI Plugs** | | |
| **Q140** | Plugs, G.I 1/2"(12.5mm) supplying and fixing. | **Nos** | **89** |
| **Q141** | Plugs, G.I 3/4" (20mm)supplying and fixing. | **Nos** | **107** |
| **Q142** | Plugs, G.I 1"(25mm) supplying and fixing. | **Nos** | **130** |
| **Q143** | Plugs, G.I 1/4"(31.25mm) supplying and fixing. | **Nos** | **140** |
| **Q144** | Plugs, G.I 1 1/2"(37.5mm) supplying and fixing. | **Nos** | **162** |
| **Q145** | Plugs, G.I 2"(50mm) supplying and fixing. | **Nos** | **214** |
| | **Socket G.I** | | |
| **Q146** | Socket G.I 1/2"(12.5mm) plain supplying & fixing. | **Nos** | **133** |
| **Q147** | Socket, G.I 3/4"(20mm) plain supplying and fixing. | **Nos** | **145** |
| **Q148** | Socket, G.I 1" (25mm) plain supplying and fixing. | **Nos** | **168** |
| **Q149** | Socket, G.I 1 1/4" (31.25mm) plain supplying and fixing. | **Nos** | **191** |
| **Q150** | Socket, G.I 1 1/2"(37.5mm) plain supplying and fixing. | **Nos** | **214** |
| **Q151** | Socket, G.I 2"(50mm) plain supplying and fixing. | **Nos** | **332** |
| **Q152** | Socket, G.I 3"(75mm) plain supplying and fixing. | **Nos** | **554** |
| **Q153** | Socket, G.I reducing 3/4"(20mm) to smaller sizes supplying and fixing. | **Nos** | **177** |
| **Q154** | Socket, G.I reducing 1" (25mm)to smaller size supplying and fixing. | **Nos** | **181** |
| **Q155** | Socket, G.I reducing 1 1/4"(31.25mm) to smaller sizes supplying and fixing. | **Nos** | **250** |
| **Q156** | Socket, G.I reducing 1 1/2"(37.5mm) to smaller sizes supplying and fixing. | **Nos** | **304** |

| Item Code | Item Description | Unit | Basic Rate 2020 |
|---|---|---|---|
| Q157 | Socket G.I reducing 2"(50mm) to smaller sizes, supplying and fixing. | Nos | 382 |
| Q158 | Sockets G.I reducing 3"(75mm) to smaller sizes supplying and fixing. | Nos | 436 |
| | **Plastishell (Single Layer) water tank (Slon PE+ or Equivalent)** | | |
| Q159 | Supplying and fixing Plastishell (Single Layer) water tank 350 liter capacity. ( fittings paid for separately ).<br>*Prime cost: Rs. 7600.00* | Nos | 10,219 |
| Q160 | Supplying and fixing Plastishell (Single Layer) water tank 500 liter capacity. ( fittings paid for separately ).<br>*Prime cost: Rs. 9670.00* | Nos | 12,089 |
| Q161 | Supplying and fixing Plastishell (Single Layer) water tank 750 liter capacity. ( fittings paid for separately ).<br>*Prime cost: Rs. 16000.00* | Nos | 18,795 |
| Q162 | Supplying and fixing Plastishell (Single Layer) water tank 1000 liter capacity. ( fittings paid for separately ).<br>*Prime cost: Rs. 21535.00* | Nos | 24,330 |
| | **Plastishell (Triple Layer) water tank (Slon PE+ Premium or Equivalent)** | | |
| Q163 | Supplying and fixing Plastishell (Triple Layer) water tank,5000 liter capacity. ( fittings paid for separately ).<br>*Prime cost: Rs. 86700.00* | Nos | 90,750 |
| | **Floater switch** | | |
| Q164 | Supplying and fixing floater switch with necessary fittings to over head water tank.<br>*Prime cost: Rs. 1000.00* | Nos | 2,800 |
| | **Tees** | | |
| Q165 | Tees, G.I 1/2"(12.5mm) equal supplying and fixing. | Nos | 226 |
| Q166 | Tees, G.I 3/4" (20mm) equal supplying and fixing. | Nos | 243 |
| Q167 | Tees, G.I 1"(25mm) equal supplying and fixing. | Nos | 317 |
| Q168 | Tees, G.I 1 1/4"(31.25mm) equal supplying and fixing. | Nos | 409 |
| Q169 | Tees, G.I 1 1/2"(37.5mm) equal supplying and fixing. | Nos | 493 |
| Q170 | Tees, G.I 2"(50mm) equal, supplying and fixing. | Nos | 698 |
| | **Soap tray/dish** | | |
| Q171 | Supplying and fixing chromium plated soap tray. (American Standard or Equivalent.)<br>*Prime Cost Rs. 9020.00* | Nos | 9,390 |
| Q172 | Supplying and fixing soap dish (American Standard or Equivalent.)<br>*Prime Cost Rs. 4780.00* | Nos | 5,150 |
| Q173 | Supplying & fixing soap dispenser (American Standard or Equivalent.)<br>*Prime Cost Rs. 43,760.00* | Nos | 43,989 |
| | **Towel rail** | | |
| Q174 | Supplying & fixing chromium plated Towel rail (American Standard or Equivalent.-S. No:6588) , 600mm long and , 25mm dia. with necessary rawl plugs and screws.<br>*Prime Cost Rs. 6,370.00* | Nos | 6,772 |

| Item Code | Item Description | Unit | Basic Rate 2020 |
|---|---|---|---|
| | **Paper holder SEVA** | | |
| **Q175** | Supplying & fixing SEVA paper holder (American Standard or Equivalent.) complete to working order.<br>*Prime Cost Rs. 5,840.00* | **Nos** | **5,988** |
| | **Tooth brush holder** | | |
| **Q176** | Supplying & fixing tooth brush holder (American Standard or Equivalent.) complete to working order.<br>*Prime Cost Rs. 3,940.00* | **Nos** | **4,088** |
| | **Robe hook (SEVA)** | | |
| **Q177** | Supplying & fixing SEVA Robe hook (American Standard or Equivalent.) complete to working order.<br>*Prime Cost Rs. 4,510.00* | **Nos** | **4,658** |
| | **Bath room mirror,** | | |
| **Q178** | Supplying & fixing mirror, beveled, bath room type, oval shape, 508mm x 406mm Max. and min. dimensions, to wall with Rawl plugs and chromium plated fittings.<br>*Prime Cost Rs. 5000.00* | **Nos** | **5,956** |
| **Q179** | Supplying & fixing 610mm x 203mm, 5mm thickness beveled rectangular mirror, to wall with Rawl plugs, noton tape and chromium plated fittings.<br>*Prime Cost Rs. 3,650.00* | **Nos** | **4,606** |
| | **Shower rose** | | |
| **Q180** | Supplying & fixing shower Rose 175mm chromium plated. | **Nos** | **450** |
| **Q181** | Supplying & fixing PVC- 150mm x 20mm shower rose. | **Nos** | **911** |
| | **Plastic Jet Shower rose** | | |
| **Q182** | Supplying & fixing Plastic Jet Shower Rose 20mm dia. (S-Lon or Equivalent.) | **Nos** | **1,032** |
| **Q183** | Supplying & fixing **Jet shower** complete(American Standard or Equivalent.)<br>*Prime Cost Rs. 7784.00* | **Nos** | **7,975** |
| | **Shower head** | | |
| **Q184** | Supplying & fixing Shower head with arm. (American Standard)<br>*Prime Cost Rs. 6,900.00* | **Nos** | **7,091** |
| | **Bidet spray imported** | | |
| **Q185** | Supplying and fixing bidet spray - Plastic<br>*Prime Cost Rs. 1,300.00* | **Nos** | **1,702** |
| **Q186** | Supplying and fixing bidet spray Chromium Plated (Plumber or equivalent)<br>*Prime Cost Rs. 3800.00* | **Nos** | **4,212** |
| | **Bends P.V.C** | | |
| **Q187** | Supplying & fixing bends P.V.C 20mm. | **Nos** | **102** |
| **Q188** | Supplying & fixing bends P.V.C 25mm. | **Nos** | **118** |
| **Q189** | Supplying & fixing bends P.V.C 32mm. | **Nos** | **138** |
| **Q190** | Supplying & fixing bends P.V.C 40mm. | **Nos** | **225** |

| Item Code | Item Description | Unit | Basic Rate 2020 |
|---|---|---|---|
| **Q191** | Supplying & fixing bends P.V.C 50mm. | **Nos** | **320** |
| **Q192** | Supplying & fixing bends P.V.C 63mm. | **Nos** | **475** |
| **Q193** | Supplying & fixing bends P.V.C 90mm. | **Nos** | **1,905** |
| | **Elbows P.V.C** | | |
| **Q194** | Supplying & fixing elbows P.V.C 20mm. | **Nos** | **87** |
| **Q195** | Supplying & fixing elbows P.V.C 25mm. | **Nos** | **109** |
| **Q196** | Supplying & fixing elbows P.V.C 32mm. | **Nos** | **120** |
| **Q197** | Supplying & fixing elbows P.V.C 40mm. | **Nos** | **150** |
| **Q198** | Supplying & fixing elbows P.V.C 50mm. | **Nos** | **225** |
| **Q199** | Supplying & fixing elbows P.V.C 63mm. | **Nos** | **285** |
| **Q200** | Supplying & fixing elbows P.V.C 90mm. | **Nos** | **715** |
| | **Reducing sockets & Tees P.V.C** | | |
| **Q201** | Supplying & fixing sockets reducing P.V.C (25mm x 20mm ) to smaller sizes. | **Nos** | **99** |
| **Q202** | Supplying & fixing sockets reducing P.V.C (32mm x 25mm) to smaller sizes. | **Nos** | **115** |
| **Q203** | Supplying & fixing sockets reducing P.V.C (40mm x 32mm) to smaller sizes. | **Nos** | **154** |
| **Q204** | Supplying & fixing sockets reducing P.V.C (50mm x40mm) to smaller sizes. | **Nos** | **197** |
| **Q205** | Supplying & fixing sockets reducing P.V.C (63mm x 32mm) to smaller sizes. | **Nos** | **229** |
| **Q206** | Supplying & fixing sockets reducing P.V.C (63mm x50mm) to smaller sizes. | **Nos** | **245** |
| | **Reducing Tees P.V.C** | | |
| **Q207** | Supplying & fixing tees reducing P.V.C (25mm x 20mm ) to smaller sizes. | **Nos** | **119** |
| **Q208** | Supplying & fixing tees reducing P.V.C (32mm x 25mm) to smaller sizes. | **Nos** | **121** |
| **Q209** | Supplying & fixing tees reducing P.V.C (40mm x32mm) to smaller sizes. | **Nos** | **194** |
| **Q210** | Supplying & fixing tees reducing P.V.C (50mm x 40mm) to smaller sizes. | **Nos** | **277** |
| **Q211** | Supplying & fixing tees reducing P.V.C (63mm x 50mm) to smaller sizes. | **Nos** | **420** |
| **Q212** | Supplying & fixing tees reducing P.V.C (90mm x 63mm) to smaller sizes. | **Nos** | **1,000** |
| **Q213** | Supplying & fixing reducing tee P.V.C. ( 110mm x 63mm) | **Nos** | **2,065** |
| | **Repair Sockets & Tees P.V.C** | | |
| **Q214** | Supplying & fixing repair socket P.V.C 20mm. | **Nos** | **90** |
| **Q215** | Supplying & fixing repair socket P.V.C 25mm. | **Nos** | **95** |
| **Q216** | Supplying & fixing repair socket P.V.C 32mm. | **Nos** | **109** |
| **Q217** | Supplying & fixing repair socket P.V.C 40mm. | **Nos** | **135** |
| **Q218** | Supplying & fixing repair socket P.V.C 50mm. | **Nos** | **187** |
| **Q219** | Supplying & fixing repair socket P.V.C 63mm. | **Nos** | **279** |
| **Q220** | Supplying & fixing repair socket P.V.C 90mm. | **Nos** | **630** |
| | **Valve Socket P.V.C** | | |
| **Q221** | Supplying & fixing valve socket P.V.C 20mm. | **Nos** | **94** |
| **Q222** | Supplying & fixing valve socket P.V.C 25mm. | **Nos** | **108** |
| **Q223** | Supplying & fixing valve socket P.V.C 32mm. | **Nos** | **119** |
| **Q224** | Supplying & fixing valve socket P.V.C 40mm. | **Nos** | **159** |
| **Q225** | Supplying & fixing valve socket P.V.C 50mm. | **Nos** | **187** |
| **Q226** | Supplying & fixing valve socket P.V.C 63mm. | **Nos** | **229** |

| Item Code | Item Description | Unit | Basic Rate 2020 |
|---|---|---|---|
| Q227 | Supplying & fixing valve socket P.V.C 90mm. | Nos | 605 |
| | **Faucet Socket P.V.C** | | |
| Q228 | Supplying & fixing faucet sockets P.V.C 20mm. | Nos | 92 |
| Q229 | Supplying & fixing faucet sockets P.V.C 25mm. | Nos | 109 |
| Q230 | Supplying & fixing faucet sockets P.V.C 32mm. | Nos | 120 |
| Q231 | Supplying & fixing faucet sockets P.V.C 40mm. | Nos | 163 |
| Q232 | Supplying & fixing faucet sockets P.V.C 50mm. | Nos | 195 |
| Q233 | Supplying & fixing faucet sockets P.V.C 63mm. | Nos | 242 |
| Q234 | Supplying & fixing faucet sockets P.V.C 90mm. | Nos | 605 |
| | **Tapered union without thread P.V.C** | | |
| Q235 | Supplying & fixing tapered union without thread P.V.C 20mm. | Nos | 622 |
| Q236 | Supplying & fixing tapered union without thread P.V.C 25mm. | Nos | 1,005 |
| Q237 | Supplying & fixing tapered union without thread P.V.C 32mm. | Nos | 1,084 |
| Q238 | Supplying & fixing tapered union without thread P.V.C 40mm. | Nos | 1,798 |
| Q239 | Supplying & fixing tapered union without thread P.V.C 50mm. | Nos | 2,323 |
| Q240 | Supplying & fixing tapered union without thread P.V.C 63mm. | Nos | 3,005 |
| Q241 | Supplying & fixing tapered union without thread P.V.C 90mm. | Nos | 3,320 |
| Q242 | Supplying & fixing tapered union with thread for P.V.C and metal pipe connection 20mm. | Nos | 333 |
| Q243 | Supplying & fixing tapered union 25mm with thread for P.V.C & metal pipe connections. | Nos | 438 |
| Q244 | Supplying & fixing tapered union 32mm with thread for P.V.C & metal pipe connections. | Nos | 438 |
| Q245 | Supplying & fixing tapered union 40mm with thread for P.V.C & metal pipe connections. | Nos | 706 |
| Q246 | Supplying & fixing tapered union 50mm with thread for P.V.C & metal pipe connections. | Nos | 832 |
| Q247 | Supplying & fixing tapered union 63mm with thread for P.V.C & metal pipe connections. | Nos | 1,483 |
| Q248 | Supplying & fixing tapered union 90mm with thread for P.V.C & metal pipe connections. | Nos | 2,060 |
| | **Equal tees-P.V.C** | | |
| Q249 | Supplying & fixing tees equal P.V.C 20mm. | Nos | 92 |
| Q250 | Supplying & fixing tees equal P.V.C 25mm. | Nos | 119 |
| Q251 | Supplying & fixing tees equal P.V.C 32mm. | Nos | 148 |
| Q252 | Supplying & fixing tees equal P.V.C 40mm. | Nos | 200 |
| Q253 | Supplying & fixing tees equal P.V.C 50mm. | Nos | 295 |
| Q254 | Supplying & fixing tees equal P.V.C 63mm. | Nos | 365 |
| Q255 | Supplying & fixing tees equal P.V.C 90mm. | Nos | 975 |
| | **Plugs, sockets-P.V.C** | | |
| Q256 | Supplying & fixing plugs P.V.C 20mm. | Nos | 95 |
| Q257 | Supplying & fixing plugs P.V.C 25mm. | Nos | 104 |
| Q258 | Supplying & fixing plugs P.V.C 32mm | Nos | 116 |
| Q259 | Supplying & fixing plugs P.V.C 40mm. | Nos | 139 |
| Q260 | Supplying & fixing plugs P.V.C 50mm. | Nos | 170 |

| Item Code | Item Description | Unit | Basic Rate 2020 |
|---|---|---|---|
| **Q261** | Supplying & fixing Plugs P.V.C 63mm. | **Nos** | **200** |
| **Q262** | Supplying & fixing plugs P.V.C 90mm. | **Nos** | **610** |
| **Q263** | Supplying & fixing sockets plain P.V.C 20mm. | **Nos** | **87** |
| **Q264** | Supplying & fixing sockets plain P.V.C 25mm. | **Nos** | **101** |
| **Q265** | Supplying & fixing sockets plain P.V.C 32mm. | **Nos** | **115** |
| **Q266** | Supplying & fixing sockets plain P.V.C 40mm. | **Nos** | **142** |
| **Q267** | Supplying & fixing sockets plain P.V.C 50mm. | **Nos** | **180** |
| **Q268** | Supplying & fixing sockets plain P.V.C 63mm. | **Nos** | **215** |
| **Q269** | Supplying & fixing sockets plain P.V.C 90mm. | **Nos** | **530** |
| | **Pipes P.V.C** | | |
| **Q270** | Supplying & fixing pipes P.V.C, 20mm dia.($PN_T$ 11)- PE.(Fittings paid separately). | **m** | **85** |
| **Q271** | Supplying & fixing pipes P.V.C, 25mm dia..($PN_T$ 11)- PE (Fittings paid separately). | **m** | **177** |
| **Q272** | Supplying & fixing pipes P.V.C, 32mm dia..($PN_T$ 11)- PE(Fittings paid separately). | **m** | **417** |
| **Q273** | Supplying & fixing pipes P.V.C, 40mm dia. .($PN_T$ 11)- PE(Fittings paid separately). | **m** | **531** |
| **Q274** | Supplying & fixing pipes P.V.C 50mm dia. .($PN_T$ 11)- PE (Fittings paid separately). | **m** | **672** |
| **Q275** | Supplying & fixing pipes P.V.C, 63mm dia..($PN_T$ 11)- PE (Fittings paid separately). | **m** | **1,050** |
| **Q276** | Supplying & fixing pipes P.V.C 90mm dia. .($PN_T$ 11)- PE (Fittings paid separately). | **m** | **1,919** |
| | **Pipes P.V.C (25% pipe cost included for Specials)** | **m** | |
| **Q277** | Supplying & fixing pipes P.V.C, 20mm dia. .($PN_T$ 11) including specials. (25% pipe cost included for Specials) | **m** | **108** |
| **Q278** | Supplying & fixing pipes P.V.C, 25mm dia. .($PN_T$ 11) including specials. (25% pipe cost included for Specials) | **m** | **223** |
| **Q279** | Supplying & fixing pipes P.V.C, 32mm dia. .($PN_T$ 11) including specials. (25% pipe cost included for Specials) | **m** | **499** |
| **Q280** | Supplying & fixing pipes P.V.C, 40mm dia. .($PN_T$ 11) including specials. (25% pipe cost included for Specials) | **m** | **640** |
| **Q281** | Supplying & fixing pipes P.V.C, 50mm dia. .($PN_T$ 11) including specials. (25% pipe cost included for Specials) | **m** | **813** |
| **Q282** | Supplying & fixing pipes P.V.C, 63mm dia. .($PN_T$ 11) including specials. (25% pipe cost included for Specials) | **m** | **1,282** |
| | **Flexible cord (S--Lon or Equivalent))** | | |
| **Q283** | Supplying and fixing flexible cord -300mm (S-lon or equivalent) | **Nos** | **351** |
| **Q284** | Supplying and fixing flexible cord -450mm (S-lon or equivalent) | **Nos** | **441** |
| **Q285** | Supplying and fixing flexible cord -600mm (S-lon or equivalent) | **Nos** | **516** |
| **Q286** | Supplying and fixing flexible cord -1200mm (S-lon or equivalent) | **Nos** | **646** |

| Item Code | Item Description | Unit | Basic Rate 2020 |
|---|---|---|---|
| **Q287** | Supplying and fixing flexible cord -1500mm (S-lon or equivalent) | **Nos** | **726** |
| | **Flexible hose** | | |
| **Q288** | Supplying and fixing 20mm dia: Flexible hose (American Standard or Equivalent.) 450mm long<br>*Prome cost Rs. 1080.00* | **Nos** | **1,251** |
| | **Plastic gully** | | |
| **Q289** | Supplying & fixing plastic gully grating 150mm x150mm. | **Nos** | **210** |
| **Q290** | Providing **Catch pit** 150mm x150mm x75mm in cement mortar. | **Nos** | **739** |
| | **Elbows for down pipe.** | | |
| **Q291** | Supplying & fixing P.V.C. elbows for down pipe. | **Nos** | **593** |
| | **Running head.** | | |
| **Q292** | Supplying & fixing P.V.C. running head. | **Nos** | **660** |
| | **Gutter end.** | | |
| **Q293** | Supplying & fixing or replacing, only a square type P.V.C. gutter ends. | **Nos** | **460** |
| | **Gutter Joint.** | | |
| **Q294** | Supplying & fixing or replacing, only a square type P.V.C. gutter joints. | **Nos** | **465** |
| | **Eves gutters (PVC)-Square type** | | |
| **Q295** | Supplying and fixing eves gutters square type PVC with necessary specials, including running heads, miter joints, gutter joints, gutter brackets, gutter ends etc. | **m** | **807** |
| | **Down pipes P.V.C** | | |
| **Q296** | Supplying & fixing rain water down pipes P.V.C to wall, with necessary specials, including elbows, sockets, clips etc. | **m** | **705** |

| Item Code | Item Description | Unit | Basic Rate 2020 |
|---|---|---|---|
| | **R-MECHANICAL INSTALLATIONS** | | |
| | **Unitary Air Conditioning Equipments** | | |
| | Air Cooled inverter Type wall mounted split air conditioners such as L.G., Mitsubishi, Daikin or quivelant (refrigerant zero ODP) of cooling capacity as specified (direct expansion) c/w Refrigerant Piping, Drain line, Insulation, Drain pumps, control, brackets and Condensing units c/w motors, compressors, condenser, copper tubes and pre-painted anti-corrosion resin coated aluminium fins, blowers, filter drier, refrigerant..(Refrigirat pipe length of 5m considered inclusive to the rate) | | |
| **R001** | 9000 Btu/Hr | **Nos** | **128,150** |
| **R002** | 12000 Btu/Hr | **Nos** | **133,500** |
| **R003** | 18000 Btu/Hr | **Nos** | **154,900** |
| **R004** | 24000 Btu/Hr | **No.** | **178,350** |
| | Air Cooled non inverter Type wall mounted split air conditioners such as L.G., Mitsubishi, Daikin or quivelant (refrigerant zero ODP) of cooling capacity as specified (direct expansion) c/w Refrigerant Piping, Drain line, Insulation, Drain pumps, control, brackets and Condensing units c/w motors, compressors, condenser, copper tubes and pre-painted anti-corrosion resin coated aluminium fins, blowers, filter drier, refrigerant.(Refrigirat pipe length of 5m considered inclusive to the rate.) | | |
| **R005** | 9000 Btu/Hr | **Nos** | **120,660** |
| **R006** | 12000 Btu/Hr | **Nos** | **130,825** |
| **R007** | 18000 Btu/Hr | **Nos** | **149,550** |
| **R008** | 24000 Btu/Hr | **Nos** | **209,850** |
| | Air Cooled inverter Type Ceiling mounted split air conditioners such as L.G., Mitsubishi, Daikin or quivelant (refrigerant zero ODP) of cooling capacity as specified (direct expansion) c/w Refrigerant Piping, Drain line, Insulation, Drain pumps, control, brackets and Condensing units c/w motors, compressors, condenser, copper tubes and pre-painted anti-corrosion resin coated aluminium fins, blowers, filter drier, refrigerant.(Refrigirat pipe length of 5m considered inclusive to the rate.) | | |
| **R009** | 18000 Btu/Hr | **Nos** | **310,050** |
| **R010** | 24000 Btu/Hr | **Nos** | **404,100** |
| **R011** | 36000 Btu/Hr | **Nos** | **467,100** |

| Item Code | Item Description | Unit | Basic Rate 2020 |
|---|---|---|---|
| | Air Cooled non inverter Type Ceiling mounted split air conditioners such as L.G., Mitsubishi, Daikin or quivelant (refrigerant zero ODP) of cooling capacity as specified(direct expansion) c/w Refrigerant Piping, Drain line, Insulation, Drain pumps, control, brackets and Condensing units c/w motors, compressors, condenser, copper tubes and pre-painted anti-corrosion resin coated aluminium fins, blowers, filter drier, refrigerant.(Refrigirat pipe length of 5m considered inclusive to the rate.) | | |
| **R012** | 18000 Btu/Hr | **Nos** | **272,600** |
| **R013** | 24000 Btu/Hr | **Nos** | **309,600** |
| **R014** | 36000 Btu/Hr | **Nos** | **377,850** |
| | Air Cooled inverter Type Ceiling Suspended 4 Way Cassete split air conditioners such as L.G., Mitsubishi, Daikin or quivelant (refrigerant zero ODP) of cooling capacity as specified (direct expansion) c/w Refrigerant Piping, Drain line, Insulation, Drain pumps, control, brackets and Condensing units c/w motors, compressors, condenser, copper tubes and pre-painted anti-corrosion resin coated aluminium fins, blowers, filter drier, refrigerant.(Refrigirat pipe length of 5m considered inclusive to the rate.) | | |
| **R015** | 12000 Btu/Hr | **Nos** | **261,900** |
| **R016** | 18000 Btu/Hr | **Nos** | **285,100** |
| **R017** | 24000 Btu/Hr | **Nos** | **362,100** |
| **R018** | 36000 Btu/Hr | **Nos** | **519,600** |
| | Air Cooled non inverter Type Ceiling Suspended 4 Way Cassete split air conditioners such as L.G., Mitsubishi, Daikin or quivelant (refrigerant zero ODP) of cooling capacity as specified (direct expansion) c/w Refrigerant Piping, Drain line, Insulation, Drain pumps, control, brackets and Condensing units c/w motors, compressors, condenser, copper tubes and pre-painted anti-corrosion resin coated aluminium fins, blowers, filter drier, refrigerant.(Refrigirat pipe length of 5m considered inclusive to the rate.) | | |
| **R019** | 18000 Btu/Hr | **Nos** | **272,600** |
| **R020** | 24000 Btu/Hr | **Nos** | **309,600** |
| **R021** | 36000 Btu/Hr | **Nos** | **377,850** |
| | Air Cooled inverter Type Ceiling mounted ducted type split air conditioners such as L.G., Mitsubishi, Daikin or quivelant (refrigerant zero ODP) of cooling capacity as specified (direct expansion) c/w Refrigerant Piping, Drain line, Insulation, Drain pumps, control, brackets and Condensing units c/w motors, compressors, condenser, copper tubes and pre-painted anti-corrosion resin coated aluminium fins, blowers, filter drier, refrigerant.(Refrigirat pipe length of 5m considered inclusive to the rate.) | | |
| **R022** | 12000 Btu/Hr | **Nos** | **265,645** |
| **R023** | 18000 Btu/Hr | **Nos** | **276,345** |
| **R024** | 24000 Btu/Hr | **Nos** | **323,775** |
| **R025** | 36000 Btu/Hr | **Nos** | **476,025** |

| Item Code | Item Description | Unit | Basic Rate 2020 |
|---|---|---|---|
| | Air Cooled non inverter Type Ceiling mounted ducted type split air conditioners such as L.G., Mitsubishi, Daikin or quivelant (refrigerant zero ODP) of cooling capacity as specified (direct expansion) c/w Refrigerant Piping, Drain line, Insulation, Drain pumps, control, brackets and Condensing units c/w motors, compressors, condenser, copper tubes and pre-painted anti-corrosion resin coated aluminium fins, blowers, filter drier, refrigerant.(Refrigirat pipe length of 5m considered inclusive to the rate.) | | |
| **R026** | 12000 Btu/Hr | **Nos** | **181,550** |
| **R027** | 18000 Btu/Hr | **Nos** | **201,445** |
| **R028** | 24000 Btu/Hr | **Nos** | **255,525** |
| **R029** | 36000 Btu/Hr | **Nos** | **255,525** |
| | **Medical Grade Copper Pipes and Fittings** | | |
| | Medical grade Phosphorous De-Oxidized, Degreased and Non-Arsenical Copper pipes, Pipe Fittings and valvescompied to BSEN 13348, Joint shall normally be made on site by silver copper phosphate brazing using British Standard 1845 type AG 14 alloy and fittings shall be of the "high duty" type suitable for steam service gauge pressure up to 17 bars. | | |
| | **Medical Grade Copper Pipes** | | |
| **R030** | 15 mm diameter | **m** | **1,493** |
| **R031** | 22 mm diameter | **m** | **2,723** |
| **R032** | 28 mm diameter | **m** | **4,058** |
| **R033** | 35 mm diameter | **m** | **4,748** |
| **R034** | 42 mm diameter | **m** | **6,368** |
| | **Lockable Line Valves** | | |
| **R035** | 15 mm diameter | **Nos** | **11,520** |
| **R036** | 22 mm diameter | **Nos** | **13,095** |
| **R037** | 28 mm diameter | **Nos** | **22,335** |
| **R038** | 35 mm diameter | **Nos** | **31,575** |
| **R039** | 42 mm diameter | **Nos** | **45,585** |
| | **90 Degree Elbow** | | |
| **R040** | End Feed 15mm x 90 Degree Elbow | **Nos.** | **141** |
| **R041** | End Feed 22mm x 90 Degree Elbow | **Nos.** | **301** |
| **R042** | End Feed 28mm x 90 Degree Elbow | **Nos.** | **469** |
| **R043** | End Feed 35mm x 90 Degree Elbow | **Nos.** | **1,415** |
| **R044** | End Feed 42mm x 90 Degree Elbow | **Nos.** | **2,359** |
| | **Couplings** | | |
| **R045** | End Feed 15mm Coupling | **Nos** | **164** |
| **R046** | End Feed 22mm Coupling | **Nos** | **359** |

| Item Code | Item Description | Unit | Basic Rate 2020 |
|---|---|---|---|
| **R047** | End Feed 28mm Coupling | **Nos** | **617** |
| **R048** | End Feed 35mm Coupling | **Nos** | **623** |
| **R049** | End Feed 42mm Coupling | **Nos** | **860** |
| | **Equal Tee** | | |
| **R050** | End Feed 15mm Equal Tee | **Nos** | **256** |
| **R051** | End Feed 22mm Equal Tee | **Nos** | **669** |
| **R052** | End Feed 28mm Equal Tee | **Nos** | **1,038** |
| **R053** | End Feed 35mm Equal Tee | **Nos** | **1,711** |
| **R054** | End Feed 42mm Equal Tee | **Nos** | **2,544** |
| | **Reducing Coupling** | | |
| **R055** | End Feed 22mm x 15mm Fitting Reducer | **Nos** | **822** |
| **R056** | End Feed 28mm x 15mm Fitting Reducer | **Nos** | **1,466** |
| **R057** | End Feed 28mm x 22mm Fitting Reducer | **Nos** | **1,502** |
| **R058** | End Feed 35mm x 22mm Fitting Reducer | **Nos** | **1,562** |
| **R059** | End Feed 35mm x 28mm Fitting Reducer | **Nos** | **1,610** |
| **R060** | End Feed 42mm x 35mm Fitting Reducer | **Nos** | **1,741** |
| | **Reducing Tee** | | |
| **R061** | End Feed 22mm x 15mm Fitting Reducer | **Nos** | **859** |
| **R062** | End Feed 28mm x 15mm Fitting Reducer | **Nos** | **1,568** |
| **R063** | End Feed 28mm x 22mm Fitting Reducer | **Nos** | **1,568** |
| **R064** | End Feed 35mm x 22mm Fitting Reducer | **Nos** | **3,157** |
| **R065** | End Feed 35mm x 28mm Fitting Reducer | **Nos** | **3,157** |
| **R066** | End Feed 42mm x 35mm Fitting Reducer | **Nos** | **3,330** |
| | **Brass Munsen Rings - Single Ring M10** | | |
| **R067** | 15mm Brass Munsen Ring Tapped M10 | **Nos** | **728** |
| **R068** | 22mm Brass Munsen Ring Tapped M10 | **Nos** | **749** |
| **R069** | 28mm Brass Munsen Ring Tapped M10 | **Nos** | **812** |
| **R070** | 35mm Brass Munsen Ring Tapped M10 | **Nos** | **896** |
| **R071** | 42mm Brass Munsen Ring Tapped M10 | **Nos** | **938** |
| | **FRESH AIR DUCTING WORK** | | |
| | pre-insulated supply air duct works including all bends, reducers, flange joints, silicon sealant for all joints, anti vibration joint, Reinforcements, hangers etc….. | | |
| **R072** | 100 x 100 mm | **m** | **2,333** |
| **R073** | 150 x 100 mm | **m** | **2,841** |
| **R074** | 150 x 150 mm | **m** | **3,349** |
| **R075** | 200 x 150 mm | **m** | **3,857** |
| **R076** | 500 x 150 mm | **m** | **8,570** |
| **R077** | 200 x 200 mm | **m** | **5,344** |
| **R078** | 250 x 200 mm | **m** | **5,485** |
| **R079** | 300 x 200 mm | **m** | **6,270** |
| **R080** | 350 x 200 mm | **m** | **7,309** |
| **R081** | 400 x 200 mm | **m** | **7,940** |
| **R082** | 500 x 200 mm | **m** | **9,200** |
| **R083** | 200 x 250 mm | **m** | **5,974** |

| Item Code | Item Description | Unit | Basic Rate 2020 |
|---|---|---|---|
| **R084** | 300 x 250 mm | **m** | **7,309** |
| **R085** | 400 x 250 mm | **m** | **8,645** |
| **R086** | 550 x 250 mm | **m** | **9,691** |
| **R087** | 575 x 250 mm | **m** | **10,852** |
| **R088** | 650x 250 mm | **m** | **11,797** |
| **R089** | 675 x 250 mm | **m** | **12,112** |
| **R090** | 700 x 250mm | **m** | **12,427** |
| **R091** | 900 x 250 mm | **m** | **14,949** |
| **R092** | 300x 300 mm | **m** | **8,015** |
| **R093** | 400 x 300 mm | **m** | **8,674** |
| **R094** | 500 x 300 mm | **m** | **10,536** |
| **R095** | 675 x 300 mm | **m** | **12,743** |
| **R096** | 700 x 300 mm | **m** | **13,057** |
| | **Fire Detection System** | | |
| | Conventional Type Fire alarm control/indicating panel( (UL/LPCB approved, NFPA 72/EN 54 complied) ) c/w contacts/auxiliary contacts( control modules, monitoring modules) for shut down of A/C & ventilation equipment, connection of fire link/lift homing and all necessary accessories (including battery backup, design for the fire alarm control system, training & providing all passwords); | | |
| **R097** | Panel of 4 zones or less | **Nos** | **173,150** |
| **R098** | Panel of 5-8 zones | **Nos** | **251,700** |
| **R099** | Panel of 9-12 zones | **Nos** | **318,250** |
| **R100** | Panel of 12 zones or more | **Nos** | **398,225** |
| | Automatic addressable Type Fire alarm control/indicating panel( (UL/LPCB approved, NFPA 72/EN 54 complied) ) c/w contacts/auxiliary contacts( control modules, monitoring modules) for shut down of A/C & ventilation equipment, connection of fire link/lift homing and all necessary accessories (including battery backup, design for the fire alarm control system, training & providing all passwords) | | |
| **R101** | Panel of 50 points or less | **Nos** | **345,150** |
| **R102** | Panel of 51 points to 100 | **Nos** | **431,700** |
| **R103** | Panel of 101 points to 200 | **Nos** | **648,250** |
| **R104** | Panel of 201 or higher | **Nos** | **828,225** |
| | Analogue Addressable Type smoke detector with multiple sensitivity (adjustable at site) levels, programmable for timed automatic sensitivity selection with base, Junction box and other accessories as required. | | |
| **R105** | Ionization Type | **Nos** | **8,090** |
| **R106** | Optical Type (Photoelectric Type) | **Nos** | **8,990** |



This BSR is for construction works only

| Item Code | Item Description | Unit | Basic Rate 2020 |
|---|---|---|---|
| | Conventional Type smoke detector with multiple sensitivity (adjustable at site) levels, programmable for timed automatic sensitivity selection with base, Junction box and other accessories as required. | | |
| **R107** | Ionization Type | **Nos** | **7,490** |
| **R108** | Optical Type (Photoelectric Type) | **Nos** | **8,390** |
| | Analogue Addressable Type duct detector with multiple sensitivity (adjustable at site) levels, programmable for timed automatic sensitivity selection with base, Junction box and other accessories as required. | | |
| **R109** | Ionization Type | **Nos** | **8,890** |
| **R110** | Optical Type (Photoelectric Type) | **Nos** | **7,940** |
| | Conventional Type duct detector with multiple sensitivity (adjustable at site) levels, programmable for timed automatic sensitivity selection with base, Junction box and other accessories as required. | | |
| **R111** | Ionization Type | **Nos** | **9,090** |
| **R112** | Optical Type (Photoelectric Type) | **Nos** | **9,690** |
| | Analogue Addressable Type heat detector with standard base and fixing accessories. | | |
| **R113** | Rate-of-rise (ROR) Heat Detectors | **Nos** | **7,390** |
| **R114** | Fixed Temperature Heat Detectors | **Nos** | **7,490** |
| | Conventional Type heat detector with standard base and fixing accessories. | | |
| **R115** | Rate-of-rise (ROR) Heat Detectors | **Nos** | **7,390** |
| **R116** | Fixed Temperature Heat Detectors | **Nos** | **7,490** |
| **R117** | Automatic/manual fire alarm call points c/w re-programming work of existing addressable fire control panel, if necessary, and all necessary mounting accessories and connected to the fire alarm control panel | **Nos** | **15,280** |
| **R118** | Analogue Addressable Type Fault isolator module capable of monitoring shorted loop circuit and automatically restore communications when shorted conditions are corrected. | **Nos** | **9,140** |
| **R119** | Addressable Manual pull station having an integrally mounted addressable module that monitors and reports contact status. | **Nos** | **8,390** |
| **R120** | Emergency Exit Lights and Emergency Exit Signs with 3hrs battery back up and all necessary accessories. | **Nos** | **13,335** |
| **R121** | 2 x 2.5 sq. mm, fire resistance screened cable with PVC insulated copper wires confirming to specification with polycon rigid and flexible conduits in inside the walls, floor or ceiling. | **Nos** | **1,116** |
| **R122** | 2 x 1.5 sq. mm, fire resistance screened cable with PVC insulated copper wires confirming to specification with polycon rigid and flexible conduits in inside the walls, floor or ceiling. | **Nos** | **1,089** |

| Item Code | Item Description | Unit | Basic Rate 2020 |
|---|---|---|---|
| | **S-ELECTRICAL INSTALLATION** | | |
| | Recommended makes of Electrical Accessories<br>**MCCB:-** *Schneider, ABB, Terasaki, Siemens or equivalent.*<br>**MCB'S & RCCB'S:-** *Schneider , Siemens, Crabtree, Eaton, Hager, Moeller, Legrand, F & G (Austria) or equivalent.*<br><br>**Cable :-** *ACL, Kelani, Sierra or equivalent.*<br>**Ceiling Fan:-** *K.D.K., National-Japanese origins*<br>**Exhaust Fan:-** *K.D.K., National-Japanese origins*<br>**Switch & socket outlet :-** *Tenby, Clipsal, MK, Crabtree, PDL, Kevilton, Orange or Equivalent.*<br><br>**LED Fittings/ Tube:-** *The light should be good quality, Philips, DIMO, OSRAM or approved equivalent. Minimum efficacy at scotopic condition should be above 100 lumen/W Corelate colour temperature (CCT) should be above 4000K, (Cool White). Colour rendering index (CRI) should be above 80. Rated life time should be above 50,000 hrs.*<br>**Distribution Board:-** *Shall be in surface mount metal enclosure fabricated With Zinc coated sheet metal of gauge not less than 1.8 mm total enclosed, with hinged door with protective cover plate for terminals, finished with powder coating of approved colour and components as specified in the BOQ.*<br><br>**Energy Saving Bulbs:-** *CFL Builbs should be 5 stars*<br>Recommended Fabricators of Switch boards and Enclosures.<br>Elsteel<br>K.I.K. Lanka (Pvt) Ltd<br>Pubudu Engineering (pvt) Ltd<br>Richardsons Projects (pvt) Ltd<br>Bentota Power Generators (Pvt) Ltd<br>OS Project (Pvt) Ltd. (Orange)<br>Or similar product | | |
| | **In PVC conduit** | | |
| | Point wiring to be carried out with 2x1mm$^2$ PVC/PVC/CU + 2.5mm$^2$ PVC/CU earth cable terminated in a 3 terminal ceilingrose and sunk switch, wired in concealed conduit in wall and above ceiling to be supplied and installed to working order | | |
| **S001** | Lamp point wiring | **Nos.** | **2,726** |
| **S002** | Water tight lamp point wiring | **Nos.** | **2,770** |
| **S003** | Indoor Braacket lamp point wiring | **Nos.** | **2,715** |
| **S004** | Stair way lamp point wiring controlled by 2 No. two way switches | **Nos.** | **4,445** |
| **S005** | Ceiling fan point wiring complete with hook and sunk switch | **Nos.** | **3,307** |
| | wiring to be carried out with 2C,2.5mm2 PVC/PVC/CU + 2.5mm2 PVC/CU earth cable wired in concealed conduit in wall and above ceiling to be supplied and installed to working order | | |
| **S006** | 13 AMP switch socket outlet | **Nos.** | **4,276** |

| Item Code | Item Description | Unit | Basic Rate 2020 |
|---|---|---|---|
| **S007** | 15 AMP switch socket outlet | **Nos.** | **4,873** |
| **S008** | 15 AMP switch socket outlet c/w 20A DP Switch with Neon Indicator Lamp | **Nos.** | **6,758** |
| | **In PVC Casing** | | |
| | point wiring to be carried out with 2x1mm2 PVC/PVC/CU + 2.5mm2 PVC/CU earth cable terminated in a 3 terminal ceiling rose and sunk switch, wired with PVC casing on wall and on soffit to be supplied and installed to working order. | | |
| **S009** | Lamp point wiring | **Nos.** | **3,029** |
| **S010** | Water tight lamp point wiring | **Nos.** | **3,073** |
| **S011** | Indoor Bracket lamp point wiring | **Nos.** | **3,018** |
| **S012** | Stair way Lamp point wiring controlled by 2 No. two way switches. | **Nos.** | **4,983** |
| **S013** | Ceiling fan point wiring complete with fan hook and sunk switch. | **Nos.** | **3,610** |
| | Wiring to be carried out with 2C,2.5mm2 PVC/PVC/CU + 2.5mm2 PVC/CU earth cable wired in concealed conduit in wall and above ceiling to be supplied and installed to working order | | |
| **S014** | 13 AMP switch socket outlet (Radial Circuit) | **Nos.** | **4,566** |
| **S015** | 15 AMP switch socket outlet | **Nos.** | **5,268** |
| **S016** | 15 AMP switch socket outlet c/w 20A DP | **Nos.** | **7,480** |
| | **Distribution Boards** | | |
| | Supply, Wiring and Installation of distribution board in surface mount plastic enclosure with the undermentioned switch gears to working order. | | |
| **S017** | 6 way SP & N Distribution board complete with 30AMP 2P MCB and 40A 2P RCD(30mA) | **Nos.** | **9,549** |
| **S018** | 8 way SP & N Distribution board complete with 30AMP 2P MCB and 40A 2P RCD(30mA) | **Nos.** | **10,842** |
| **S019** | 10 way SP & N Distribution board complete with 30AMP 2P MCB and 40A 2P RCD(30mA) | **Nos.** | **13,034** |
| **S020** | 12 way SP & N Distribution board complete with 30AMP 2P MCB and 40A 2P RCD(30mA) | **Nos.** | **14,433** |
| **S021** | 14 way SP & N Distribution board complete with 30AMP 2P MCB and 40A 2P RCD(30mA) | **Nos.** | **16,742** |
| **S022** | 16 way SP & N Distribution board complete with 30AMP 2P MCB and 40A 2P RCD(30mA) | **Nos.** | **18,687** |
| **S023** | 6 way SP & N Distribution board complete with 60AMP 2P MCB and 60A 2P RCD(30mA) | **Nos.** | **13,801** |
| **S024** | 8 way SP & N Distribution board complete with 60AMP 2P MCB and 60A 2P RCD(30mA) | **Nos.** | **15,094** |
| **S025** | 10 way SP & N Distribution board complete with 60AMP 2P MCB and 60A 2P RCD(30mA) | **Nos.** | **17,392** |
| **S026** | 12 way SP & N Distribution board complete with 60AMP 2P MCB and 60A 2P RCD(30mA) | **Nos.** | **18,801** |
| **S027** | 14 way SP & N Distribution board complete with 60AMP 2P MCB and 60A 2P RCD(30mA) | **Nos.** | **21,647** |
| **S028** | 16 way SP & N Distribution board complete with 60AMP 2P MCB and 60A 2P RCD(30mA) | **Nos.** | **22,939** |

| Item Code | Item Description | Unit | Basic Rate 2020 |
|---|---|---|---|
| **S029** | Suppling and Installation of TP & N Distribution board complete with 60 A 4P MCB(10 kA) and 2 No. 32 A 3P MCB (10kA) in surface mount plastic enclosure. | **Nos.** | **17,572** |
| **S030** | Suppling and Installation of TP & N Distribution board complete with 60 A 4P MCCB (25 kA) and 4 No. 16 A 3P MCB(10 kA) in surface mount metal enclosure. | **Nos.** | **39,228** |
| **S031** | Suppling and Installation of TP & N Distribution board complete with 100 A 4P MCCB 925 kA) and 2 No. 30/60AMP 3P MCCB (kA) in surface mount metal enclosure. | **Nos.** | **59,927** |
| **S032** | Suppling and Installation of TP & N Distribution board complete with 125 A 4P MCCB (25 kA) and 4 No. 30/60AMP 3P MCCB (25 kA) in surface mount metal enclosure. | **Nos.** | **92,669** |
| **S033** | Suppling and Installation of 20-100AMP 4P MCCB in surface mount metal enclosure | **Nos.** | **20,922** |
| **S034** | Suppling and Installation of 30AMP 2P isolator complete with plastic enclosure. | **Nos.** | **3,094** |
| **S035** | Suppling and Installation of 60AMP 2P isolator complete with plastic enclosure. | **Nos.** | **3,367** |
| **S036** | Suppling and Installation of 30AMP 4P isolator complete with plastic enclosure. | **Nos.** | **5,581** |
| **S037** | Suppling and Installation of 60AMP 4P isolator complete with plastic enclosure. | **Nos.** | **6,248** |
| **S038** | Suppling and Installation of 40AMP 2P RCCB (30mA) complete plastic enclosure. | **Nos.** | **5,750** |
| **S039** | Suppling and Installation of 60AMP 2P RCCB (30mA) complete plastic enclosure. | **Nos.** | **8,114** |
| **S040** | Suppling and Installation of 40AMP 4P RCCB (30mA) complete plastic enclosure. | **Nos.** | **9,985** |
| **S041** | Suppling and Installation of 60AMP 4P RCCB (30mA) complete plastic enclosure. | **Nos.** | **12,561** |
| | **Cabling in conduits** | | |
| | Cable shall be PVC/PVC/CU unless other wise specified to be supplied and installed in conduit to working order. | | |
| **S042** | 2x1 sq. mm + 2.5 sq. mm E cable | **m** | **193** |
| **S043** | 2x2.5 sq. mm + 2.5 sq. mm E cable | **m** | **348** |
| **S044** | 2x4 sq. mm + 2.5 sq. mm E cable | **m** | **479** |
| **S045** | 2x6 sq. mm + 6 sq. mm E cable | **m** | **742** |
| **S046** | 2x10 sq. mm + 10 sq. mm E cable | **m** | **1,133** |
| **S047** | 2x16 sq. mm + 16 sq. mm E cable | **m** | **1,678** |
| **S048** | 2x25 sq. mm + 16 sq. mm E cable | **m** | **2,685** |
| **S049** | 4x2.5 sq. mm + 2.5 sq. mm E cable | **m** | **529** |
| **S050** | 4x4 sq. mm + 4 sq. mm E cable | **m** | **792** |
| **S051** | 4x6 sq. mm + 6 sq. mm E cable | **m** | **1,133** |
| **S052** | 4x10 sq. mm +10 sq. mm E cable | **m** | **1,808** |



This BSR is for construction works only

| Item Code | Item Description | Unit | Basic Rate 2020 |
|---|---|---|---|
| S053 | 4x16 sq. mm +16 sq. mm E cable | m | 2,529 |
| S054 | 4x25 sq. mm +16 sq. mm E cable | m | 3,894 |
| S055 | 4x35 sq. mm +16 sq. mm E cable | m | 5,059 |
| | **Unarmoured Cabling** | | |
| | Cable shall be Cu/PVC/PVC OR Cu/XLPE/PVC supplied and installed in conduit or presure pipe (type 1000) to working order. | | |
| S056 | 2C Cu/PVC/PVC 1.5 sq. mm + 2.5 sq. mm E cable | m | 475 |
| S057 | 2C Cu/PVC/PVC 2.5 sq. mm + 2.5 sq. mm E cable | m | 621 |
| S058 | 2C Cu/PVC/PVC 4 sq. mm + 2.5 sq. mm E cable | m | 1,092 |
| S059 | 2C Cu/PVC/PVC 6 sq. mm + 6 sq. mm E cable | m | 1,448 |
| S060 | 2C Cu/PVC/PVC 10 sq. mm + 10 sq. mm E cable | m | 1,947 |
| S061 | 2C Cu/PVC/PVC 16 sq. mm + 16 sq. mm E cable | m | 2,711 |
| S062 | 2C Cu/PVC/PVC 25 sq. mm + 16 sq. mm E cable | m | 3,422 |
| S063 | 4C Cu/PVC/PVC 10 sq. mm + 10 sq. mm E cable | m | 2,786 |
| S064 | 4C Cu/PVC/PVC 16sq. mm + 16 sq. mm E cable | m | 3,616 |
| S065 | 4C Cu/PVC/PVC 25 sq. mm + 16 sq. mm E cable | m | 4,615 |
| S066 | 4C Cu/XLPE/PVC 35 sq. mm + 16 sq. mm E cable | m | 5,477 |
| S067 | 4C Cu/XLPE/PVC 50 sq. mm + 25 sq. mm E cable | m | 7,518 |
| S068 | 4C Cu/XLPE/PVC 70 sq. mm + 35 sq. mm E cable | m | 10,642 |
| S069 | 4C Cu/XLPE/PVC 95 sq. mm + 50 sq. mm E cable | m | 14,167 |
| | **Armoured Cabling** | | |
| | Cable shall be Cu/XLPE/SWA/PVC (BS 5467 : 1997 600/1000V) supplied and installed in cable tile with necessary accessories & materials to working order. | | |
| S070 | 4C Cu/XLPE/SWA/PVC 25 sq. mm | m | 5,313 |
| S071 | 4C Cu/XLPE/SWA/PVC 35 sq. mm | m | 6,282 |
| S072 | 4C Cu/XLPE/SWA/PVC 50 sq. mm | m | 8,173 |
| S073 | 4C Cu/XLPE/SWA/PVC 70 sq. mm | m | 10,611 |
| S074 | 4C Cu/XLPE/SWA/PVC 95 sq. mm | m | 14,048 |
| S075 | 4C Cu/XLPE/SWA/PVC 120 sq. mm | m | 16,909 |
| S076 | 4C Cu/XLPE/SWA/PVC 150 sq. mm | m | 20,693 |
| S077 | 4C Cu/XLPE/SWA/PVC 185 sq. mm | m | 25,362 |
| | **Cabling in PVC Casing** | | |
| | Cable shall be PVC/PVC/CU unless other wise specified to be supplied and installed in PVC casing to working order. | | |
| S078 | 2x1 sq. mm + 2.5 sq. mm E cable | m | 243 |
| S079 | 2x2.5 sq. mm + 2.5 sq. mm E cable | m | 373 |
| S080 | 2x4 sq. mm + 2.5 sq. mm E cable | m | 590 |
| S081 | 2x6 sq. mm + 6 sq. mm E cable | m | 805 |
| S082 | 2x10 sq. mm +10 sq. mm E cable | m | 1,130 |
| S083 | 2x16 sq. mm +16 sq. mm E cable | m | 1,618 |
| S084 | 2x25 sq. mm +16 sq. mm E cable | m | 2,909 |



This BSR is for construction works only

| Item Code | Item Description | Unit | Basic Rate 2020 |
|---|---|---|---|
| **S085** | 4x2.5 sq. mm + 2.5 sq. mm E cable | **m** | **630** |
| **S086** | 4x4 sq. mm + 4 sq. mm E cable | **m** | **957** |
| **S087** | 4x6 sq. mm + 6 sq. mm E cable | **m** | **1,388** |
| **S088** | 4x10 sq. mm + 10 sq. mm E cable | **m** | **2,087** |
| **S089** | 4x16 sq. mm + 16 sq. mm E cable | **m** | **2,920** |
| **S090** | 4x25 sq. mm + 16 sq. mm E cable | **m** | **4,204** |
| **S091** | 4x35 sq. mm + 16 sq. mm E cable | **m** | **5,387** |
| | **Lightning Protection System** | | |
| **S092** | Supplying and Installation of earth Electrode c/w 50 mm dia. Of 2 LM to working order complete with forming of a gulley around the pipe. | **Nos.** | **4,455** |
| **S093** | Supplying and Installation of 16 mm dia.solid copper earth rod with inspection pit of 300mm x 300mm x 300mm | **Nos.** | **30,296** |
| **S094** | Supply and Installation of 25mm x 3mm Cu tape in Air termination system | **Nos.** | **2,083** |
| **S095** | Supply and Installation of 25mm x 3mm Cu tape in Down conductor system | **Nos.** | **2,179** |
| **S096** | Supply and Installation of test joint mounted in a yellow PVC enclosure | **Nos.** | **3,535** |
| **S097** | Supply and Installation of finial type air terminal with minimum 1000mm height and 12mm diameter | **Nos.** | **15,892** |
| | **Luminaire and Fixtures** | | |
| | Supplying and Installation of Luminaire and fixtures complete with all fixing accessories, G.I. Chains cup hook 2/3 core cable, conector suspension holder etc. to working order. | | |
| **S098** | Pendent Lamp C/W 250 mm dia. Conical plastic shade and 15W CFL bulb (Prime cost for plastic shade -Rs. 350) | **Nos.** | **1,349** |
| **S099** | Pendent Lamp C/W 200 mm dia. Glass globe and 15W CFL bulb (Prime cost for pendant lamp c/w 200mm dia. Glass globe -Rs.1650) | **Nos.** | **2,574** |
| **S100** | Indoor Bracket lamp C/W ornament shade and 15W CFL bulb (Prime cost for bracket lamp c/w ornament shade -Rs. 1850) | **Nos.** | **2,699** |
| **S101** | Water tight bracket lamp C/W Clear glass ornament shade and 15W CFL bulb(4 star rated) (Prime cost for water tight bracket lamp c/w ornament shade -Rs. 2750) | **Nos.** | **3,581** |
| **S102** | Recessed type, T8 LED tube light fitting 1200mm x 300mm complete with polished aluminium double parabolic louver and 2x18W LED tube. (Prime cost for complete lamp fitting set with all accessories -Rs. 6775) | **Nos.** | **7,570** |
| **S103** | Recessed type, T8 LED tube light fitting 1200mm x 600mm complete with polished aluminium double parabolic louver and 3x18W LED tube. (Prime cost for lamp fitting set with all accessories -Rs.10150) | **Nos.** | **11,029** |
| **S104** | Recessed type, T8 LED tube light fitting 600mm x 600mm complete with polished aluminium double parabolic louver and 4x9W LED tube. (Prime cost for lamp fitting set with all accessories -Rs. 8050) | **Nos.** | **8,877** |
| **S105** | Recessed type, T8 LED tube light fitting 600mm x 600mm complete with polished aluminium double parabolic louver and 3x9W LED tube. (Prime cost for lamp fitting set with all accessories -Rs.7150) | **Nos.** | **7,954** |
| **S106** | 1200mm battern type T8 LED tube light (1x18W tube) fitting.(Prime cost for lamp fitting set with all accessories -Rs. 2250) | **Nos.** | **2,773** |

| Item Code | Item Description | Unit | Basic Rate 2020 |
|---|---|---|---|
| **S107** | 1200mm battern type T8 LED tube light (2x18W tube) fitting. (Prime cost for lamp fitting set with all accessories -Rs. 3950) | **Nos.** | **4,728** |
| **S108** | 600mm battern type T8 LED tube light (1x9W tube) fitting. (Prime cost for lamp fitting set with all accessories -Rs. 1780) | **Nos.** | **2,498** |
| **S109** | 1200mm Suspension type T8 LED tube light complete with prismatic diffuser and (1x18W tube) (Prime cost for lamp fitting set with all accessories -Rs. 3250) | **Nos.** | **4,010** |
| **S110** | 600mm Suspension type T8 LED tube light complete with prismatic diffuser and (1x9W tube)(Prime cost for lamp fitting set with all accessories -Rs. 2500) | **Nos.** | **3,086** |
| **S111** | 1200mm Suspension type T8 LED tube light complete with prismatic diffuser and (2x18W tube) (Prime cost for lamp fitting set with all accessories -Rs. 4950) | **Nos.** | **5,597** |
| **S112** | Recessed type 6W LED panel light fitting (Prime cost for Recessed down light -Rs.775) | **Nos.** | **1,247** |
| **S113** | Recessed type12W LED panel light fitting (Prime cost for Recessed down light -Rs. 1200) | **Nos.** | **1,683** |
| **S114** | Recessed type 18W LED panel light fitting (Prime cost for Recessed down light -Rs. 1500) | **Nos.** | **1,991** |
| **S115** | Recessed mounted 6W Down light (Prime cost for Recessed down light -Rs. 1850) | **Nos.** | **2,363** |
| **S116** | Recessed mounted 12W Down light (Prime cost for Recessed down light -Rs. 2950) | **Nos.** | **3,490** |
| **S117** | Bulk head lamp water tight C/W 18W CFL bulb (4 star rated) (Prime cost for Recessed down light -Rs. 2250) | **Nos.** | **3,441** |
| **S118** | 10W IP 65 flood light | **Nos.** | **3,658** |
| **S119** | 20W IP 65 flood light | **Nos.** | **5,042** |
| **S120** | 50W IP 65 flood light | **Nos.** | **8,783** |
| **S121** | 100W IP 65 flood light | **Nos.** | **13,652** |
| | **Switch socket outlet** | | |
| | Switch socket outlet 5AMP/13Amp/15AMP to be supplied and installed | | |
| **S122** | 13 AMP switch socket outlet | **Nos.** | **1,182** |
| **S123** | 15 AMP switch socket outlet | **Nos.** | **1,214** |
| | **Supplying and fixing sunk switch** | | |
| | Supplying and fixing sunk switch complete with plastic sunk box to be supplied | | |
| **S124** | Supplying and fixing 1 gang sunk switch | **Nos.** | **535** |
| **S125** | Supplying and fixing 2 gang sunk switch | **Nos.** | **555** |
| **S126** | Supplying and fixing 3 gang sunk switch | **Nos.** | **782** |
| **S127** | Supplying and fixing 4 gang sunk switch | **Nos.** | **1,118** |
| **S128** | Supplying and fixing 5 gang sunk switch | **Nos.** | **1,346** |
| **S129** | Supplying and fixing fan regulator dimmer type | **Nos.** | **1,406** |
| **S130** | Supplying and fixing Ceiling fan regulator | **Nos.** | **1,678** |
| **S131** | Supplying and fixing 20 AMP DP switch with Neon indicator | **Nos.** | **2,312** |
| **S132** | Supplying and fixing sunk Bell push | **Nos.** | **656** |
| **S133** | Supplying and fixing Cell Bell Ding Dong type excluding wires | **Nos.** | **962** |

| Item Code | Item Description | Unit | Basic Rate 2020 |
|---|---|---|---|
| | **Fans** | | |
| **S134** | Supply & Installation of Ceiling fan 1400mm dia. Complete with 3 speed regulator (Excluding wiring) | **Nos.** | **9,236** |
| | **Exhaust Fans** | | |
| **S135** | Supply & Installation of 200mm dia. Exhaust fan with auto shutter (K.D.K or equvalent) (Excluding wiring) | **Nos.** | **5,188** |
| **S136** | Supply & Installation of 250mm dia. Exhaust fan with auto shutter (K.D.K or equvalent) (Excluding wiring) | **Nos.** | **8,108** |
| **S137** | Supply & Installation of 300mm dia. Exhaust fan with auto shutter (K.D.K or equvalent) (Excluding wiring) | **Nos.** | **8,865** |
| **S138** | Supply & Installation of 450mm dia. Exhaust fan with auto shutter (K.D.K or equvalent) (Excluding wiring) | **Nos.** | **10,002** |
| | **Wall Fans** | | |
| **S139** | Supply & Installation of wall fan 450mm dia. Complete with 3 speed regulator (Excluding wiring) | **Nos.** | **12,201** |
| | **Conduit Pipe** | | |
| | Supplying & installation of conduit pipe clipped in surface | | |
| **S140** | 18mm conduit pipe | **m** | **84** |
| **S141** | 20mm conduit pipe | **m** | **88** |
| **S142** | 25mm conduit pipe | **m** | **102** |
| **S143** | 30mm conduit pipe | **m** | **170** |
| **S144** | 40mm conduit pipe | **m** | **207** |
| **S145** | 50mm conduit pipe | **m** | **276** |
| | **PVC Casing** | | |
| | Supplying and Installation of PVC casing | | |
| **S146** | 10mmx20mm PVC Casing | **m** | **122** |
| **S147** | 14mmx24mm PVC Casing | **m** | **272** |
| **S148** | 16mmx40mm PVC Casing | **m** | **233** |
| **S149** | 25mmx40mm PVC Casing | **m** | **260** |
| **S150** | 50mmx25mm PVC Casing | **m** | **343** |
| **S151** | 50mmX50mm PVC Box Casing | **m** | **467** |
| **S152** | 50mmX75mm PVC Box Casing | **m** | **607** |
| **S153** | 100mmX50mm PVC Box Casing | **m** | **914** |
| **S154** | 100mmx27mm PVC Box Casing | **m** | **637** |
| | **Supply and Installation of main cables** | | |
| **S155** | 2x1 sq. mm Cu/PVC/PVC Cable | **m** | **135** |
| **S156** | 2 x 2.5 sq. mm Cu/PVC/PVC Cable | **m** | **281** |
| **S157** | 2 x 4 sq. mm Cu/PVC/PVC Cable | **m** | **401** |
| **S158** | 2 x 6 sq. mm Cu/PVC/PVC Cable | **m** | **551** |



This BSR is for construction works only

| Item Code | Item Description | Unit | Basic Rate 2020 |
|---|---|---|---|
| S159 | 2 x 10 sq. mm Cu/PVC/PVC Cable | m | 805 |
| S160 | 2 x 16 sq. mm Cu/PVC/PVC Cable | m | 1,186 |
| S162 | 2 x 35 sq. mm Cu/PVC/PVC Cable | m | 2,335 |
| | **Supply and Installation of Earth cables** | | |
| S163 | 2.5 sq. mm Cu/PVC Earth cable | m | 125 |
| S164 | 4 sq. mm Cu/PVC Earth cable | m | 207 |
| S165 | 6 sq. mm Cu/PVC Earth cable | m | 332 |
| S166 | 10 sq. mm Cu/PVC Earth cable | m | 507 |
| S167 | 16 sq. mm Cu/PVC Earth cable | m | 735 |
| S168 | 25 sq. mm Cu/PVC Earth cable | m | 1,142 |
| S169 | 35 sq. mm Cu/PVC Earth cable | m | 1,477 |
| S170 | 50 sq. mm Cu/PVC Earth cable | m | 1,888 |
| S171 | 70 sq. mm Cu/PVC Earth cable | m | 2,550 |
| S172 | 95 sq. mm Cu/PVC Earth cable | m | 3,251 |
| S173 | 120 sq. mm Cu/PVC Earth cable | m | 4,192 |
| | **SUPPLY & INSTALLATION OF DOL STARTER** | | |
| S174 | Single phase DOL starter for 5.5kW motor (without overload) | Nos. | 14,369 |
| S175 | Three phase DOL starter for 5.5kW motor (without overload) | Nos. | 47,732 |
| | **EXTRA LOW VOLTAGE SYSTEM** | | |
| S176 | Supply and installation of Cat6 Data Outlet for Data points including Cat6 cables, Cat6 Keystone Jacks, Single face plates, Sunk Box, PVC Conduits/Trunking, Floor Trunking and all other accessories to be supplied and installed to working order | Nos. | 6,815 |
| S177 | Supply and Laying of Solid Pure Copper CAT 6 Cable from a relevant Patch Panel to each Camera point | Nos. | 4,667 |
| S178 | MM OM3 6-Core Outdoor Armed Fiber Optic Cables supplied and installed in a trench including all required civil works and installation charges | Nos. | 2,706 |
| S179 | MM OM3 8-Core Outdoor Armed Fiber Optic Cables supplied and installed in a trench including all required civil works and installation charges | Nos. | 2,812 |
| S180 | MM OM3 12-Core Outdoor Armed Fiber Optic Cables supplied and installed in a trench including all required civil works and installation charges | Nos. | 3,024 |
| S181 | Supply and Installation of 12 Core Optic Fiber indoor MM 50/125 OM3 through securely fixed PVC Pipes and casings ( runs per floor Access switches, starting from Core switches) | Nos. | 2,574 |
| S182 | Supply and Installation of 8 Core Optic Fiber indoor MM 50/125 OM3 through securely fixed PVC Pipes and casings ( runs per floor Access switches, starting from Core switches) | Nos. | 2,107 |
| S183 | Supply and Installation of 6 Core Optic Fiber indoor MM 50/125 OM3 through securely fixed PVC Pipes and casings ( runs per floor Access switches, starting from Core switches) | Nos. | 1,746 |
| S184 | Supply and Laying of Solid Pure Copper CAT 6 Cable | Nos. | 1,190 |
| S185 | Supply and installation of fiber patch cords ( 1m ) | Nos. | 2,231 |

| Item Code | Item Description | Unit | Basic Rate 2020 |
|---|---|---|---|
| S186 | 0.5m Solid Pure Copper CAT 6 Slim Boot Patch Cords. | Nos. | 499 |
| S187 | 1m Solid Pure Copper CAT 6 Slim Boot Patch Cords. | Nos. | 604 |
| S188 | 3m Solid Pure Copper CAT 6 Slim Boot Patch Cords. | Nos. | 814 |
| S189 | Supply and Installation of 16U 19" wall mounting, glass door, fully loaded rack with the following accessories.<br>4 way power bar with 13A socket outlets. Thermostatically controlled 3 nos 100mmx100mm size 230Vac, cooling fan plate with finger guard, Vertical & Horizontal cable trays,Gland plates top & bottom, Fixed trays, UK Plug etc.( As per specifications ) | Nos. | 60,660 |
| S190 | Supply and Installation of 25U 19" wall mounting, glass door, fully loaded rack with the following accessories.<br>4 way power bar with 13A socket outlets. Thermostatically controlled 3 nos 100mmx100mm size 230Vac, cooling fan plate with finger guard, Vertical & Horizontal cable trays,Gland plates top & bottom, Fixed trays, UK Plug etc.( As per specifications ) | Nos. | 90,417 |
| S191 | Supply and installation of 12 Port POE 185W, Non blocking, Manageable Switch with 12 x RJ-45 10/100/1000 Mbps Gigabit Ethernet Ports, 2 No. SFP ports as uplinks ,SFP transceivers and any other connecting equipments for uplinks. having auto Crossover Function | Nos. | 279,030 |
| S192 | Supply and installation of 24 Port POE 370W, Non blocking, Manageable Switch with 24 x RJ-45 10/100/1000 Mbps Gigabit Ethernet Ports, 2 No. SFP ports as uplinks ,SFP transceivers and any other connecting equipments for uplinks. having auto Crossover Function | Nos. | 323,710 |
| S193 | Supply and installation of 48 Port POE 370W, Non blocking, Manageable Switch with 48 x RJ-45 10/100/1000 Mbps Gigabit Ethernet Ports, 2 No. SFP ports as uplinks ,SFP transceivers and any other connecting equipments for uplinks. having auto Crossover Function | Nos. | 510,090 |
| S194 | Supply and installation of 16 Port Unmanageable Switch with 16 x RJ-45 10/100/1000 Mbps Gigabit | Nos. | 28,150 |
| S195 | Supply and installation of 24 Port Unmanageable Switch with 24 x RJ-45 10/100/1000 Mbps Gigabit | Nos. | 41,410 |
| S196 | Supply and installation of 48 Port Unmanageable Switch with 48 x RJ-45 10/100/1000 Mbps Gigabit | Nos. | 104,810 |
| S197 | Supply and Installation of 12 port duplex SC port fiber Patch Panel | Nos. | 29,113 |
| S198 | Supply and Installation of 12 port Copper Patch Panel | Nos. | 7,250 |
| S199 | Supply and Installation of 24 port Copper Patch Panel | Nos. | 12,700 |
| S200 | Supply and Installation of 48 port Copper Patch Panel | Nos. | 21,420 |

| Item Code | Item Description | Unit | Basic Rate 2020 |
|---|---|---|---|
| | **T -FINISHERG & FLOORING** | | |
| | ***T1-Plasterer*** | | |
| | **Plastering *(walls)*** | | |
| **T001** | (15 mm) thick plastering to wall in **cement lime and sand** 1:1:5 finished semi rough with wooden float. | **$m^2$** | **714** |
| **T002** | (15 mm thick plastering to wall in cement lime and sand 1:1:5 finished smooth with lime putty floating. | **$m^2$** | **831** |
| **T003** | (15 mm)) thick plastering 1:5 **cement and sand** semi rough | **$m^2$** | **634** |
| | **Plastering *(beams, slab soffits)*** | | |
| **T004** | 10mm thick plastering to R.C.C. beams, slab soffit in cement and sand 1:3 including floating with lime putty. | **$m^2$** | **940** |
| **T005** | Cove moulding 62.5mm x 62.5mm in cement mortar 1:2 built in existing wall. | **m** | **337** |
| **T006** | Cresting with broken glass in cement mortar 1:4 on coping of boundary wall. | **m** | **378** |
| | **Moulding** | | |
| **T007** | Moulding 75mm x 12mm in walls in lime and cement mortar 1:1:4 only for replacements to match existing or to be "extra" over rate for plastering. | **m** | **358** |
| **T008** | Moulding 150mm x 25mm in walls in lime and cement mortar 1:1:4 only for replacements to match existing or to be "extra" over rate for plastering. | **m** | **536** |
| **T009** | Moulding 100mm x 50mm in cement and sand 1:2 built in existing wall. | **m** | **707** |
| **T010** | Flashing or plaster bands laid over tiles 100mm to 150mm wide on roof in cement and lime mortar 1:1:4. | **m** | **230** |
| **T011** | Letters embossed in plaster 20mm thick upto 150mm high in cement and sand 1:2 cement floated and painted complete. | **Nos** | **311** |
| **T012** | 16mm thick plastering to walls in **lime and sand** 2:5 including floating, finished smooth with lime putty. | **$m^2$** | **837** |
| **T013** | Pointing flush in cement 1:2 in surface cracks including raking out joints. | **m** | **153** |
| **T014** | Pointing, tuck, projected in cement 1:2 on brick masonry etc. | **$m^2$** | **1,284** |
| | **Rendering Cement** | | |
| **T015** | Rendering Cement 12mm; 1:2 above 9.29m2. | **$m^2$** | **672** |
| **T016** | Rendering, cement 12mm, 1:2 upto 9.29m2. | **$m^2$** | **772** |
| **T017** | Rendering, cement 12mm, 1:3 above 9.29m2. | **$m^2$** | **624** |
| **T018** | Rendering, cement 12mm 1:3 upto 9.29m2. | **$m^2$** | **724** |
| **T019** | Rendering, cement 20mm, 1:2 above 9.29 m2. | **$m^2$** | **933** |
| **T020** | Rendering, cement 20mm, 1:2 upto 9.29m2. | **$m^2$** | **1,065** |
| **T021** | Rendering, cement 20mm 1:3 above 9.29 m2 . | **$m^2$** | **877** |
| **T022** | Rendering, cement 20mm, 1:3 upto 9.29 m2. | **$m^2$** | **1,009** |
| | **Cement floating coat.** | | |
| **T023** | Rendering, cement, **floating coat**, using neat Cement and finished smooth with Carborandum Stone. | **$m^2$** | **150** |



This BSR is for construction works only

| Item Code | Item Description | Unit | Basic Rate 2020 |
|---|---|---|---|
| T024 | Rendering, cement, floating coat, using Red Cement finished smooth with Carborandum stone. | $m^2$ | 243 |
| T025 | Rendering, cement, floating coat, using brown or green cement finished smooth with Carborandum Stone. | $m^2$ | 204 |
| T026 | Rendering, cement, floating coat, using black cement finished smooth with Carborandum Stone. | $m^2$ | 239 |
| T027 | Rendering cement 20mm 1:2 with Pudlo, 2.25kg to 45kg, cement. | $m^2$ | 977 |
| | **Skirting in cement mortar** | | |
| T028 | Skirting in cement mortar 1:3, 12mm x 100mm projected or flushed with wall, and including forming groove. | m | 464 |
| T029 | Skirting in cement mortar 1:3, 12mm x100mm projected or flushed with wall finished with Red Cement floating, including forming groove. | m | 521 |
| | **Plastering *(Reveals)*** | | |
| T030 | Plastering external reveals 0mm - 100mm wide finished rough. | m | 540 |
| T031 | Plastering internal reveals 0mm - 100mm wide finished smooth. | m | 673 |
| | ***T2-PAVIOR*** | | |
| T032 | Expansion joints in brick floors, filling with bitumen and sand. | m | 90 |
| T033 | Expansion joints in concrete floors filling with bitumen and sand (to full depth of concrete and rendering).6mm tk and 100mm deep. | m | 171 |
| | **Floors, gravel** | | |
| T034 | Floors, gravel 100mm thick, spreading, watering and ramming. | $m^2$ | 192 |
| | **Floor tiles (Laying only)** | | |
| | Fixing tiles on floors with all specials, including raking plaster and bedding in cement mortar 1:3 pointed with tile grout to match the tiles. (Tiles supplied by the client or paid separately. | | |
| T035 | --Do-- for, tiles 200mm x 200mm in size. | $m^2$ | 1,610 |
| T036 | --Do-- for, tiles 300mm x 300mm in size. | $m^2$ | 1,604 |
| T037 | --Do-- for, tiles 400mm x 400mm in size. | $m^2$ | 1,527 |
| T038 | --Do-- for, tiles 600mm x 600mm in size. | $m^2$ | 1,432 |
| | **Floor tiles; (Gloss/Semi Gloss/Matt) - Vitreous Porcelain ( Homogenous/ Non Homogenous)-Local** | | |
| | Porcelain Homogenous/ Non Homogenous Vitreous, floor tiles with all specials supplying and fixing to floors including raking plaster and bedding in cement mortar 1:3 and pointed with tile grout to match the tiles. ( Rocell or equivalent brand) | | |
| T039 | '--Do-- for, 300mm x 300mm MATT floor tile<br>*Prime Cost of, 12"x12" MATT floor tile (Rocell or Equivalent)Prime Cost of, =226* | $m^2$ | 4,280 |
| T040 | '--Do-- for, 300mm x 300mm GLOSS floor tile<br>*Prime Cost of, 12"x12" GLOSS floor tile (Rocell or Equivalent)Prime Cost of, =196* | $m^2$ | 3,919 |

| Item Code | Item Description | Unit | Basic Rate 2020 |
|---|---|---|---|
| **T041** | --Do-- for, 300mm x 300mm SEMI GLOSS floor tile<br>*Prime Cost of, 12"x12" SEMI GLOSS floor tile (Rocell or Equivalent)Prime Cost of, =168* | **$m^2$** | **3,587** |
| **T042** | --Do-- for, 400mm x 400mm MATT floor tile<br>*Prime Cost of, 16"x16" MATT floor tile (Rocell or Equivalent)Prime Cost of, =396* | **$m^2$** | **4,200** |
| **T043** | --Do-- for, 450mm x 450mm MATT floor tile<br>*Prime Cost of, 18"x18" MATT floor tile (Rocell or Equivalent)Prime Cost of, =520* | **$m^2$** | **4,303** |
| **T044** | --Do-- for, 500mm x 500mm GLOSS floor tile<br>*Prime Cost of, 20"x20" GLOSS floor tile (Rocell or Equivalent)Prime Cost of, =688* | **$m^2$** | **4,431** |
| **T045** | --Do-- for, 600mm x 300mm MATT floor tile<br>*Prime Cost of, 24"x12" MATT floor tile (Rocell or Equivalent)Prime Cost of, =607* | **$m^2$** | **5,120** |
| **T046** | --Do-- for, 600mm x 300mm GLOSS floor tile<br>*Prime Cost of, 24"x12" MATT floor tile (Rocell or Equivalent)Prime Cost of, =607* | **$m^2$** | **4,999** |
| **T047** | --Do-- for, 600mm x 400mm MATT floor tile<br>*Prime Cost of, 24"x16" MATT floor tile (Rocell or Equivalent)Prime Cost of, =730* | **$m^2$** | **4,783** |
| **T048** | --Do-- for, 600mm x 600mm POLISH floor tile<br>*Prime Cost of, 24"x24" POLISH floor tile (Rocell or Equivalent)Prime Cost of, =1470* | **$m^2$** | **5,827** |
| **T049** | --Do-- for, 600mm x 600mm MATT floor tile<br>*Prime Cost of, 24"x24" MATT floor tile (Rocell or Equivalent)Prime Cost of, =1302* | **$m^2$** | **5,324** |
| **T050** | --Do-- for, 900mm x450mm MATT floor tile<br>*Prime Cost of, 36"x18" MATT floor tile (Rocell or Equivalent)Prime Cost of, =1292* | **$m^2$** | **4,988** |
| | **Floor tiles- Rustic Type ( Homogenous)-Local** | | |
| | Floor tiles- Rustic Type ( Homogenous), with all specials supplying and fixing to floors including raking plaster and bedding in cement mortar 1:3 and pointed with tile grout to match the tiles. ( Rocell or equivalent brand) | | |
| **T051** | --Do-- for, 300mm x 300mm in size.<br>*Prime Cost of, Tiles 12"x12" Rustic Type ( Homogenius) ( Rocell )Prime Cost of, =228* | **$m^2$** | **4,304** |
| **T052** | --Do-- for, 400mm x 400mm in size.<br>*Prime Cost of, Tiles 16" x 16"Rustic Type ( Homogenius) ( Rocell )Prime Cost of, =372* | **$m^2$** | **4,038** |

| Item Code | Item Description | Unit | Basic Rate 2020 |
|---|---|---|---|
| | **Tile Skirting** | | |
| **T053** | Vitreous ceramic floor tiles Skirting 12"x4" supplying and fixing to bottom line of wall including raking plaster bedding with cement mortar 1:3 and pointed with tile grout to match the tiles. (Quality approved by the Engineer.)<br>*Prime Cost of, Tiles 16" x 16"Rustic Type ( Homogenius) ( Rocell )Prime Cost of, =372* | **m** | **679** |
| | **Terrazzo tile flooring** | | |
| **T054** | Terrazzo tile flooring supplying and laying. | **$m^2$** | **3,353** |
| **T055** | Terrazzo, wall lining with precast walling slabs 37.5mm thick supplying and fixing to complete. | **$m^2$** | **3,277** |
| | **Wall tiles -glazed ( Approved Quality)** | | |
| **T056** | Tiles, glazed with all specials, supplying and fixing to walls including raking plaster and backing in cement mortar 1:3. for available tiles (Tiles supplied by the client or paid separately.) | **$m^2$** | **1,549** |
| | **Wall tiles -*Local*** | | |
| **T057** | Boarder tiles glazed colour 300mm X 75mm, with decorative patterns , supplying and fixing to walls including raking plaster backing in cement mortar 1:3 and pointed with tile grout to match the tiles.<br>*Prime Cost of, Boarder tiles glazed colour 12 "x 3" with decorative patternsPrime Cost of, =242* | **m** | **987** |
| **T058** | Boarder tiles glazed colour 300mm X 75mm, with decorative patterns , supplying and fixing to walls including raking plaster backing in cement mortar 1:3 and pointed with tile grout to match the tiles.<br>*Prime Cost of, Boarder tiles glazed colour 12 "x 3" with decorative patterns (extreme design)Prime Cost of, =341* | **m** | **1,344** |
| | **Granite flooring-*Local*** | | |
| **T059** | Granite floor tiles 300mm x 300mm x 12mm (Local) supplying and fixing to floors including raking plaster bedding with cement mortar 1:3.<br>*Prime Cost of, Granite floor tiles 12" x 12"x ½" (Local, Range 1)Prime Cost of, =919* | **$m^2$** | **11,973** |
| **T060** | Granite floor tiles 600mm x 300mm x 20mm (Local) supplying and fixing to floors including raking plaster bedding with cement mortar 1:3.<br>*Prime Cost of, Granite floor tiles 12" x 12"x ½" (Local, Range 1)Prime Cost of, =919* | **$m^2$** | **17,062** |
| **T061** | Labour cost for fixing 300mm x 100mm x 12mm Granite skirting to bottom line of walls including cutting ,rounding & Forming edges polishing etc. | **m** | **518** |
| | **Glass block** | | |
| **T062** | Glass block 200mm x 200mm with all specials supplying and fixing to walls including raking plaster and bedding in cement mortar 1:3. | **$m^2$** | **13,792** |

| Item Code | Item Description | Unit | Basic Rate 2020 |
|---|---|---|---|
| | **Vinyl Sheet Flooring** | | |
| **T063** | Supplying and laying **2mm thick** Vinyl Flooring with necessary adhesive etc. (Mipolam 150 or equivalent) (Upto 14 m2 only) | **$m^2$** | **4,575** |
| | **Vinyl Tile** | | |
| **T064** | Supplying and laying **2mm thick** Vinyl tile with necessary adhesive etc. (Mactile - Gerflor or equivalent) (Upto 14m2 only) | **$m^2$** | **3,175** |
| | **Loop pile carpeting** | | |
| **T065** | Supplying and laying Loop pile carpeting with 5mm thick with Mcfoam under layer , firmly bonded to the existing floor. Carpet having primary & Secondary backings, namely polypropylene & Classic back respectively. And having the minimum pile weight of 20 Oz-USA per sq. yard. & loop density of 6,100 Oz/Cu.yard. (Neyland II or equivalent) (Upto 14m2 only) | **$m^2$** | **1,722** |
| | **Cut pile carpeting** | | |
| **T066** | Supplying and laying 1/8 gauged, Wide Open Cut pile carpeting (USA or equivalent) with 5mm thick with Mac Form under layer , firmly bonded to the existing floor. Carpet having primary & Secondary backings, namely woven polypropylene & Classic back polypropylene, respectively. And having the minimum pile weight of 30 Oz per sq. yard. & loop density of 5320 Oz/Cu.yard. (Upto 14m2 only) | **$m^2$** | **3,272** |
| | **Interlocking paving** | | |
| **T067** | Supplying and Laying 80mm thick "Uni" type Coloured interlocking paving blocks having Compressive Strength of 40N/mm2, layed on plain improved sub surface. Rate inclusive for Quarry dust bedding (Upto 14m2 only) | **$m^2$** | **3,965** |
| **T068** | Supplying and Laying 80mm thick "Uni" type Natural cement colour interlocking paving blocks having Compressive Strength of 40N/mm2, layed on plain improved sub surface. Rate inclusive for Quarry dust bedding. (Upto 14m2 only) | **$m^2$** | **3,722** |
| | **Paving tile Slabs** | | |
| **T069** | Supplying and Laying 300 x300 x50mm thick **Non Reinforced**, Natural cement colour, Concrete paving Slab, layed on plain improved sub surface. Rate inclusive for Quarry dust bedding. (Upto 14m2 only) | **$m^2$** | **2,559** |
| **T070** | Supplying and Laying 300 x300 x50mm thick **Reinforced**, Natural cement colour, Concrete paving Slab, layed on plain improved sub surface. Rate inclusive for Quarry dust bedding. (Upto 14m2 only) | **$m^2$** | **3,527** |

| Item Code | Item Description | Unit | Basic Rate 2020 |
|---|---|---|---|
| | **U-GLAZER** | | |
| **U001** | Glass panes fixing with (Group 6 category A) timber beadings (Glass available) | **$m^2$** | **1,955** |
| **U002** | Glass panes 3 mm clear supplying and fixing with (Group 6 category A) timber beadings. | **$m^2$** | **2,761** |
| **U003** | Glass panes 5 mm clear, supplying and fixing with Teak Beadings. | **$m^2$** | **3,223** |
| **U004** | Glass panes 5 mm pinhead or obscure supplying and fixing with (Group 6 category A) timber beadings. | **$m^2$** | **3,511** |
| **U005** | Glass panes 3 mm pinhead or obscure supplying and fixing with (Group 6 category A) timber beadings. | **$m^2$** | **2,415** |
| **U006** | Paint removing from painted glass panes with Caustic Soda Solution or other paint remover. | **$m^2$** | **527** |



This BSR is for constuction works only

| Item Code | Item Description | Unit | Basic Rate 2020 |
|---|---|---|---|
| | **V-PAINTING & DECORATING** | | |
| **V001** | **Walls, scraped to original plaster**, sand papering and lime putting cracks and defects, preparing surface for Distemper, snowcem, paint or similar application. | $m^2$ | **143** |
| **V002** | Walls, scraping and removing soot and levelling internally in Kitchen (extra over colour washing) | $m^2$ | **40** |
| | **Total coat / Skim coat** | | |
| **V003** | Applying **Total coat** joint compound and wall filler two coats, finished smooth with sand papering, and prepare for colour washing. | $m^2$ | **623** |
| **V004** | Applying **Skim Coat** compound on walls or sofit two coats, finished smooth with sand papering, and prepare for colour washing. | $m^2$ | **411** |
| | **Cement washing to walls** | | |
| **V005** | Cement washing to walls of single storeyed buildings, 1 coat, patching and preparing surface. | $m^2$ | **42** |
| **V006** | Cement washing to walls of single storeyed buildings, 2 coat, patching and preparing surface. | $m^2$ | **72** |
| **V007** | Cement washing externally to walls of building with upper floors, 1 coat. | $m^2$ | **54** |
| | **White or colour washing walls** | | |
| **V008** | White or **colour washing walls** of single storeyed buildings 1 coat, including patching up and preparing surface. | $m^2$ | **43** |
| **V009** | White or colour washing walls of single storeyed buildings 2 coats, including patching up and preparing surface. | $m^2$ | **75** |
| **V010** | White or Colour washing external walls of two storeyed buildings, 1 coat. | $m^2$ | **50** |
| **V011** | White or Colour washing external walls in buildings, of more than 2 storeys, 1 coat. | $m^2$ | **57** |
| **V012** | White or Colour washing external walls in Two storeyed buildings, 2 coats. | $m^2$ | **89** |
| **V013** | White or Colour washing external walls in building with more than 2 storeys, 2 coats. | $m^2$ | **96** |
| | **Snowcem paint** | | |
| **V014** | Painting walls with snowcem or equivalent cement paint, 2 coats to new work. | $m^2$ | **378** |
| | **Alkali resisting primer** | | |
| **V015** | Painting walls with alkali resisting primer where necessary. | $m^2$ | **237** |
| | **Elastometic filler Primer** | | |
| **V016** | Painting walls with one coat of Elastometic filler Primer where necessary. | $m^2$ | **182** |
| | **Alkali resisting water Proofing sealer** | | |
| **V017** | Painting walls with one coat of Alkali resisting water Proofing sealer where necessary. | $m^2$ | **217** |
| | **Anti-fungus paint** | | |
| **V018** | Applying **Anti-fungus paint** to all exposed surfaces on walls already prepared. | $m^2$ | **803** |
| | **Silicone masonry water repellent paint** | | |
| **V019** | Painting Walls with one coat of Silicone masonry water repellent paint. | $m^2$ | **149** |
| | **Bathroom paint** | | |
| **V020** | Painting Walls with one coat of Bathroom paint. | $m^2$ | **197** |

| Item Code | Item Description | Unit | Basic Rate 2020 |
|---|---|---|---|
| | **Emulsion paint** | | |
| **V021** | Painting Walls with one coat of emulsion paint. (new work or after preparation of old wall) | **$m^2$** | **179** |
| **V022** | Painting walls with two coats of emulsion paint. (new work or after preparation of old wall) | **$m^2$** | **326** |
| | **Painting weather shied (External walls) on New work** | | |
| **V023** | Painting external walls with **One coat** of **weather shied paint**. (On New work or prepared old work). | **$m^2$** | **307** |
| **V024** | Painting external walls with **Two coats** of **weather shied** paint. (On New work or prepared old work). | **$m^2$** | **576** |
| | **Acrylic Emulsion (Exterior paint)** | | |
| **V025** | Painting external walls with two coats of Acrylic Emulsion paint resist against algae, fungus and scrubs. | **$m^2$** | **414** |
| | **Painting asbestos sheet roof** | | |
| **V026** | Painting over the asbestos sheet roof with coats of roof shield paint. | **$m^2$** | **383** |
| **V027** | Painting under side of asbestos roofing sheet with one coats of emulsion paint | **$m^2$** | **251** |
| **V028** | Painting under side of asbestos roofing sheet with two coats of emulsion paint | **$m^2$** | **380** |
| **V029** | Painting under side of asbestos roofing sheet with one coat of primer after preparing surface | **$m^2$** | **394** |
| | **Floor Painting** | | |
| **V030** | Painting floors with **One coat** of quick drying **Floor paint** including washing, cleaning and smoothing down the surface. | **$m^2$** | **288** |
| **V031** | Painting floors with **Two coats** of quick drying **Floor paint** including washing, cleaning and smoothing down the surface. | **$m^2$** | **558** |
| | **Anticorrosive paint** | | |
| **V032** | Painting steelwork, 1 coat with anticorrosive paint including removing scale and wire brushing. | **$m^2$** | **214** |
| **V033** | Painting steelwork, 2 coats, with anticorrosive paint including removing scale and wire brushing. | **$m^2$** | **392** |
| | **Painting on GI Surface** | | |
| **V034** | Painting new galvanized iron GI Adhesion Promoter one coat and one coat of Dulux metal primer zink chromate or duco oil primer or equivalent including washing surface with water after manufactures specification. | **$m^2$** | **403** |
| | **Aluminium paint** | | |
| **V035** | Painting, aluminium paint, 1 coat on metal surfaces. | **$m^2$** | **181** |
| **V036** | Aluminium paint, one coat, along 50mm thick band. | **m** | **39** |
| **V037** | Aluminium paint, two coat, along 50mm thick band. | **m** | **70** |
| | **Enamel paint** | | |
| **V038** | Painting one coat of Enamel paint, including washing and cleaning the surface. | **$m^2$** | **231** |
| **V039** | Painting two coat of Enamel paint, including washing and cleaning the surface. | **$m^2$** | **429** |
| | **Removal of Paint from timber.** | | |
| **V040** | Paint removed entirely with blow lamp to bare timber. | **$m^2$** | **273** |
| **V041** | Painting G.I pipes 12mm to 20mm with approved paint, 2 coats. | **m** | **71** |
| | **Wood preservative** | | |
| **V042** | Wood preservative, (clear) applied to woodwork one coat (old work) | **$m^2$** | **111** |

| Item Code | Item Description | Unit | Basic Rate 2020 |
|---|---|---|---|
| V043 | Wood preservative, (clear) applied to woodwork two coats (New work) | $m^2$ | 210 |
| | **Enamel paint with Wood primer Under coat** | | |
| V044 | Painting new woodwork, with primer, undercoat and 2 coats of enamel paint. | $m^2$ | 716 |
| V045 | Painting new woodwork with approved primer, one coat. | $m^2$ | 240 |
| | **Polishing wood work with Wax** | | |
| V046 | **Wax polishing wood work** including thoroughly sand papering surface in new work only of permanent fixtures. | $m^2$ | 589 |
| | **Painting with Wood sheen** | | |
| V047 | Painting with **Wood sheen** paint including washing cleaning and smoothing down surface, **One coat**. | $m^2$ | 235 |
| V048 | Painting with wood sheen paint including washing cleaning and smoothing down surface, T**wo coats**. | $m^2$ | 400 |
| | **Polyurethane Varnishing** | | |
| V049 | Varnishing with polyurethane varnish after washing down and sand papering, 1 coat. | $m^2$ | 302 |
| V050 | Varnishing with polyurethane varnish after washing down and sand papering, 2 coats. | $m^2$ | 499 |
| | **polyurethane varnish-Matt** | | |
| V051 | Varnishing with polyurethane varnish after washing down and sand papering, 2 coats. | $m^2$ | 509 |
| | **Removing Varnish** | | |
| V052 | Varnishing, removing entirely to bare timber and preparing surface. | $m^2$ | 348 |
| | **Painting with Sanding sealer / Woof finish** | | |
| V053 | Applying new woodwork with two coats of **Sanding sealer** and two coats of wood finish | $m^2$ | 634 |
| V054 | Applying **wood finish**, one coat, including washing, cleaning and smoothing down surface. | $m^2$ | 261 |
| V055 | Applying **wood finish**, one coat, including two coats of sanding sealer after washing, cleaning and smoothing down surface. | $m^2$ | 728 |
| | **Painting with Perque varnish** | | |
| V056 | Cutting, levelling ,polishing and applying two coats of **Perque varnish** for an existing timber base floor. | $m^2$ | 1,328 |
| V057 | Applying masonry sealer for walls one coat. | $m^2$ | 227 |
| | **Painting Letters on (Board / Wall)** | | |
| V058 | Lettering 25mm to 37.5mm painted in Sinhalese, English or Tamil, including painting background. | Nos | 57 |
| V059 | Lettering 50mm to 75mm painted in Sinhalese, English or Tamil, including painting background. | Nos | 190 |
| V060 | Lettering 100mm to 125mm painted in Sinhalese, English or Tamil, including painting background. | Nos | 102 |

| Item Code | Item Description | Unit | Basic Rate 2020 |
|---|---|---|---|
| | **W-DRAINAGE SYSTEMS** | | |
| | **Wire dome (Steel)** | | |
| **W001** | Wire domes for 63mm pipes supplying and fixing. | **Nos** | **318** |
| **W002** | Wire domes for 110mm pipes supplying and fixing. | **Nos** | **371** |
| | **Wire dome (PVC)** | | |
| **W003** | Supplying & fixing PVC wire dome for 2"(50mm) dia. P.V.C drainage pipes. | **Nos** | **250** |
| **W004** | Supplying & fixing PVC wire dome for 4" (100mm)dia. P.V.C drainage pipes. | **Nos** | **302** |
| | **Drainage Fittings 4" (110mm) dia-(Local make)** | | |
| **W005** | Supplying & fixing 110mm dia. P.V.C plain socket (Local make) | **Nos** | **950** |
| **W006** | Supplying & fixing 110mm dia. P.V.C drainage elbow with single Door, approved quality with rubber ring joint.(Locally made) | **Nos** | **1,223** |
| **W007** | Supplying & fixing 110mm dia. P.V.C drainage bend 45 degree. (S-Lon or Equivalent.) | **Nos** | **943** |
| **W008** | Supplying & fixing 110mm dia. P.V.C drainage bend 45 degree ,with single Door (S-Lon or Equivalent.) | **Nos** | **1,093** |
| **W009** | Supplying & fixing 110mm dia. P.V.C drainage bend 89 degree. (S-Lon or Equivalent.) | **Nos** | **863** |
| **W010** | Supplying & fixing 110mm dia. P.V.C drainage bend 89 degree. With single Door (S-Lon or Equivalent.) | **Nos** | **1,523** |
| **W011** | Supplying & fixing 110mm dia. P.V.C drainage Tee. (S-Lon or Equivalent.) | **Nos** | **1,213** |
| **W012** | Supplying & fixing 110mm dia. P.V.C drainage Swept Tee. (S-Lon or Equivalent.) | **Nos** | **1,323** |
| **W013** | Supplying & fixing 110mm dia. P.V.C drainage Tee. with single Door (S-Lon or Equivalent.) | **Nos** | **1,413** |
| **W014** | Supplying & fixing 110mm dia. P.V.C drainage Swept Tee. with single Door (S-Lon or Equivalent.) | **Nos** | **1,543** |
| **W015** | Supplying & fixing 110mm dia. P.V.C drainage "Y" junction (S-Lon or Equivalent.) | **Nos** | **1,363** |
| **W016** | Supplying & fixing 110mm dia. P.V.C drainage "Y" junction with single Door (S-Lon or Equivalent.) | **Nos** | **1,603** |
| | **Drainage Fittings 2" (63mm) dia.** | | |
| **W017** | Supplying & fixing 63mm dia. P.V.C drainage bend 45 degree. (S-Lon or Equivalent.) | **Nos** | **563** |
| **W018** | Supplying & fixing 63mm dia. P.V.C drainage bend 45 degree, with single Door (S-Lon or Equivalent.) | **Nos** | **653** |
| **W019** | Supplying & fixing 63mm dia. P.V.C drainage bend 89 degree. (S-Lon or Equivalent.) | **Nos** | **609** |
| **W020** | Supplying & fixing 63mm dia. P.V.C drainage bend 89 degree, with single Door (S-Lon or Equivalent.) | **Nos** | **1,284** |
| **W021** | Supplying & fixing 63mm dia. P.V.C drainage Tee. (S-Lon or Equivalent.) | **Nos** | **723** |
| **W022** | Supplying & fixing 63mm dia. P.V.C drainage Tee. with single Door (S-Lon or Equivalent.) | **Nos** | **883** |



This BSR is for construction works only

| Item Code | Item Description | Unit | Basic Rate 2020 |
|---|---|---|---|
| **W023** | Supplying & fixing 63mm dia. P.V.C drainage "Y" junction (S-Lon or Equivalent.) | **Nos** | **728** |
| **W024** | Supplying & fixing 63mm dia. P.V.C drainage "Y" junction with single Door (S-Lon or Equivalent.) | **Nos** | **903** |
| | **Drainage Fittings 1½"or (50mm) dia** | | |
| **W025** | Supplying & fixing 50mm dia. P.V.C drainage bend 45 degree. (S-Lon or Equivalent.) | **Nos** | **533** |
| **W026** | Supplying & fixing 50mm dia. P.V.C drainage bend 45 degree with single Door (S-Lon or Equivalent.) | **Nos** | **603** |
| **W027** | Supplying & fixing 50mm dia. P.V.C drainage bend 89 degree. (S-Lon or Equivalent.) | **Nos** | **538** |
| **W028** | Supplying & fixing 50mm dia. P.V.C drainage bend 89 degree, with single Door (S-Lon or Equivalent.) | **Nos** | **603** |
| **W029** | Supplying & fixing 50mm dia. P.V.C drainage Tee. (S-Lon or Equivalent.) | **Nos** | **663** |
| **W030** | Supplying & fixing 50mm dia. P.V.C drainage Swept Tee. (S-Lon or Equivalent.) | **Nos** | **843** |
| **W031** | Supplying & fixing 50mm dia. P.V.C drainage Tee. with single Door (S-Lon or Equivalent.) | **Nos** | **773** |
| **W032** | Supplying & fixing 50mm dia. P.V.C drainage Swept Tee. with single Door (S-Lon or Equivalent.) | **Nos** | **873** |
| **W033** | Supplying & fixing 50mm dia. P.V.C drainage "Y" junction (S-Lon or Equivalent.) | **Nos** | **703** |
| **W034** | Supplying & fixing 50mm dia. P.V.C drainage "Y" junction with single Door (S-Lon or Equivalent.) | **Nos** | **778** |
| | **Drain Pipes P.V.C, 4" or (110mm)dia, ($PN_T9$)- lay in Trenches** | | |
| **W035** | Drains, P.V.C, 110mm dia: ($PN_T9$) laying on cement concrete 150mm thick bedding up to 600mm depth of invert including excavation, back filling and cement concrete hunching 1:3:6(25mm). | **m** | **3,369** |
| **W036** | Drains P.V.C, 110mm dia. ($PN_T9$) laying on cement concrete 150mm thick bedding over 600mm. up to 1200mm. depth of invert including excavation back filling and cement concrete hunching 1:3:6(25mm). | **m** | **3,631** |
| **W037** | Drains P.V.C, 110mm dia. ($PN_T9$) laying on cement concrete 150mm thick bedding over 1200mm. up to 1800mm. depth of invert including excavation back filling and cement concrete hunching 1:3:6(25mm). | **m** | **4,415** |
| | **Drain Pipes P.V.C, 6" or (160mm)dia, ($PN_T9$)- lay in Trenches** | | |
| **W038** | Drains PVC, 160mm dia. ($PN_T9$) laying on cement concrete 150mm thick bedding up to 600mm. depth of invert including excavation , backfilling and cement concrete hunching 1:3:6 (25mm). | **m** | **4,874** |
| **W039** | Drains PVC, 160mm dia.( $PN_T9$ ) laying on cement concrete 150mm thick bedding over 600mm up to 1200mm depth of invert including excavation backfilling and cement concrete hunching 1:3:6 (25mm ). | **m** | **5,146** |
| **W040** | Drains PVC, 160mm dia.( $PN_T9$ ) laying on cement concrete 150mm thick bedding 1200mm up to 1800mm depth of invert including excavation backfilling and cement concrete hunching 1:3:6 (25mm) . | **m** | **5,920** |



This BSR is for construction works only

| Item Code | Item Description | Unit | Basic Rate 2020 |
|---|---|---|---|
| | **Drain Pipes P.V.C, 12" or (315mm)dia, ($PN_T9$)** | | |
| **W041** | Drains PVC, 315mm dia.( $PN_T9$ ) laying on cement concrete 150mm thick bedding over 600mm up to 1200mm depth of invert including excavation backfilling and cement concrete hunching 1:3:6 (25mm ). | **m** | **14,114** |

| Item Code | Item Description | Unit | Basic Rate 2020 |
|---|---|---|---|
| | **X-EXTERNAL WORKS** | | |
| | **Fencing** | | |
| X001 | Fence barbed wire, 12 1/2 gauge, 4 points, 75mm apart, supplying & fixing on existing timber posts with G.I staples. | m | 39 |
| X002 | Fence, Barbed wire 12 1/2 gauge, 4 points, 75mm apart, supplying & fixing on existing concrete posts with available hook bolts. | m | 42 |
| X003 | Fence posts or struts, Milla, Na, Palu or Satin 100mm to 150mm average dia. supplying and fixing in ground complete, inclusive of sharpening and tarring. | m | 734 |
| X004 | Intermediate fence posts or struts, cement concrete 1: 1½ :3 (20mm) reinforced with 4 Nos. 6mm (1/4")dia. M.S rods, 1700mm high square section 100mm to 150mm supplying and fixing complete as per drawing No. 68 of 22.07.1936. | Nos | 1,860 |
| X005 | Intermediate fence posts or struts, cement concrete 1: 1½ :3 (20mm) reinforced with 4 Nos. 6mm (1/4") dia. M.S rods, 1700mm high square section 100mm to 150mm supplying and fixing complete as per drawing No. 68 of 22.07.1936. | Nos | 2,170 |
| X006 | End post and strut for Type barbed wire fence supplying and fixing complete in cement concrete as per drawing No. 68 of 22.07.1936. | Nos | 10,546 |
| X007 | Fence, bared wire, 5 strands, 12 1/2 B.W.G with 4 points at 75mm centers and R.C. posts (1:2:4) 20mm metal, reinforced with 4 Nos. 6mm rods with No. 14 B.W.G stirrups at 200mm centers. Post to be fixed at 2400mm centers including excavation, cement concrete foundation 1:3:6 (40mm) metal to corner posts and struts, and straining bolts. Struts to be reinforced with 4 Nos. 10mm roads and corner posts with 4 Nos. 12mm roads. | m | 1,421 |
| X008 | Straining Bolts, 450mm long 12mm dia. making and fixing (approx.). | Nos | 965 |
| X009 | Stoneware pipes, 100mm dia, over fume cupboards, supplying and fixing along wall with iron brackets and plugs. | m | 2,013 |
| | **Chain link fencing** | | |
| X010 | Supplying and fixing 50mm dia. heavy duty GI pipe uprights for receiving chain link fence. Rate to include for painting one coat of anticorrosive and two coats of enamel paint and welding 150mmx150mmx6mm thick MS plate to bottom of pipe and fixing fiberglass pipe cap 50mm dia.(Rate exclude cement concrete base & Excavation.) | m | 2,651 |
| X011 | Supplying and fixing 50mmx50mm gauge 10 , 1.5m high (gauge 10), galvanized and PVC coated chain link fence . Fixed to existing GI post and including horizontal bracing with 16mmx 6mm MS flat iron with GI J bolts and washers , PVC coated tieing wires etc., | $m^2$ | 1,734 |
| X012 | Supplying and welding 37.5mmx37.5mmx6mm MS angle iron horizontal bracing to existing GI pipe posts. Rate to include for painting one coat of anticorrosive paint and two coats of enamel paint. | m | 765 |
| X013 | Fabricating and fixing of MS grills with 25mmx 6mm flat iron frame and 6mm dia.MS. rods welded to diamond shape 75mm centers both ways. | $m^2$ | 4,719 |
| | **LANDSCAPING** | | |
| | **Laying turf sods** | | |
| X014 | Supplying & laying turf sods of approved type including bedding material, pegging and watering. | $m^2$ | 801 |

| Item Code | Item Description | Unit | Basic Rate 2020 |
|---|---|---|---|
| | **Road Construction** | | |
| **X015** | Supplying and pilling approved 100mm aggregate for road construction, at site excluding hire charges. | **$m^3$** | **2,644** |
| **X016** | Supplying and pilling approved 38mm aggregate for road construction, at site excluding hire charges. | **$m^3$** | **3,132** |
| **X017** | Supplying and pilling approved 20mm aggregate for road construction, at site excluding hire charges. | **$m^3$** | **3,246** |
| **X018** | Supplying and pilling approved 12mm aggregate for road construction, at site excluding hire charges. | **$m^3$** | **3,209** |
| **X019** | Spreading ,watering & rolling 12mm aggregate including hire charges of roller.(Materials Paid Separately) | **$m^3$** | **3,044** |
| **X020** | Spreading ,watering & rolling 50mm-20mm aggregate including hire charges of roller.(Materials Paid Separately) | **$m^3$** | **3,559** |
| **X021** | Bitumen(80/100) surfacing first coat using 2Ltr/Sq.m including blinding with sand at the rate of 125 Sq.m/Cu.m. | **$m^2$** | **277** |
| **X022** | Bitumen(80/100) surfacing 2 nd subsequent coat using 1 Ltr/Sq.m including blinding at the rate of 125 Sq.m/Cu.m | **$m^2$** | **185** |
| **X023** | Emulsion /Cold bitumen (CRS-1) surface treatment 1st coat with 3.5 ltr/Sq.m including blinding with sand,@125 Sq.m/Cu.m(Manual) | **$m^2$** | **354** |
| **X024** | Emulsion /Cold bitumen (CRS-1) surface treatment subsequent coat using 0.075 ltr/Sq.m including blinding with sand,@125 Sq.m/Cu.m(Manual) | **$m^2$** | **125** |

**The End**